MacDonaldtown Electrical containment works

| From: | Aidan Cox <aidan@rjsprojects.com.au></aidan@rjsprojects.com.au> |
|--------------|---|
| То: | michael@tcqconstruction.com.au |
| Date: | Thu, 26 Sep 2019 07:59:25 +1000 |
| Attachments: | QUOTE No. T9188_MacDonaldtown Containment works.pdf (416.15 kB) |

Hi Michael,

Following our discussion yesterday and site visits, we are pleased to submit a price for MacDonaldtown buried containment works.

See attached quote for consideration.

If you wish to proceed with the works, we are in a position to commence on site next week in order to finalise all works by end October 2019.

Please do not hesitate to contact me if you have any questions.

Regards,

Aidan Cox Project Manager



E: aidan@rjsprojects.com.au M: 2 185 A: PO Box 185, Concord West 2138 W: www.rjsprojects.com.au



QUOTATION

26th September 2019 Quote No.: T9188

TCQ Construction

Ground based warning system - electrical containment

Michael,

RE: MacDonaldtown containment works

We have pleasure in submitting our quotation for your consideration as per your Tender drawing set recieved "GROUND BASED WARNING SYSTEM ELECTRICAL SERVICES" and subsequent site visits and telephone conversation. We draw your attention to our list of assumptions and exclusions also attached based on the information provided.

Our Lump Sum quotation to carry out the work is **\$454,209.10** (four hundred and fifty-four thousand and two hundred and nine dollars and ten cent) exclusive of GST.

Thank you for the opportunity to Tender on this project and we trust the above meets with your approval, however should you require further information or wish to discuss any aspect of our Tender, please to not hesitate to contact us. We look forward to your reply.

Yours sincerely,



Aidan Cox Project Manager M: 2 185 E: aidan@rjsprojects.com.au RJS Infrastructure Group Pty Ltd



Vol 13.6



QUOTATION

SCOPE OF WORKS

We understand the scope of works to include the following:

| ltem No | Description | Unit | Amount (excl. GST) |
|-----------------------|--|------|-----------------------|
| 1.1 | Buried conduit containment (circa 550 In metres along sidings 1-5) as per typical sections A and B on drawing SAP-MDC-EL-1024. | | |
| | Allowance has been made for initial service search, electromagnetic detection of all services, saw cutting of asphalt walkways, excavation of trench, supply and lay conduits, supply, place and compact bedding sand, supply and place marker tape, removal of spoil material, place and compact general fill, reinstatement 75mm layer of concrete to existing surface level. | L.S. | INCL |
| Total Subcontract Sum | | | \$454,209.10 |



Vol 13.6



QUOTATION

GENERAL TERMS OF WORK

- By accepting this quote, you agree to all of the terms and conditions listed in this document.
- This quotation is valid for 30 days from date of issue unless otherwise stated.

LIST OF ASSUMPTIONS

- Price assumes all Authority approvals for the works have been obtained and are in-place including but not limited to Council, Power authority, Sydney Trains, TfNSW or heritage authorities.
- Price is based on information provided via email.
- We assume all necessary underground search and existing underground services present within the work area are those identified on the DSS. If unknown service/s are encountered within the work area, an additional fee will apply as no allowance have been made for relocation. Additional fee will apply for any down time.
- Client to issue all necessary permits to conduct the works.
- Client to provide surveyors for works if and when required.
- Assume hi rail access is available for hi rail deliveries, if SMS-0268 requirements are followed.
- Assume laydown / storage areas is available in close proximity to hi rail pad.
- Assume hi-rail access is provided via Siding Road 1
- Assume all protection officers required to complete entire scope are provided by Client.
- We assume that all works can be carried out between of 0700 1700, Monday to Friday.
- We assume Hi Rail access will be available to a Siding Road adjacent to our work front at all times.
- •
- Allowance has been made for all permanent materials supply
- Allowance has been made for disposal of spoil material as General Solid Waste Recyclable
- 3t excavators can be used adjacent to live rail line as long as machines are fitted with slew and height restrictors and Electrical spotter is in place.

EXCLUSIONS

- Survey (set out, as-builts, pick-ups, etc).
- Supply of protection officers.
- Supply of traffic controllers.
- Non destructive excavation, allowance for hand digging around existing services only
- Dilapidation Reports or as constructed surveys.



Vol 13.6