MAIZE GROUP PTY LTD

EASY ACCESS STATION UPGRADES -ROSEVILLE STATION

Wednesday 2nd September 2020 Prepared by Maize Group Pty Ltd



Executive Summary

Maize Group is an astounding new age company which delivers traditional maintenance & construction services through an innovative & modern approach.

Our Relationship with Downer

As a current service provider through Downer on other TAP Projects, Maize Group is in the unique position of knowing TfNSW assets and which suppliers / subcontractors to engage for the provision of Building Works and any Additional Works.

Benefit to you: Minimal disruptions with Mobilisation.

Maize Group staff and contractors possess extensive knowledge of the facilities within the NSW Geographical Areas and have an excellent rapport with the Downer staff who we have worked with in the past and present.

Benefit to you: Congenial transition and minimal Mobilisation timeframe.

Our Capability, Capacity & Experience

Maize Group is a solely-owned and operated Australian company that has established an innovative, dynamic approach to the building industry. With over 17 years' experience dealing with Government clientele, we consistently produce the workmanship needed, delivering successful services through our diverse and tailored methods.

We have developed strong relationships with our business associates to create the foundations of our successful company which we can pass on to all of our clients, who are aware of our proficiency in attacking complex and difficult projects with integrity. Combined with the skill and know how that our staff and sub-contractors possess, it creates an approach to this industry that supersedes our clients' expectations.

Capability

In addition to Maize Group's Facility Management and Building Works capabilities as outlined in this document, we are fully licensed to carry out all services within the Building & Construction Sector.

Some examples are:

- General Building Works, including amenities and accessibility upgrades
- Heritage Works
- Works in Rail corridor
- Electrical
- Fire
- Hydraulic / Plumbing



• Security – CCTV and lighting

Maize Group's operations ensure a consistent communication process with our team members and clients through our service delivery model. This allows us to maintain a strong bond with our clients.

Our Services

General Building Services	Brick and Block Work Car Park Maintenance Carpentry Ceiling Repairs Concreting Fencing Floor and Wall Tiling Heritage Works Gate & Grille Repairs	Glazing Grounds Maintenance Line Marking Patch & Painting Roof & Gutters Repairs Rubbish Removals Waterproofing Structural Works Workstations
Electrical	install across a broad section of ap to provide rapid and efficient servi breakdown maintenance.	undertakes all maintenance and new oplications. This department is geared ice covering any preventative and
	Building Management Control System Generators Lighting & Power	Lighting Controls Switchboards Testing & Tagging
Security		access control, video surveillance, oducts and services means we can your premises.
	Back to base monitoring Building Access Control including Honeywell Prowatch access control CCTV Systems Security Alarm Systems	Design and Installation Door and lift integration Intercom Systems Testing & maintenance Vehicle access control
Hydraulic	Cold / hot water services Downpipes – roof, balcony, planter outlets Existing sewer & water main connections and diversions Gas services In-ground sewer & trade waste drainage	Installation of sewer and water mains Intercom Systems Sanitary plumbing Sewer / sub-soil pump-out pits

Capacity

Our team of professionals are highly qualified to provide services in all fields of construction and have experience working on projects in a wide variety of industries, including healthcare, housing, transport, government and education.



Experience

The foundations of Maize Group have been developed by our strong relationships with our business associates, including our clients, suppliers, contractors and employees. With the knowledge and determination that our staff and contractors possess, Maize Group has created a unique approach to the construction industry that supersedes our clients' expectations.

Client Testimonials



"A class above the rest! Maize Group have been wonderful to work with as they look after our clients' homes with all sorts of maintenance, renovations and expert knowledge. Cannot see us using anyone else"

Steven Josevski RiverBank Real Estate Managing Partner & Senior Consultant



"I write this letter in recommendation of Mal Helweh- Maize Group as lead building fabric contractor at Waratah Private Hospital- Hurstville.

I had the pleasure of working with Mal within the building, performing planned maintenance, reactive maintenance and minor/major building works."

"I can recommend him highly and without reservation. Throughout the entire course of the approximate two years Mal has worked within the building he was a consummate professional. He was accurate in his initial assessment of works and always delivered a high level and quality service."



Rebecca Carlson LEIGHTON CONTRACTORS PTY LTD





"Construction and its ever changing environment can be very challenging, fast paced and dynamic to work in. It was through my experience working with Mal that made our job run efficiently and conquer these challenges. It was refreshing as a site supervisor to be able to interact with such a proactive and well organised person who always showed a can do attitude towards the job and managed to fulfil, above expectation, all client requests. Mal was professional, punctual and showed that he has broad knowledge of the industry. It was through my experience that I could see

that Mal would definitely go above and beyond for his clients. I would recommend Mal as someone to work with, without hesitation and I look forward to being able to work with him again in the near future."

Rebecca Gerantonis Projects Administrator SYDNEY AIRPORT

"Maize Group is a very client- focused business. We are a very fast paced company and the way the team at Maize reacts and adapts to a project plan is first class.

It's pretty simple, they make it happen without a fuss. To deal with all sorts of clients from Body Corporates to Department of Housing, is no small feat. The team get along really well and create a high level of rapport. Great work, pleasure as always!"

Belal Derbas Programmed Facility Management Manager





Maize Group has a sound track record of project delivery within agreed time and budget parameters. As well as our company, our Director has also accomplished major works in a wide range of market sectors and industries, including:

Health	
	e Hospital Jing Maintenance & Security Controls contract iple Fitouts below \$100k
Education Cam	puses
\$4M \$1M \$400 \$400 \$200	Inspire Centre Refectory Refurbishment Faculties/Disabilities Floor DK Deputy Vice Chancellor Fit-Out DK Café/Kitchen DK Toilet Upgrades DK Roof Restoration
Commercial, Re	etail & Industrial
Sydney Water P NSW State Arch Australian Fede HQ •	ding Maintenance contracts with BroadSpectrum (AMS LAHC Works) Programmed Ventia Jones Lang LaSalle Pump House Refurbishments ives Kingswood – Building Works Package \$650k
Transport	
\$4.5 \$2M \$2M \$400	T1 Pier C redevelopment M Virgin Blue baggage loop T1 Paving Upgrade (Approximately 5000m²) ID & Access Fitout OK T2 Virgin Check-In Counter Upgrade Ok Station Building Works - \$550k









E19-1595-AS-02-279-PR-0001







. 5G EB

Text Message 3 May 2016 at 11:30 am

Hey bro it's Mal, can I get a contact off you for a demo company? My guy is charging me too much, need another price. Thanks

Hey Mal, I use Nustas, the guys name is: Edmund nustas Mobile

17 Oct 2018 at 11:57 am

Des 0040 -+ 0/15

Hey bro,

How's it going? I'm still working on the SYDNEY trains tender (it's killing me). Nearly finished, just wanted to see if you have the following; - RISK MANAGEMENT PLAN - PROJECT MANAGEMENT PLAN Would you reckon you have them?

7

Vol 26.1

0.



Sorry Mal, just saw this message now. Yes, I have both. What's your email, I'll send them to you

No worries bro

It's mal@maizegroup.com.au

They're going to be in a Downer format. Is that ok? I got them from a mate who works there

> Yeah bro that's fine. I'll work on them tomorrow. Are you going for the panel too?

> > It's a long tender lol

Yeh I'll be going for it too. It is long but they've extended the deadline 4 times. They mustn't be getting enough responses

Good thing about those downer plans is that there made for rail anyway. So should be an easy fix, I'll work on them tomorrow

0.



E19-1595-AS-02-279-PR-0001







1 5G ER

Yeah I noticed. You going for all the trades up to 250k? I am but also for building and construction up to 1M (or 5, can't remember the Tier 2 category)

Ahhh mad

Tier 2 is up to 1m, at the briefing they don't have much work for tier 3 (5m) and they said even of you go for tier 1, if you perform they'll bump you to tier 2 or 3

I'll go for 2

Ahh ok. Yeah I read that you can jump up which is good. At least you get the feel of it for the first few months then you know how to work with them

18 Oct 2018 at 1:57 pm

Do you have a fatigue management plan?

Yeah. You want me to send it?

9

Vol 26.1



Fatigue Management Plan

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	Andrew Gayed <agayed86@< th=""></agayed86@<>
Date:	Thu, 18 Oct 2018 14:16:58 +1100
Attachments:	Maize Group Fatigue Management Plan.docx (55.41 kB)

Regards, Mal Helweh



Phone: (02) 9773 1027

Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.



1. PURPOSE

To identify, capture and put into place adequate controls to manage risk associated with factors that directly (or indirectly) contribute to fatigue within the workplace environments and minimise these risks on the Dulwich Hill - Refurbishment of Pressure Tunnel Valve Houses project. This is to include motor vehicle travel before and after rostered shifts. It is fact that excessive fatigue can have a significant impact upon the performance, health and well-being of workers. Impairment associated with fatigue has potential to result in serious incidents and accidents.

2. SCOPE

This plan defines the management strategies and expectations that will be used to manage fatigue related risks within Maize Group operations on the Dulwich Hill - Refurbishment of Pressure Tunnel Valve Houses project.

In situations where other than normal circumstances prevent compliance to this plan, workers must advise their supervisor / manager, and the risk associated with fatigue shall be controlled before work can resume.

All employees/ workers must be involved implementing the fatigue management plan and making sure it is followed. Review of the Fatigue Risk Management Plan (FRMP) will be undertaken annually with due consultation with the work teams and Safety Team.

3. PROCEDURE

3.1 Hours of Work

Maize Group follows the below planned roster to meet with our business needs on the Dulwich Hill -Refurbishment of Pressure Tunnel Valve Houses project.

• All staff > 5 days on shift, followed by 2 days off

3.2 Type of Work

3.2.1. Dulwich Hill Arrangements

On the Dulwich Hill Project Maize Group typically perform works and deliver services under contract arrangements and conditions.

Works Include: -

- Admin
- General Building works such as; carpentry, roofing, painting
- Remediation works to Heritage building
- Scaffolding
- Sourcing materials as per specifications
- Workshop activities

3.3 Employee Responsibilities

It is the responsibility of all employees to comply with this plan. All employees will receive fatigue management awareness training by Maize Group and the Site Safety Induction, Pre-start Safety meetings and regular Safety Toolbox Roll-outs. Awareness and refresher training will also include the actions and controls an employee shall adopt to ensure Fitness for Work (FFW) and to minimise the risk of fatigue within the workplace.

Dulwich Hill – Refurbishment of Pressure Tunnel Valve Houses **FATIGUE MANAGEMENT PLAN**



All employees are required to attend work fit to safely perform their duties without risk to themselves or others. This can only be managed from a personal perspective by ensuring that an individual's time away from work includes enough sleep and recovery. This will include amongst other things employees managing any health, lifestyle, personal or family responsibilities that may impact on their fatigue.

Employees must:

- Present to work in a fit condition and not adversely affected by fatigue;
- Utilise breaks provided within and between shifts to rest and recuperate;
- Report all incidents and accidents arising from hazards associated with shift work;
- Recognise signs of sleep deprivation and/or fatigue and the impact on themselves and others and report to their supervisor the circumstances in which fatigue and lack of sleep are impacting on individual wellbeing and workplace safety;
- Understand the implications of voluntarily seeking additional work hours, including secondary employment, that have the potential to increase risks to individual and organisational health and safety; and
- Ensure your allocated shifts comply with this plan.

3.4 Fatigue Management

Fatigue has been identified within Maize Groups Hazard Register. Control strategies have been implemented accordingly.

Where it is likely fatigue related risk will impact upon work, the following examples of control strategies should be considered for implementation. However, control strategies that may be implemented during work periods, shall be discussed and agreed upon by the relevant Supervisor.

- Regular scheduled rest breaks.
- Must take scheduled breaks during the day.
- Working in pairs or groups as the task may demand.
- Regular check-ins.
- Provision of adequate and appropriate PPE
- Providing the employee with transport home if there is risk of worker fatigue (eg –exceeding 14 hours worked or if the person is unwell)

Different situations may require certain control strategies, these should be discussed and agreed upon by the Supervisor in due consultation with the work team and or HSE representatives.

Maize Group employees are encouraged to be proactive in the management of fatigue and to report incidents of fatigue. Supervisors will maintain a record of these reports and a regular review will be conducted to identify trends or specific risk factor and additional controls will be implemented as may be necessary to reduce the risk of fatigue.

3.5 Driving and Travel

Fatigue slows a driver's reaction time and affects their scanning ability and information processing skills.

Workers driving vehicles to and from work or for long periods of their working day should:

- plan any driving or travel well in advance
- avoid driving after being awake for a continuous period of 17 hours

Dulwich Hill – Refurbishment of Pressure Tunnel Valve Houses **FATIGUE MANAGEMENT PLAN**



- avoid driving if they have not accumulated more than five hours sleep in the previous 24 hours or 12 hours sleep in the previous 48 hours
- avoid driving for more than 8-10 hours in any one day
- ensure adequate sleep the night before a long journey
- share driving where possible
- take a rest break from driving of at least 10 minutes every two hours or more frequently if feeling tired
- if concerned about the fatigue risks, consider arranging an alternative method of transport and/or accommodation.

It is important to note that these methods only have an effect for approximately 15 minutes. Therefore, whenever a worker is driving a vehicle and begins to feel fatigued or consider that they are at risk of falling asleep, turning up the radio or relying on cold air should only be used as a method to stay awake until they find a safe place to pull over and rest.

	Operational staff	Admin staff
Maximum normal shift length	8 hours	8 hours
Maximum working time per 24 hour period including handovers and travel time	14 hours (authorisation must be granted for any hours worked >12 by supervisor)	14 hours (authorisation must be granted for any hours worked >12 by managing director)
Maximum number of consecutive shifts	6	6
Start time days shift	6-8.30am	6-8.30am
Minimum rest period between shifts	10 hours	10 hours
Travel time and work time exceeds 14 hours	Cannot operate company or personal vehicle /machinery after 14 hrs	Cannot operate company or personal vehicle /machinery after 14 hrs

Appendix 1 – SUMMARY OF WORKING HOURS AND TRAVEL TIME REQUIREMENTS

Fwd: Vendor Creation - Mansion Building

From:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
To:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
Date:	Thu, 21 Mar 2019 18:47:07 +1100
Attachments:	Unnamed Attachment (68 bytes); Unnamed Attachment (68 bytes); image004.png (11.3 kB)

-------Forwarded message -------From: AMSVendor <<u>AMSVendor@broadspectrum.com</u>> Date: Wed., 20 Mar. 2019, 3:40 pm Subject: Vendor Creation - Mansion Building To: andrew@mansionbuilding.com.au <andrew@mansionbuilding.com.au>

To: <u>andrew@mansionbuilding.com.au <andrew@mansionbuilding.com.au></u> Cc: AMSVendor <<u>AMSVendor@broadspectrum.com</u>>, Chandler, Brian <<u>Brian.Chandler@broadspectrum.com</u>>

Good Afternoon,

Thank you for previous application of interest for works on the LAHC AMS contract.

We have approved the progression of your application, and wish to begin assessing your documentation, pricing, and start the creation process of your account in our system.

Please find attached our Contract Documents and New Vendor Creation forms.

The attached documents below are to be completed and returned in order for us to progress your application.

- New Vendor Creation Form (Pages 3-5)
- Agreement to Issue RCTI
- Subcontractor_Supplier Assessment Checklist
- AMS Particulars (Areas Categories Services)
- AMS Price Schedule

Along with a copy of the specified documentation below:

- Banking documentation to be one of the following:
 - Encoded deposit slip or bank statement,
 - Company letter head with ABN/GST# and bank details signed by an authorised signatory
 - OR Recent invoice with bank details specified

- Signed letter with legal/trading name, ABN, address and contact details with your company letterhead

- Workers Comp Insurance / Personal Accident or Injury / Income Protection

- Public Liability Insurance
- Third Party Motor Vehicle Insurance

As discussed with Brian today, please find below base pricing for asbestos codes yet to be added to our SOR book. Please refer to the below when pricing for asbestos/hazardous services.

SOR Item	Short Description	Long Description	Units of Measure	Prices (E Effective
MIN14020	Proud patch external / internal fibrous cement wall - make safe. Hole size or sizes up to 1m2	Proud patch hazardous material external wall cladding (fibrous cement). Code is claimed as a make safe and scope and quote to be provided if component is not to Asset Performance Standards. Broken Hazardous materials to be removed from site and area cleaned.	Item.	\$ 84.00
MIN14960	(Technical inspect dwelling and take action on hazardous substances and make safe and seek direction.)	Undertake a visual inspection (technical inspection) of a dwelling for hazardous substances. Identify hazard, undertake urgent action to make safe and seek further direction. If the hazardous substance is to remain inform residents of nature of the work and any precautions to be followed. Erect warning signs and labels as appropriate. (May be claimed with MIN15040 or MIN14020 where required) Cannot be claimed with SCP0007	Dwel.	\$ 91.00
MIN14970	Develop and implement control systems for any maintenance work on hazardous substances over 10m2 (Includes all permits and submission of Safe Work NSW notifications)	Review hazardous substances report (SCP0007) and develop control systems for maintenance work. Prepare appropriate Safe Work Method Statements, obtain permits to work including Safe Work NSW notifications, Waste Locate and provision of consignment number. Provide guidance to Principal on tenant relocation. Induct staff and ensure control measures are implemented. For hazardous substances over 10 m ² . May be claimed with SCP0007 where required, (Report to be provided)	Dwel.	\$ 137.00
MIN15000	Removal & disposal of asbestos cement sheeting over 10m2 to 50m2 in one room	Removal and disposal of asbestos cement sheeting for internal Asbestos over 10m ² to 50m2 in one room (May claim MIN 14970, SCP0007, SCP0008 in combination if required. (Evidence to be provided on claim)	Room.	\$ 1,240.0
MIN15005	(Supply and fix warning label 'sticker; to electric Meter box. – 'Warning – Asbestos Switchboard Panel')	Supply and fix warning label (weatherproof) 'sticker' to electric meter box in accordance with Work Safe NSW . – 'Warning – Asbestos Switchboard Panel'. Item can be claimed in combination with MIN15010.	Each.	\$ 14.00
MIN15010	(Vacuum and dispose of Asbestos dust after drilling)	Vacuum and dispose of Asbestos dust inside after drilling in accordance with Work Safe NSW. Item includes an allowance to comply with the regulations for the personal protection of workers in the removal of asbestos dust including advising of tenants. Item cannot be claimed in combination with MIN14970, MIN15000, MIN15020, MIN15030 or SCP0007.	Dwel.	\$ 57.00
MIN15020	Removal and Disposal of asbestos cement product up to and including 4m ² (Internal & External)	Removal and disposal of asbestos cement product up to and including 4m ² only. Includes all legislative, PPE, disposal, reporting & safety requirements. (Internal & External) Under 1m2 of loose asbestos MIN15090 to be used.	Each.	\$ 557.00
MIN15060	Additional removal per m2 for disposal of asbestos cement product over 4m2 up to 10m2 (Internal & External)	Additional removal and disposal of asbestos cement product per m2, over4m ² up to 10m2 (Internal & external) Includes all legislative, PPE, disposal, repor ting & safety requirements.	Each.	\$ 64.70
MIN15090	Loose asbestos, Collection and disposal up to 1m2 or equivalent in smaller pieces	Collection of loose asbestos piece or pieces to the equivalent of 1m2. Includes collection and disposal and all safety requirements. Code can only be claimed once per order. Over 1m2 MIN15020 to be used. For large areas contaminated by small pieces and for soil removal a site specific quote is to be provided.	Each.	\$ 120.00
MIN15030	(Removal and disposal of asbestos cement product over 10m2 and less than 30m2 – external areas only)	Removal and disposal of Exterior Asbestos cement product over 10m2 and less than 30m2. Under 10m2 use MIN15020 or MIN15000 for Internal areas. NOTE: Any measurement of Asbestos over 30m2 provide quote for removal. Can claim MIN14970, SCP0007, SCP0008 in combination.	m2.	\$ 64.70
MIN15040	Make safe friable asbestos / spray	Make safe friable asbestos / spray contaminated area with PVA up to 50m2 (Internal & External).	50m2.	\$ 273.00

	contaminated area with PVA up to 50m2	PVA solution is to include coloured dye for visual identification, code co. Ets. 9411595#AS#2#279-1	R-0001	
MIN15070	Air monitoring, Weekly supply of 4 pumps and report only, cannot be claimed with removal codes	Weekly rate for supply of up to 4 air monitoring pumps, report of monitoring results to be provided with claim. Code cannot be claimed in addition to SCP0008, MIN15030, MIN15000	Each.	\$ 450.00
MIN15080	Air monitoring, Weekly supply of additional pump and report only, cannot be claimed with removal codes	Weekly rate for supply of 1 additional air monitoring pump, report of monitoring results to be provided with claim. Code cannot be claimed in addition to SCP0008, MIN15030, MIN15000	Each.	\$ 75.00
SCP0006	Asbestos sampling - additional samples	Asbestos sampling per additional sample, Code includes copy of report on test result. May be claimed with SCP0007	Each.	\$ 40.00
SCP0007	Inspect, Identify, test and provide detailed Report on hazardous substances (Asbestos removal over 10m2)	Undertake an inspection to identify and report on hazardous substances. Report must contain details on location, types and condition of hazardous substances. Report should contain a risk assessment, test results of any air monitoring and control measures. Control measures must contain a scope of works and measures to handle hazardous substances based upon the level of the risk assessment. Item can only be claimed following Principal's approval.	Dwel.	\$ 220.00
SCP0008	Monitor and report removal of hazardous substances over 10m2 including clearance certificate	Undertake clearance monitoring of the work involving hazardous substances and issue clearance certificate. Clearance monitoring will involve visual inspections to ensure work is carried out in accordance with control systems. Carry out monitoring and testing while work is carried out and at the completion of all work. Prepare a report at the end of work and advise the Principal that the dwelling is habitable and hazardous substances are removed or controlled. Includes cost of independent test analysis and issue of clearance certificate at the end of work. For removal of hazardous substances over 10 m ² . Item can only be claimed following Principal's approval. (May be claimed with MIN15030, MIN15000, Cannot be claimed with MIN15020)	Dwel.	\$1,000.0

Kind regards,

Subcontractor Management Team | NSW LAHC Contract

Description: Adobe Systems	

D 1300 913 950 Option 3

W <u>www.broadspectrum.com</u>

Consider the environment and 'think $\ensuremath{\textit{before}}$ you print'

"This email and any attachments are confidential and are for the intended addressee[s] only. Unauthorised use of this communication is prohibited. If you have received this communication in error, please notify the sender and remove them from your system. Confidentiality is not waived or lost by reason of the mistaken delivery to you. Before opening or using any attachments, it is your responsibility to check them for viruses and defects." Thank You.

Fwd: Mansion Building - Area 3 Works

From:Andrew Gayed <andrew@mansionbuilding.com.au>To:Mal Helweh <mal@maizegroup.com.au>Date:Thu, 20 Feb 2020 09:43:35 +1100

FYI - Iol

------Forwarded message ------From: AMSVendor <<u>AMSVendor@broadspectrum.com</u>> Date: Thu., 20 Feb. 2020, 9:26 am Subject: RE: Mansion Building - Area 3 Works To: Andrew Gayed <<u>andrew@mansionbuilding.com.au</u>> Cc: AMSVendor <<u>AMSVendor@broadspectrum.com</u>>

Good Afternoon,

Thank you for the submission and updated areas.

We currently don't have any requirement for additional services this area.

Kind regards,

Benjamin Manzi

Subcontractor Coordinator | NSW LAHC Contract

D 1300 913 950 Option 3

W www.broadspectrum.com

From: AMSVendor Sent: Thursday, November 21, 2019 4:44 PM To: Andrew Gayed <<u>andrew@mansionbuilding.com.au</u>> Cc: AMSVendor <<u>AMSVendor@broadspectrum.com</u>> Subject: RE: Mansion Building - Area 3 Works

Good Afternoon,

You can assist them with their induction uploads, just not the other modules.

Ensure they're using the correct login page:

To log in: http://broadspectrum.interactiontraining.net/central/

Create users: http://broadspectrum.interactiontraining.net/Registration/Default.aspx

I will submit your updated pricing for review.

Kind regards,

Benjamin Manzi

Subcontractor Coordinator | NSW LAHC Contract

D 1300 913 950 Option 3

W <u>www.broadspectrum.com</u>

From: Andrew Gayed [mailto:andrew@mansionbuilding.com.au] Sent: Thursday, November 21, 2019 3:39 PM To: AMSVendor <<u>AMSVendor@broadspectrum.com</u>> Subject: Re: Mansion Building - Area 3 Works

Good afternoon Ben

An update to all areas.

Also, some of my workers are having difficulty uploading their information, is there any way I can upload it for them?

Regards

Andrew

On Thu., 21 Nov. 2019, 3:31 pm AMSVendor, <<u>AMSVendor@broadspectrum.com</u>> wrote:

Good Afternoon!

Could I please confirm if this is an update to all areas or just area 3?

Kind regards,

Benjamin Manzi

Subcontractor Coordinator | NSW LAHC Contract

D 1300 913 950 Option 3

W <u>www.broadspectrum.com</u>

From: Andrew Gayed [mailto:<u>andrew@mansionbuilding.com.au]</u> Sent: Thursday, November 21, 2019 12:05 PM To: AMSVendor <<u>AMSVendor@broadspectrum.com</u>> Subject: Mansion Building - Area 3 Works

Hi Ben,

Please see attached Particulars and Price Schedule for Area 3 works.

Regards,

Andrew Gayed

Mansion Building Pty Ltd

P: (02) 9606 6206

M: 0 815

E: andrew@mansionbuilding.com.au

Mansion Building

From:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
То:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>

Date: Wed, 06 May 2020 14:24:50 +1000

Hi Mal


As discussed, we are ready, willing and able to commence work with Broad-spectrum on the LAHC contract.

We are prepared to work in any area.

Our AMS vendor number 2000048286.

Please let me know if you require any information.

Kind regards Andrew





E19-1595-AS-2-279-PR-0001








1 5G ER





21 Nov 2019 at 7:50 am

Is that done in the connect website? Where the work orders are managed?

21 Nov 2019 at 10:17 am

Nah it's through AMS Vendor

Email them (Ben Manzi) the Areas Sheet with Area 3 filled out

In a meeting, I'll call you back

11 Dec 2019 at 11:42 am

Message

Vol 26.1

 \mathbf{O}



I'll call you back.

1 May 2020 at 11:29 am


iade.io

(a)


7/117 Stoddart St Roselands

15 May 2020 at 7:11 am





Vol 26.1







E19-1595-AS-2-279-PR-0001









Kim Thanh NGUYEN, BE MES

Assistant Category Officer | Construction

Public Works Advisory | Department of Regional NSW

T 02 9240 8798 | F

kim.nguyen@finance.nsw.gov.au

27 Jul 2020 at 4:48 pm

Hey bro,

I got the estimate back for the service building for the Metro. Full BBOQ with rates are \$10,500 plus GST and another \$3000 (by another company) for the station (not all works).

Reckon it's worth the outlay?

I'm thinking to call Reza and ask for a weeks extension. If so, I might do it

Vol 26.1

0.




E19-1595-AS-2-279-PR-0001

1 5G ER







If you spend that money for an EOI, they'll still squeeze you down if they win the job

And that's why you're on the big bucks haha. Thanks bro.

They sent me a BOQ today, I'll just get the estimators to put rates in and see what it comes to

28 Jul 2020 at 10:47 am

Hey bro, have you spoken to Mark? If not that's ok, I'll call Him but before I do, just wanted to see if you told him I'm alright to speak about what we discussed the other night

27

Hey Mal, I'm so sorry I haven't gotten a chance to call him. I've discussed with him what we spoke about, you can talk freely

Message

0.



I'm in a meeting, I'll call you back.

17 Sep 2020 at 12:14 pm


I'm in a meeting, I'll call you back.

2 things; Proffessional Indemnity - Can I exclude this? Limitation Of Liability - it states 200% of contract. Can I exclude this?

Yes to both

0.













E19-1595-AS-2-279-PR-0001





. 5G GB



Expect a call from Haslin for a building package

4 Aug 2021 at 7:32 am



24 Nov 2021 at 5:58 pm

You missed a call, but the caller didn't leave a message.

> iMessage 25 Nov 2021 at 7:56 pm

> > Hey bro, <u>8am</u> Grained in Revesby or Heights Cafe at Revesby Heights?

Grained is probably nicer but your call

25 Nov 2021 at 8:58 pm

Sorry bro, got called into spotless at Narellan at <u>9am</u>. Can we do Monday instead?

Vol 26.1

0.

Glenbrook Station BOQ

From:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
То:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
Date:	Tue, 16 Apr 2019 10:26:18 +1000
Attachments:	Glenbrook - Building BOQ.xlsx (133.79 kB)

Hi Mal,

Please see attached as discussed. Apologies, actual budget is approx. \$330k, I've highlighted it in yellow for you.

Cheers

Andrew Gayed Mansion Building Pty Ltd P: (02) 9606 6206 M: 0 815 E: andrew@mansionbuilding.com.au

Level Bill Code Cod	e. Bill Code Description.	Jask code Co	ode. Task code Description.	Bill description.	Unit Bill Quantit	× 1	iet Rate.	Resource Net Amount Works Resource	code Resources on Price code heets Worksheets Resource Cost	Resources on Price code Worksheets Resource Code*	Bessurces on Price code Worksheets Resource Descriptio	Terources on Price code Worksheets Resource Unit	Besources on Price code Worksheets Bill Net usage*	Resources on Price code Worksheets Resource Final	Besources on Price code Worksheets Bill Net omsunt
								<u>co</u>			-				
1				1AP3 - Easy Access Station Upgrade (Glenbrook Station)				11,245,426.13							
2				Freiminaries & Design Fees - Lump Sum Freiminaries Fees				4,473,932.21							
4				Core Management Costs (Lump Sum)				1,321,406.01							
5				Downer Project Management				1,110,064.88							
90	Contractors Lump Sum	1101	Staff & Indirect Labour - gene	Downer Core Management Staff Costs (Stage 1 - Target Budget Estimate)	item		,	iot priced							
90	Contractors Lump Sum	1101	Staff & Indirect Labour - gene	Downer Care Management Staff Costs (Stage 2 - Construction Phase)	item		1,110,064.88	1,110,064.88 6053	Staff Salaries	LCM1002h	Project Director	/mtx	588	242.66	142,684.08
								6053 6053 6053	Staff Salaries Staff Salaries Staff Salaries	LCM1006h LCM1015h LCM1016h	Construction Manager Engineering Manager Design Manager	/mbr /mbr /mbr	588 594	209.19 125.51	123,003.72 74,552.94
								6053 6053	Stoff Solories Stoff Solories	LCM1227h LCM1404h LCM1408h	Graduate Engineer (Assurance) Salety Advisor	/mtv /mtv	936 1,000 500	61.59 85.35	57,648.24
								6053 6053 6053	Staff Salaries Staff Salaries Staff Salaries	LCM1408h LCM1416h LCM1601h	Erviconmental Advisor Quality Systems Assurance Mana Commercial Manager	/mtv ge /mtv	500 471 536	75.31 92.04 209.19	43.350.84
								6053 6053	Staff Salaries Staff Salaries	LCM1402h LCM1402j LCM1403h	Contract Administrator Senior Contract Administrator	/entr /entr	588 588 568	88.69 128.86	52,149.72 75,749.68
								6053 6053 6053	Staff Salaries Staff Salaries Staff Salaries	LCM1403h LCM1405h LCM1405h	Planning Manager Scheduler Bid/Risk Manager	/mbu /mbu /mbu	568	112.13	63,689.84
								6053 6053	Staff Salaries Staff Salaries	LCM1407h LCM1408h LCM3801h	Quantity Surveyor Estimator Document Controller	/mtv /mtv	102	128.86 209.19	
								6053 6053 6053	Staff Salaries Staff Salaries Staff Salaries	LCM3801h LCM3802h LCM3804h	Document Controller General Admin/Reception Cost Clerk/Accounts/PA/Genera	/mtv /mtv IA /mtv	588 588 1,274	43.51 33.47 43.51	25,583.88 19,680.36 55,431.74
								4053 4053 4053	Staff Salaries Staff Salaries Staff Salaries	LCM3814e LCM3814h LCM3815h	Communication & Stakeholder M Communication & Stakeholder C Procurement Officer	ar /mhr	204 500 588	155.64 88.69 88.69	31,750.56
								6552	Travel & Accommodation	LCM5004	Accommodation including food	/day	200	250	
90	Contractors Lump Sum	1201	Facilities/Office Establishmen	Downer Preliminaries Head Office Setup Costs	item	1	18,750.00	211,341.13 18,750.00 4098	Office Costs	IC10112	Setting Up office	/m2	125	100	12,500.00
80	Contractors Lump Sum	1205	Project Office	Head Office Rental Casts at North	item			4202 Rot priced	Material	IC10501	Site Furniture	/item		25,000.00	4,250.00
				Sydney/Paramatta (Stage 1 - Target Budget Estimate)											
90	Contractors Lump Sum	1205	Project Office	Head Office Rental Costs at North Sydney/Paramatta (Stage 2 - Construction	item	1	108,844.09	108,844.09 6098	Office Costs	IC201016	Head Office Rental (\$480/m2 @ 5	00 /wk	18	4,615.00	83,070.00
				Phase)				6098 6098	Office Costs Office Costs	IC21117 IC21141	Consumables for Head Office	/wk	18	250	4,500.00
								4098 4098 4098	Office Costs Office Costs Office Costs	IC21141 IC21143 IC21547	Office Running Cost (\$50/m2 @ 5 Office Outgoings Cost (\$75/m2 @ Rental of Carpark Space	50 /wk 51 /wk /ea/m	18 42	480 720 200	12,960.00 8,314.09
90	Contractors Lump Sum	1310	Site Services	Head Office II Equipment at North Sydney/Paramatta	item	1	83,747.04	83,747.04 6411	r	IC10704a	If Setup Cost (1xHQ plus 4xSites)	/item		124,415.52	
				-, unwyr unurddiid				6411 6411	а а	IC10733 IC21320a	Set up Teambinder If Monthly Cost (1xHQ plus 4dilter	/bem) /mth	3	4,500.00 20,714.20	
								6411 6411	а а	IC21332 IC21333	Running Cost for Teambinder License Pees for Envision (\$750/m	/mth I C /sum	3 2,813	1,080.00	3.240.00 2.812.50
4	Contraction from the first	1092	Other Fees and charges	Insurances & Levies (Lump Sum) Long Service Levy	item	1	42,000.00	183,000.00 42,000.00 6671	Insurances/Permits/Licences	IC50110a	Long Service Levy	/ðem	42,000	1	42,000.00
90	Contractors Lump Sum	1092	Other Fees and charges	Long Service Levy Insurances and Bank Guarantees	item		42,000.00	141,000.00 4471	Insurances/Permits/Licences	IC50104a	Work Insurance	/item	120,000	1	120,000.00
4				Sile Management Costs (Lump Sum)				6622 1,494,121.95	Bank Guarenhees	IC50108a	Bank Guarantees	/item	21,000	1	21,000.00
5				Downer Project Management				1,152,634.40							
90	Contractors Lump Sum	1101	Staff & Indirect Labour - gene	Site Delivery Team (Stage 1 - Target Budget Estimate)	item		,	iot priced							
90	Contractors Lump Sum	1101	Staff & Indirect Labour - gene	Site Delivery Team (Stage 2 - Construction Phase)	item	1 1	1,152,634.40	1,152,634.40 6053	Staff Salaries	LCM1004	Project Manager (Glenbrook)	/mite	2,600	179.07	
								6053 6053 6053	Staff Salaries Staff Salaries Staff Salaries	LCM1210i LCM1211i LCM1216i	Project Engineer (Glenbrook) Senior Project Engineer (Glenbro Site Engineer (Glenbrook)	/mtv sk) /mtv /mtv	2,520	108.78 108.78 61.59	274,125.60 155,206.80
								4053 4552	Staff Salaries Travel & Accommodation	LCM1218i LCM5004	Supervisor (Glenbrook) Accommodation including food	/mtx /day	2,000	128.86 250	257,720.00
5				Downer Preliminaries				341,487.55							
90	Contractors Lump Sum	1015	Mobilisation & Demobilisation	Mobilise/Demobilise Downer Site Offices	item	1	159,957.10	159,957.10 4052 4382 4382	Labour Wages Equipment Cost Equipment Cost	LCB1002 PCH1210 PCH2206	Labour-CW3 Excavator 201 Grader 14H	/mkv /tx /tx	25 13 13	69 120.2 180.3	1,502.50
								6382 6382	Equipment Cost Equipment Cost	PCH2604 PCH2812	Water Carl 12,000L Pad Foot Roller 127	/tx /tx	13	100	1,250.00
								6202 6302 6098	Material Subcontract Uncommitted Office Costs	MC10302 SC10116a IC10106a	Gravel Type DGS 20 Carl & Dispose of GSW-Recycle Establish Site Shed (SO,LS,A8,Tank	/ton /ton	949 825	27.5 40.8 14,740.00	50,140.00
								6382 6098	Equipment Cost Office Costs	IC10106b IC10107a	Delivery Charges for estabishmen Diestabish Site Shed (SO LS A8.To	/ /each nki /each		10,704.39 4,933.33	10,704.39 4,933.33
								4382 6454 6454	Equipment Cost Utilities Utilities	IC101075 IC10306 IC10306g	Pickup Charges for disestablishm Connecting of utilities Disconnecting of utilities	/kem /kem	1	10,904.33 5,000.00 5,000.00	5,000.00
								6382 6382	Equipment Cost Equipment Cost	IC30102c IC30102d	Transport Shed to Site Transport Shed from Site	/each /each	3	2,376.00 2,446.91	7,128.00 7,340.73
								4382 4382 4382	Equipment Cost Equipment Cost Equipment Cost	IC30103a IC30103b IC30105a	Transport Lunchroom to site Transport Lunchroom from site Transport to site	/each /each /each	1	792 815.64 391.34	815.64
	Confection Lump Sum							6382	Equipment Cost	IC30105b	Transport from site	/each	5	403.02	2,015.10
90	Contractors Lump Sum	1205	Project Office	Downer Facilities Hire for Site Offices	item	1	107,955.10	107,955.10 4098 4098 4098	Office Costs Office Costs Office Costs	IC20102 IC20104 IC20106a	Site Office 12.0x9.0m Lunch Room 12.0x3.0m Ablution male/Female	/mith /mith /mith	33 11 11	2,121.30 535.8 771.3	5,893.80 8,454.30
								6098 6098 6098	Office Costs Office Costs Office Costs	IC20108 IC20112 IC20116	Waste Tank 4,000L Container hire (20ff) Strange Container Hire 3 0r2 4M	/mith /mith /mith	11 22	342.9 124.2 115.8	3.771.90 2.732.40 1.273.80
								6454 6454	Utilities	IC20706 IC20906a	Storage Container Hire 3.0x2.4M Town Water Supply Rates Waste pump outs plus travelling	/KL /each	3,520 22	2.3 350	8,096.00
90	Contractors Lump Sum	1310	Site Services	Computer and IT facilities for Site Team	item	1	,	iot priced							
90	Contractors Lump Sum	1315	Facilities Maintenance Costs	Site Running Costs	item	1	41,676.25	41,676.25 6454 6098 6098	Utilities Office Costs Office Costs	IC20307 IC21112 IC21116	Site Bectricity Stationary Expenses Consumables for kitchens	/wk /Mbi /wk	48 48 48	225 100 300	10,714,75 4,763,00 14,289,00
								6098	Office Costs	IC21124	Cleaning of Sile Compound	/wk	48	250	11,907.50
90	Contractors Lump Sum	1205	Project Office	Site Furniture	item	1	8,100.00	8,100.00 6202 6202 6202	Material Material Material	IC10502 IC10504 IC10506	Office desk Office Chains Under Desk Drawer	/each /each /each		250 120 100	
								6202 6202	Material Material	IC10508 IC10510	Tressle Eating Table Mastic Chair	/each /each		130	
								6202 6202 6202	Material Material Material	IC10512 IC10514 IC10516	20 person meeting table Meeting room chair Book Case	/each /each /each		2,100.00 220 90	
								6202 6382	Material Equipment Cost	IC10518 IC10520	fire Extinguisher Ice Machine	/each /each	10	150 5,100.00	5,100.00
90	Contractors Lump Sum	1315	Facilities Maintenance Costs	Site Fencing & Barrier to Site Compound	item	1	15,860.00	6202 15,860.00 6202	Material	КС10521 КС10902b	Other items Starpicket temporary fencing	/tem	3	500	2,000.00
								6202 6202	Material Material	IC10902d IC10904a	Site Perimeter Chain Mesh Fencir Compound Gates for Site	g /m/day /each	33,000 4	0.32 825	10,560.00 3,300.00
90 90	Contractors Lump Sum	1015	Mabilitation & Demobilitation	Traffic Management for Office Establishment Site Security Setup for Site Compound	item	1	2,939.10	2,939.10 4302 5,000.00 4098	Subcontract Uncommitted	LCM4036 IC21540	2 men Iraffic Crew Site Security	/mtv /item	30	97.97	
90	Jon Houring Long Sum	rei3	muumunon a Lemobilisation	Site Security Setup for Site Compound Design Fees (Lump Sum)	- 811	1	2,000,00	5,000.00 6098	und COIS	KUA 1340	une aecually	, 20011	5,000	1	3,000.00
90	Contractors Lump Sum	8002	Engineering & Design	Eaty Design and Reviews (Stage 1 - Target Budget Estimate Phase)	item		609,712.49 R	tote only 6302	Subcontract Uncommitted	DESIGN	Design Fees	/ium		1	
90	Contractors Lump Sum	8002	Engineering & Design	Detail Design Developement (Stage 2 - Construction Phase)	item		1,048,809.25	1,048,809.25 4302	Subcontract Uncommitted	DESIGN	Design Fees	/sum	1,048,809	1	1,048,809.25
90	Contractors Lump Sum	8002	Engineering & Design	Construction Phase) CPS Phase Cost	item	1	426,595.00	426,595.00 6302	Subcontract Uncommitted	DESIGN	Design Fees	/sum	426,595	1	424,575.00
90	Contractors Lump Sum	8002	Engineering & Design	Project Completion Life Cost	item	1	t	bcluded 6302	Subcontract Uncommitted	DESIGN	Design Fees	/sum		1	
2				TAP3AP - Glenbrook Station - Reimbursable costs				4,791,493.92							
3 70	Trade Prelim Reimbursable	2105	Service Search, Survey & Geolech	Trade Preliminaries (Reimbursement) Site Investigation & Survey (Stage 1 - Target	tam		95,850.00 R	1,864,062.57 tote only 6302	Subcontract Uncommitted	3C50102	Civil Work	/item		1	
70				Budget Estimate)											
70	Trade Prelim Reimbursable	1203	Site Setup Reimbursable	Mobilisation and Demobilisation of plant, equipment and labour	item	1	50,410.52	50,410.52 6382 6382	Equipment Cost	PCH5090 PCH9022	Extra Dogman with cranes Crane Floats	/tr /each	12	85	1,020.00
								6382 6382	Equipment Cost Equipment Cost	PCH9034 PCH9036	Tower Light Floats VMS Floats	/each /each	24 12	140 140	3,840.00
								6382 6382 6382	Equipment Cost Equipment Cost Equipment Cost	PCH9037 PCH9038 IC30105a	Genset Roats Barrier w fence Roats (100m) Transport to site	/each /each /each	6 6 7	205 3,480.00 391.34	20,880.00 2,739.38
								6382 6382	Equipment Cost Equipment Cost	IC30105b IC30106	Transport from site Transport Portaloo to/from	/each /each	7	403.02 120	2,821.14
70	Trade Preim Reimbursable	1150	Indirect (Grey) Labour	Contractors Indirect Labour	item	1	455,867.19	455,867.19 6052 6052	Labour Wages Labour Wages	LCB1002 LCB1006	Labour-CW3 Labour-CW3 (Night Shift)	/mtw /mtw	5,088 144	69 85	12,240.00
								6052 6052	Labour Wages Labour Wages	LC81006a LC85002a	Labour-CW3 (fravel) LAFHA for Labour	/day /day	210 521	69 150	78,114.25
70	Trade Preim Reimbursable	1202	Site office Costs	Site Office and Amenities for Building Subcontractor	item	1	34,641.75	34,641.75 6098 6098	Office Costs	IC20102d	Site Office 6.0x3.0m	/mth	11	342.9	
								6098 6454	Office Costs Utilities	IC20112 IC20307	Container hire (20ft) Site Bectricity	/mth /wk	44 48	124.2 225	5,464.80 10,716.75
70	Trade Prelim Reimbursable	1313	Washe Removal	Waste Disposal	item		49,605.56	49,605.56 6454	Office Costs	IC21126	Maintenance of Site Compound	/wk	48	150	7,144.50
70	Trade Preim Reimbursable	1401	Plant & Equipment - general al	Construction Crone requirements in possessions	item	1	34,740.00	34,740.00 6552	Travel & Accommodation	LC85002d	LAFHA for Labour	/day	9	300	
				process Wildland 10				6382 6382	Equipment Cost Equipment Cost	PCH3010 PCH3010a	Crane Hire 1607 All terrain Crane Hire 1607 All terrain - Overt	/tr ms /tr	36	610 753	27,108.00
								6382 6382	Equipment Cost Equipment Cost	PCH3090 PCH3090a	Extra Dogman with cranes Extra Dogman with cranes - Over	rte lier /tr	36	85	
70	Trade Prelim Reimbursable	1401	Plant & Equipment - general al	Construction Plant and Equipment	item	1	55,456.27	55,456.27 6382	Equipment Cost	PCH1206	Excavator 121	/trr		105.1	

E19-1595-AS-2-279-PR-0001

								6382 6382	Equipment Cost Equipment Cost	PCH2014 PCH2010	Dump Truck Lighting Tower 4000W (Included)	/ter		170 135	6,480.00
								6382 6382 6382 6382	Equipment Cost Equipment Cost Equipment Cost Equipment Cost	PCH8010 PCH8012 PCH8074 PCH8076	Colour LED VMS Board Cherry Ficker	/day /day /day	40 24	45 200 200	1,560.00
								4382 4202 4382	Equipment Cost Material Equipment Cost	PCH8076 MC90106 IC20302b	Scisor Lift Diesel Fuel Generator Hire (60KVA)	/day /lit /wk	8,660 35	200 1.9 893.83	16,454.00 30,962.27
70	Trade Prelim Reimbunable	1314	Security / Cleaning				5,600.00	15,600.00 6052	Labour Wages	IC21506	Security Officer Services	/mtx	240	65	15,600.00
70	Trade Prelim Reimbunable	1208	Temp Building & Services	Temporary Services including CCTV, Lighting, Tollets & Office	item	1 10	9,488.00	109,488.00 4052	Labour Wages Subcontract Uncommitted	LC82002 MC90102	Bechician Misc Materials	/mhr /hem	65,000	90	45,000.00
								4098 4302	Office Costs Subcontract Uncommitted	IC20106 DESIGN	Portable Tollets Mobile (Single) Design Fees	/wk /sum	24 40,000	187	4,488.00 40,000.00
70	Trade Prelim Reimbunable	1051	Council & Other Agency fees	Council and other Agency Fees	item		3,600.00	3,600.00 6504	fees Subcontract Uncommitted	5C0524 5C0526	Council TMP Application	/each /mth	4	900	3,600.00
								4302 4302 4302	Subcontract Uncommitted Subcontract Uncommitted Subcontract Uncommitted	5C0528 5C0530 5C0532	Corflute Sign Shuttle Bus Services Respite (Movie Ticket/Giftcard)	/each /each /hem	30	50 8,100.00 1	1,500.00
70	Trade Prelim Reimbursable	1071	Environmental Management	Environmental managment and protection	item	1 2	4,600.00	24,600.00 4302 6302	Subcontract Uncommitted Subcontract Uncommitted	LCM4030 LCM4032	Report and Photos Environmental Inspection	/item /each	2	5,000.00 2,000.00	10,000.00
70	Trade Prelim Reimbursable	1204	Temp Fencing/hoardings/scaffold	Temporary Barries and Fencing	item.	1 1	1,250.00	6302 11,250.00 6202	Subcontract Uncommitted	LCM4034 MC70124g	S/C Ecologist Concrete Barrier Hire with fence	/mhr /M/day	20	130	2,600.00
								4202 4302	Material Subcontract Uncommitted	MC70126 SC12134d	Special Hoarding Temporary fencing - To Install	/m /m	200	450 6	1,200.00
70	Trade Prelim Reimbursable	1045	Safety & Training	Safety Compliances	item	1 5	5,322.50	55,322.50 4202 4302	Material Subcontract Uncommitted	LCM5010 5C0536	PPE Defibriliator	/ros /each /Rem	100	250 5,000.00 30,150.00	25,000.00 5,000.00 4,522.50
								6411 6411 6084	if Training	IC10718a IC10720a IC21502	Pegasus setup Pegasus Annual Fees Training cost of labour	/year /bem	2 20,000	400	800
70	Trade Prelim Reimbursable	1075	Traffic Management	Traffic Management for Construction Works	item	1 19	9,210.44	159,210.44 4552 4302	Travel & Accommodation Subcontract Uncommitted	LCB5002 LCM4036 LCM4036a	LAFHA for Labour 2 men fraffic Crew 2 men fraffic Crew (1.5x)	/day /mkr /mkr	1,221	180 97.97 118.09	119,627.25
								6302 6302 6302	Subcontract Uncommitted Subcontract Uncommitted Subcontract Uncommitted	LCM4038 LCM4038b	3 men Troffic Crew 3 men Troffic Crew (2.0x)	/mbu /mbu	12 144	138.98 221.72	1,667.76 31,927.68
70	Trade Prefin Reimbunable	1120	Safety & Environment		item	1 14	17,828.50	6302 147,828.50 6052	Subcontract Uncommitted	LCM4040	Establishment - Traffic Control Track Certifier	/eo/d /mhr	240	25 95.5	5,987.75
				possessions				4052 4552	Labour Wages Travel & Accommodation	LC82012b LC85002b	Track Certifier - 2.0x LAFHA for Labour	/mhe /day	24	149 200	3,576.00
								4052 4052 4052	Labour Wages Labour Wages Labour Wages	LWP210D LWP210Da LWP210Db	Protection Officer Class 2 Protection Officer Class 2 - 1.5x Protection Officer Class 2 - 2.0x	/te /te /te	2,251	50 69 95	112,530.50
								4052 4052	Labour Wages	LWP410D LWP410Db	Protection Officer Class 4 Protection Officer Class 4 - 2.0x	fer fer	12 144	64 112	768 16,128.00
70	Trade Preim Reimbunable	1005	Survey	Survey	item	1 27	9,807.93	279,807.93 4552 4302 4302	Travel & Accommodation Subcontract Uncommitted Subcontract Uncommitted	LC85002c LCM4004 LCM4004g	LAPHA for Labour S/C Survey crew S/C Survey crew (w assistant) Por	/day /mhr ses /mhr	228 814 72	145 200 285	37,539.15 162,808.00 20,520.00
								6302 6302 6302	Subcontract Uncommitted Subcontract Uncommitted Subcontract Uncommitted	LC:M4006 LC:M4006b SC:SUR02	S/C Surveyor office S/C Surveyor Mobilisation Cloud Survey	/mhr /hip /hem	222 54 1	140 250 14,460.00	31,011.40 13,469.38 14,460.00
70	Trade Preim Reimbunable	1005	Survey	Dilapidation reports	item	1 2	2,000.00	22,000.00 6302 6302	Subcontract Uncommitted Subcontract Uncommitted	5C18106 5C181060	Delap Surveys Roads & Footpath Delap Rail Infrastructure	s /each /each	1	10,000.00	10,000.00
70	Trade Prefim Reimbursable	1960	Community Liosion	Grafili and Advertising Management	item	1 1	9,340.96	19,340.96 4052 4302	Labour Wages Subcontract Uncommitted	LCB1002 MC90102	Labour-CW3 Misc Materials	/mhr /Nem	208 5,000	69 1	14,340.96
70	Trade Phelim Reimbursable	2105	Service Search, Survey & Geolech	Site Investigations and testing	item	1 e	9,240.00	49,240.00 6302 6302	Subcontract Uncommitted Subcontract Uncommitted	1004024	S/C Onsite Hygienist S/C Soll Tester	/mbu /mbu	120	127 130	15,240.00
								6382 6382 6382	Equipment Cost Equipment Cost Equipment Cost	LCM4025 PCH4002 PCH4002b PCH4002b	Vaccum Sucker Truck Transport & disposal of waste Cable Locator (Txman)	/ter /ter /ter		250 160 120	
70	Trade Prelim Reimbursable	1071	Environmental Management	Heritage managment, protection and	item.	1 1	9,800.00	6302 19,800.00 6302	Subcontract Uncommitted	SCI102	Cill Testing S/C Heritage Consultant	/Nem /mhr	2 80	10,500.00	21,000.00
75		1071	CHICK INCOME IN CONTRACTOR	removals, Reinstatement			7,000.00	6302	Subcontract Uncommitted	LCM4030	Report and Photos	/hem	1	5,000.00	5,000.00
70	Trade Prelim Reimbursable	1313	Waste Removal	Disposal of G3W (All Costs incl. Load, Haul, Unload, Disposal Fees, etc.)	item	1	No	t priced							
70	Trade Prelim Reimbursable	1940	Community Liasion	Social Procurement/Responsibility	item	1	No	I priced							
4				Builders Freilms (Reimbursement) Existing Services Search & Identify				247,002.95							
70	Trade Prelim Reimbunable	2105	Service Search, Survey & Geolech		lem	1 1:	5,000.00	15,000.00 4302	Subcontract Uncommitted	3C021	Glenbrook Pockoges	/hem	15,000	1	15,000.00
6				Scotfolding Lift 1 - Platform				59,814.90 35,424.50							
70	Trade Preim Reimbursable	1204	Temp Fencing/hoardings/scatfold	Scaffolds to lift cores, footbridge & stain provided by Contractor, other installation	tem	1 3	15,626.50	35,626.50 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	35,627	1	35,626.50
				scattolds (modular & mobile types) by each respective trade subcontractor											
6 70	Trade Prelim Reimbursable	1204	Temp Fencing/hoardings/scaffold	Temporary Access from Buffit Parade Allow for temporary access from Buffit	Item	1 2	H, 190.40	24,190.40 24,190.40 6302	Subcontract Uncommitted	3(0)21	Glenbrook Packages	/hem	24,190	1	24,190.40
				Parade during construction interface between new works & existing footbridge											
5 6				Temporary Screens & Hoardings Lift 1 - Molform				172,186.05							
70	Trade Preim Reimbursable	1204	Temp Fencing/hoardings/scatfold	Temporary hoarding screen on platform	m2 5	96	237.38	22,788.48 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	22,788	1	22,788.48
6 70	Trade Prelim Reimbursable	1204	Temp Fencing/hoardings/scaffold	Access Fathway & Stairs from Burlitt Parade Temporary hoarding/workscreen to provide		45	1,472.19	143,877.57 66,248.55 6302	Subcontract Uncommitted	30021	Glenbrook Packages	/hem	66,249	1	66,248.55
				separation between rail corridor and construction of access ramp & stairs											
70	Trade Prelim Reimbunable	1204	Temp Fencing/hoardings/scatfold	Temporary hoarding screen to she incl. street in frontage	m2 27	79	237.38	66,229.02 6302	Subcontract Uncommitted	30021	Glenbrook Packages	/hem	66,229	1	66,229.02
70	Trade Prelim Reimbunable	1204	Temp Fencing/hoardings/scatfold	Provide jersey barriers for safe temporary pedestrian movement	ltem	1	0	6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem		1	
70	Trade Prelim Reimbunable	1204	Temp Fencing/hoardings/scaffold	Tree protection to remaining trees incl. In maintenance	Item	1 1	1,400.00	11,400.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	11,400	1	11,400.00
6 70	Trade Prelim Reimbunable	1204	Temp fencing/hogrdings/scalloid	Disabled Corspoces To Existing Corpork	liem.	1 3	5,520.00	5,520.00	Subcontract Uncommitted	30021	Glenbrock Pockoges	/hem	5,520	1	5,520.00
70	Trade Prelim Reimbursable			Provide jersey barriers for safe temporary a		1	0	6302	Subcontract Uncommitted	50021	Glenbrook Pockoges	/item		1	
٤				Pathway Works of Burfit Parade & Ross Street (west)											
70	Trade Preim Reimbursable	1204	Temp Fencing/hoardings/scatfold		Item		5,000.00 Rat	fe only 6302	Subcontract Uncommitted	5C021	Gienbrook Packages	/hem		1	
70	Trade Preim Reimbursable	1204	Temp Fencing/hoardings/scaffold	Temporary pedestrian access during new footpath works	Item		٥	6302	Subcontract Uncommitted	3C021	Glenbrook Packages	/item		1	
70	Trade Prelim Reimbursable	1204	Temp Fencing/hoardings/scatfold	Provide jensey barriers for safe temporary pedestrian movement	llem		٥	6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item		1	
6 70	Trade Prelim Reimbursable	1204	Terrer Ferreinen fernen f	OHW Relocated Stanchion	-		1,404.86 Rot	fe only 6302	Subcontract Uncommitted	50221	Gienbrook Packages	Atem		1	
70		1404	/emp/ren/cing/hoardings/scaffold	Temporary hoarding/workscreen to provide separation between rail consider and construction of relocated OHW stanchion			.,		www.nacruncommitted	accard 1	unersecord POCKOges	,888			
4				Solar Panel Mounting Foundations											
¢				Location of Solar Panel Mounting to be advised, if located on south bank of rail corridar (as currently proposed) will require											
				temporary structural hoarding within rail corridor for construction of panel foundations, mounting frame & panels - see											
				SOLAR POWER trade for all allowances related to Solar											
3				STATION FLATFORMS - CIVIL WORKS (Inside roll corridor)				1,484,328.12							
4 20	Matform	2410	Excavation/Ming	Relocations/Protection Relocation/Protection of Utilities/Services	Bern	1 2	0,000.00	20,000.00	Subcontract Uncommitted	30:50102	Civil Work	/Hem	20,000	1	20,000.00
4				(LV & comms cable only not watermain) Demolition				31,516.76							
c				following are subcontract allowances, contractor preliminaries, overheads &											
e				margin are separately allowed for Works generally undertaken during normal											
				hours. Where works are to be undertaken during possession or out of hours, see "markup"											
¢				Significant material handling to/from platforms by Managing Contractor (Downer)											
c				Assume platform waste/materials to be											
				stockpiled / skip bin at end platform by sub- contractor, nemoved outside hours to stockpile outside rail corridor by Managing											
				Contractor (Downer), disposal off site by sub- contractor											
c				Scaffolds to IIIt cores, footbridge & stairs provided by Managing Contractor (Downer), other installation scaffolds (modulor & mobile											
				ofher installation scattolds (modular L mobile types) by each respective trade subcontractor											
c				Asbestos & Hazardous materiais msd. in separate trade											
c				Relocation of electrical services such as pole lights, etc are to be allowed for in the respective services trades											
5				respective services trades				6,661.76							

20	Platform	2410	Excavation/Piling	Remove existing platform garden, seating. Item etc.	1	2,500.00	2,500.00 4302	Subcontract Uncommitted	5(3021	Glenbrook Packages	/item	2,500	1	2,500.00
20	Platform	2410	Excavation/Piling	Saw cut and break out existing asphalt Mt platform surface to allow the construction of	1	2,020.00	2,020.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	2,020	1	2,020.00
20	Patform	2410	Excavation/Hing	lift pit Locally cut & remove sections of footbridge Item	1	2,141.76	2,141.76 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	2,142		2,141.76
				balushade to suit new footbridge opening to lift										
5				Access Pathway & Stairs from Burlitt Parade			24,855.00							
15			Excavation/Ming	Remove rail boundary chainwire mesh fence illem	1	1,645.00	1,645.00 4302	Subcontract Uncommitted		Glenbrook Packages	/item	1,645		
15			Excavation/Ming	Site clear incl. tree removal Bern Demolish & remove existing ramp access to Bern	1	7,290.00	7,290.00 4302	Subcontract Uncommitted	SC021 SC021	Glenbrook Packages	/item	12,510		12,510,00
15			Excavation/Ming	footbridge Demolish existing footpath m2	62	55	3,410.00 4302	Subcontract Uncommitted		Glenbrook Packages	/item	3,410		3,410.00
5	Norn schirt Fordse (k	amp) 2410	Excovator(/hing	Noticem Building Alterations	62	23	3,410.00 6302	subcontract uncommitted	30021	Genbrook hockoges	/nem	3,410		3,410.00
¢				Demoiltion for plotform building alterations allowed for in "Existing Matform Building										
				Alterations, Additions & Refurblahment" element										
4				Asbestos & Hazardous Material Removal - Iba			60,460.00							
20	Platform	2010	Demolition	Hazardous material register notes lead dust I tem in ceiling space - allowance to remove lead dust from ceiling space	1	60,460.00	60,460.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	60,460	1	60,460.00
4				Excavation			541,047.64							
¢				following are subcontract allowances, contractor preliminaries, overheads & margin are separately allowed for										
c				Works generally underlaken during normal hours. Where works are to be underlaken										
				during possession or out of hours, see "markup"										
e				Significant material handling to/from platforms by Contractor										
c				Assume plotform spoil to be stockpiled / skip bin of end plotform by sub-contractor, removed outside hours to stockpile outside										
				removed outside hours to stockpile outside rail comidor by Contractor, disposal off sile by sub-contractor										
¢				Assume disposal as GSW										
5 20	Platform	2410	Excavation/Ming	Lift 1 (Flatform) Excervate to reduce levels for iift pit/pile m3	84	505.36	166,804.92 42,450.24 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	42,450	1	42,400.24
20	Platform	2410	Excevation/Ning	cap Excavate for pad faotings - hand/smat plant m3		805.18 Ro		Subcontract Uncommitted	5C021	Glenbrook Packages	/item			
c		-		excevation Geolechnical bare hales recid 14/07/2018										
-				Geotechnical bore holes mc/d 14(07)2018 Indicate rock of 0.37 below platform level (BH01-2019), estimate allowed rock from track level										
20	Platform	2410	Excavation/Hiling	tack level Extra Over for excavation in rock m3	69	375	25,875.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item /item		1	25,875.00
20	Platform	2410	Excavation/Hiling	Backfilling around lift pit with suitable m3		600 Ro	6302 te only 6302	Subcontract Uncommitted	SC50102 SC021	Civil Work Glenbrook Packages	/item	25,875	1	25,875.00
20	Platform	2410	Excavation/Hiling	excavated materials Backfiling around lift pit with imported m3	64	685.35	43,862.40 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	43,862	1	43,862.40
20	Platform	2410	Excavation/Hiling	compacted fill Dispose surplus excavated material off site m3	84	435.92	36,617.28 6302	Subcontract Uncommitted	5(2021	Glenbrook Packages	/item	36,617	1	34,617.28
20		2410	Excavation/Piling	Shoring to lift pits m2	48	375	18,000.00 6302	Subcontract Uncommitted	5(2021	Glenbrook Packages	/item	18,000	1	18,000.00
5 15		amp) 2410	Excavation/Ming	Access Pathway & Stats from Burlit Parade Encovate to reduced levels for new access m3	265	336.91	374,242.72 89,281.15 4302	Subcontract Uncommitted	5C021	Glenbrock Packages	/item	87,281		89,281.15
15			Excavation/Ming	pathway & stains	17	536.79	9,125.43 6302	Subcontract Uncommitted		Glenbrook Pockages	/item	9,125		9,125.43
15			Excavation/Hing	Extra Over for excavation in rock - m3 allowance	215.75	300	64,725.00 6302		SC:50102	Ciril Work	/item	64,725	1	
15	North Burfitt Parade (R	amp) 2410	Excavation/Hiling	Backfiling to retaining wals with cement m3 stabilised backfil	193	456.9	88,181.70 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/hem	88,182	1	88,181.70
15	North Burfitt Parade (R	amp) 2410	Excavation/Hing	Dispose surplus excavated material off site m3	282	435.92	122,929.44 4302	Subcontract Uncommitted	5(2021	Glenbrook Packages	/item	122,929	1	122,929.44
15 5	North Burfitt Parade (R	amp) 2410	Excavation/Hiling	Shoring as required m2 ONW Support Stanchion		250 Ra	te only 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item		1	
۰ د				Rebate Cutting in Rock Wall										
40	Project Wide	2220	Excavation/Cut	Escavate cutting within rock face for m3 relocated OHW stanchion		836.79 Ro	te only 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item		1	
60	Project Wide	2220	Excavation/Cut	Allow stabilise cutting face (eg shotcrete, them anchon)		10,000.00 Ra	te only 6302	Subcontract Uncommitted	5(0021	Glenbrook Packages	/item		1	
40	Project Wide	2220	Excavation/Cut	Dispose surplus excavated material off site m3 (GSW)		435.92 Ro	te only 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item		1	
¢				Awailing design for OHW Support Stanchion - allow 750mm pile with 1200x 1202x 400mm										
60	Project Wide	2220	Excavation/Cut	deep pile cap Excavate to reduced levels for pile cap m3		536.79 Ro	te only 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item		1	
60	Project Wide	2220	Escavation/Cut	Extra Over for excavation in rock m3		300 Ra	te only 6302	Subcontract Uncommitted	5(2021	Glenbrook Packages	/item		1	
60	Project Wide	2220	Excavation/Cut	Backfiling to pile cap with imported m3 compacted materials		456.9 Ra		Subcontract Uncommitted	5(3021	Glenbrook Packages	/item		1	
60	Project Wide	2220	Excavation/Cut	Dispose surplus excavated material off site m3 (GSW)		435.92 Ro		Subcontract Uncommitted	5(3021	Glenbrook Packages	/item		1	
60 5		2220	Excavation/Cut	Shoring as required m2 Salar Panel Mounting Foundations		250 Ro	te only 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item		1	
c				Location of Solar Panel Mounting to be advised, il located on south bank of rail										
				conidor (as currently proposed) will require foundations for panel mounting frame see SOLAR POWER trade for all allowances										
4				SOLAR POWER trade for all allowances related to Solar Filing			48,391.70							
4 c				Filing following are subcontract allowances, contractor preliminaries, overheads &			-w.el130							
				margin are separately allowed for										
¢				Works generally underlaken during normal hours. Where works are to be underlaken during possession or out of hours, see "markup"										
c				Significant material handling to/from										
e				platforms by Contractor Assume platform waste/materials to be										
				stockpiled / skip bin at end platform by sub- contractor, removed outside hours to stockpile outside rall contidor by Contractor,										
5				disposed off alle by sub-contractor			48,391.70							
¢				Allow effective piling length ofter lift pit/boling excavations, glow Extra Over for										
				liners within lift pit/footings depth, note spoil quantity within lift pit/footings depth included in lift pit/footing excavation										
20	Platform	2410	Excavation/Hiling	Ne P1 - 750mm dia, minimum 2500mm socket m into rock - initial Geotech advice 8m depth		3,635.16 Ro	te only 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item		1	
				into sock - Initial culosicol davice em capm from plotform incl. 3m into rock - allow \$500mm overall pile depth										
20	Platform	2410	Excavation/Hiling	Ne 750mm dia - lines within III pit/footings No. depth		600 Ro	te only 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item		1	
20	Platform	2410	Excavation/Hiling	Adjustment made to Subcontract Pricing Item Assessment (Rev2)		1,878.00 Ro	te only 6302	Subcontract Uncommitted	SC50102	Civil Work	/item		1	
c				Revised works as per price/programme workshop 17/09/2018 (yet to be redesigned)										
20	Platform	2410	Excavation/Piling	Ground anchor - 30mm Macalloy bar grouted m	42	1,093.33	45,919.86 6302	Subcontract Uncommitted	SC:50102	Civil Work	/item	45,920	1	45,919.86
20	Mattorm	2410	Excavation/Hiling	in 200mm care hole Core casing - allowance within lift pit No.	4	400	1,600.00 4302	Subcontract Uncommitted	SC50102	Civil Work	/item	1,400	1	1,600.00
20	Platform	2410	Ecovation/Ning	Dispose surplus excavated material off site m3 (GSW)	2	435.92	871.84 4302	Subcontract Uncommitted		Civil Work	/item	872		
5				Access Pathway & Slais from Burlitt Parade										
c				No piling designed to Access Pathway & Stats from Burlitt Parade										
s c				OHW Support Stanchion Awailing design for OHW Support Stanchion -										
				allow 750mm pile with 1200x 1200x 400mm deep pile cap										

60	Project Wide 2410	Excavation/Ming	Pile P1 - 750mm dia. minimum 2300mm socket m into rock - initial Geotech advice 8m depth from platform incl. 5m into rock - allow		5,052.68 Roly	e only 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item		1	
			5500mm overall pile depth - advised to allow separate mobilise to lift pit due to possessions										
60	Project Wide 2410	Escavation/Hiling	posessions Pile 750mm dia - linen within lift pit/footings No.	3.	600 Roh	e only 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item		1	
5			depth Solar Panel Mounting Foundations										
с с			Location of Solar Panel Mounting to be										
			advised, if located on south bank of rail corridor (as currently proposed) will require foundations for panel mounting trame - see										
			SOLAR POWER trade for all allowances related to Solar										
4			Burlitt Parade Entry Ramp & Stair Structure			288,339.96							
c			following are subcontract allowances, contractor preliminaries, overheads & margin are separately allowed for										
c			Works generally underfaken during normal hours. Where works are to be underlaken										
			nous, where works are to be undertaken during possession or out of hours, see "markup"										
e			Refer to excovation trade for site preparation & excovation works										
c			Filing										
15	North Burfitt Parade (Ramp) 2410	Ecovation/Pling	Asume 600mm dia piles, socket 1000mm into No. rock	a. 10	4,192.69	41,926.90 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	41,927	1	41,926.90
e			Retaining Wall footings										
15	North Burfitt Parade (Ramp) 2401 North Burfitt Parade (Ramp) 2401	Shuchard FRP Shuchard FRP	Prepare subgrade, concrete blindings m2 xXMPa concrete in retaining wall footings m3		45 712.8	2,520.00 4302	Subcontract Uncommitted		Glenbrook Packages	/item	2,520	1	2,520.00
15	North Burlitt Parade (Ramp) 2401	Shuchural FRP	formwork to edge of retaining wall foottings m		120	8,640.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	8,640	1	8,640.00
15	North Burlitt Parade (Ramp) 2401	Shuchard FRP	Bar reinforcenment in povement slab & steps -t	3	3,600.00	10,800.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	10,800	1	10,800.00
			on ground (#120kg/m3) Concrete Ramp & Stain										
- c			Concrete										
15	North Burfitt Parade (Ramp) 2401	Structural FRP	Prepare subgrade, blindings & WPM m2		35	5,215.00 6302	Subcontract Uncommitted		Glenbrook Packages	/item	5,215	1	5,215.00
15	North Burfitt Parade (Ramp) 2401	Shucharol FRP	xXMPa concrete in pavement slab & steps m3 on ground	3 51	619.62	31,400.42 4302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	31,601	1	31,600.42
15	North Burfitt Parade (Ramp) 2401	Structural FRP	Surface finish m2		10	1,490.00 6302	Subcontract Uncommitted		Glenbrook Packages	/hem	1,490	1	1,490.00
15 e	North Burfitt Parade (Ramp) 2401	Structural PRP	Ditto but to stair tread m	48	16	768 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	768	1	768
15	North Burfitt Parade (Ramp) 2401	Structural FRP	Formwork to edge of pavement slab on m ground incl. curved on plan	86	120	10,320.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	10.320	1	10,320.00
15	North Burlitt Parade (Ramp) 2401	Structural FRP	formwork to edge of steps stringer on m	8	150	1,200.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	1,200	1	1,200.00
15	North Burlitt Parade (Ramp) 2401	Shucharal FRP	ground Farmwork to stair riser m	48	75	3,600.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	3,600	1	3,600.00
c			Reinforcement										
15	North Burfitt Parade (Ramp) 2401	Shuctural FRP	Bar reinforcenment in povement slab & steps -t on ground (@120kg/m5)	7	3,600.00	25,200.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	25,200	1	25,200.00
c			Concrete Joints										
15	North Burfitt Parade (Ramp) 2401 North Burfitt Parade (Ramp) 2401	Shuchard FRP Shuchard FRP	Concrete Joints m2	2 149	12	1,788.00 4302	Subcontract Uncommitted	SC021 SC021	Gienbrook Packages	/item	1,788	1	1,788.00
c	Home and the second sec		Concrete Seci	-	200	1,00000 0.000	addoninaci di commina	20021	den stool i destages	June	1,000		1,000,00
15	North Burlitt Parade (Ramp) 2401	Shuchard FRP	Applied concrete seal to pavement slab & m2 steps on ground	2 149	0	6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item		1	
c			Nockwork Retaining & Balushade Walls										
15	North Burfitt Parade (Ramp) 2401	Structural FRP	Core filled reinforced block retaining & m2 balustrade wall, coloured split face where	2 184	370.01	68,081.84 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	68,082	1	68,081.84
15	North Burlitt Parade (Ramp) 2401	Structural FRP	exposed, curved on plan Capping block m	104	90	9.360.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	2.30		7.340.00
15	North Burlitt Parade (Ramp) 2401	Shuchural FRP	Tanking to inside face of retaining wall with m2	2 129	0	6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item		1	
			sheet protection - deleted as per Steve Hicks deemed not required										
15	North Burfitt Parade (Ramp) 2401	Shuctural FRP	Agg drain to retaining walls m Stair Nasings, Tactiles, Handrails	104	65	6,760.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	6,760	1	6,760.00
c			Sicir Nosings, Tactiles, Handrais are allowed elsewhere in Suliding Package works										
15	North Burfitt Parade (Ramp) 2410	Ecovation/Piling	Adjustment made to Subcontract Pricing Iten	im 1	9,338.00	9,338.00 6302	Subcontract Uncommitted	SC50102	Civil Work	/hem	9,338	1	9,338.00
			Assessment (Rev2) Design Development 30/10/2018										
15	North Burlitt Parade (Ramp) 2485	Brickwork	Bus stop modified. Add concrete pathway LS for level access. Add balands to new station	1	36,564.00	36,564.00 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	36,564	1	34,544.00
			entry. etc										
4			Paving & Finishes Assume no applied finishes to concrete										
4			povements & stola Bicycle Rocks/Shellers			5,070.00							
15	North Burfitt Parade (Ramp) 2035	Landscaping	Bicycle rock No.	s. 5	550	2,750.00 4302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	2,750	1	2,750.00
15	North Burfit Parade (Ramp) 2035	Landscaping	Bicycle locker relocated from parking lot then	m 1	2,320.00	2,320.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	2,320	1	2,320.00
4			Sheet Furniture Following are subcontract allowances,			22,887.53							
			contractor preliminaries, overheads & margin are separately allowed for										
c			Works generally underfaken during normal hours. Where works are to be undertaken										
			during possession or out of hours, see "markup"										
5 15	North Burfitt Parade (Ramp) 2035	[repairs series	Access Pathway & Stairs from Burlitt Parade		3,000.00	22,887.53 3,000.00 6302	Subcontract Uncommitted	50001	Glenbrook Packages	/item	3,000		3,000.00
13 C	www.wordinicade.(Kamp) 2035	Landscaping	Design Change Register 12/07/2018 item	. 1	.,uuud0	JUNEOU 6302	autoralitiaci uncommitted	aculat	une arook nackoges	, dem	3,000		3,000.00
c			DCR043, yet to be redesigned Allow for bin store located off new access										
	March Row Western Street Street	Lange to a set of a	ramp from Burfitt Pde - allow 4000 x 1500mm		ag and	9 499 Mar 1	Robust Transmission			p	g		
15	North Burfitt Parade (Ramp) 2035 North Burfitt Parade (Ramp) 2035	Landscaping	Subfoor wall footing incl. excavation m Subfoor wall m2		2,425.99 497.21	7,277.97 6302 2,486.05 6302	Subcontract Uncommitted		Civil Work Civil Work	/item /item	7,278	1	7,277.97 2,486.05
15	North Burlitt Parade (Ramp) 2035	Landscaping	Compacted engineered backfill to form IK's m3 incl. subgrade compaction		685.35	6,168.15 6302	Subcontract Uncommitted	SC:50102	Civil Work	/item	6,168	1	6,168.15
15	North Burfitt Parade (Ramp) 2035	Landscaping	Concrete povement slab m2	2 6	384.56	2,307.34 6302	Subcontract Uncommitted	5C50102	Civil Wark	/item	2,307	1	2,307.36
15	North Burfitt Parade (Ramp) 2035	Landscaping	Balustrade m	3	550	1,650.00 6302	Subcontract Uncommitted	SC:50102	Civil Work	/item	1,650	1	1,650.00
4 c			Balustrades & Screens following are subcontract allowances,			107,416.00							
			contractor preliminaries, overheads & margin are separately allowed for										
c			Works generally undertaken during normal hours. Where works are to be undertaken										
			during possession or out of hours, see "markup"										
5	March Road American March 1997	finite of the second second	Access Pathway & Slaits from Burfit Parade			107,416.00	Robert Frankrik	10000	Plant and Part 1				8481470
15	North Burfitt Parade (Ramp) 5028	Finishes/signage/marking	HDG balustrade with stainless steel handrail, m curved on plan		1,116.00	84,816.00 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/nem	84,814	1	84,816.00
15	North Burfitt Parade (Ramp) 5028	Finithes/signage/marking	Stainless sheet balustrade with handrall incl., m curved on plan	50	456	22,800.00 4302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	22,800	1	22,800.00
4 c			fencing following are subcontract allowances,			48,250.00							
			following are subcontract allowances, contractor preliminaries, overheads & margin are separately allowed for										
¢			Works generally undertaken during normal hours. Where works are to be undertaken										
			during possession or out of hours, see "markup"										
5			Access Pathway & Slais from Burlitt Parade			48,250.00							
15	North Burfitt Parade (Ramp) 5028	Finishes/signage/marking	Rail carridor fencing, 3.0m high including m foundations, insulated panel separation	61	950	57,950.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	57,950	1	57,950.00
15	North Burfitt Parade (Ramp) 5028	Finishes/signage/marking	Allow for lockable gates as necessary then	im 1	10,300.00	10,300.00 4302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	10,300	1	10,300.00
15 4 C				m 1	10,300.00	10,300.00 6302 5,010.00	Subcontract Uncommitted	SC021	Glenbrook Packages	/hem	10,300	1	10,300.00

| c | | |
 |
 | Works generally undertaken during normal
hours. Where works are to be undertaken
 | | | |
 | |
 | | | | |
 |
|--|--------------------------------------|--
--

--|--|---|--
--
--	---	--	---
 |
 | during passession or out of hours, see
"markup"
 | | | |
 | |
 | | | | |
 |
| c | | |
 |
 | Significant material handling to/from
platforms by Contractor
 | | | |
 | |
 | | | | |
 |
| 5 | 0 | Platform | 2350
 | Regrade
 | Lift 1 (Platform)
Temporary make good existing asphalt
 | ND. | 1 | 5,010.00 | 5,010.00
5,010.00 4302
 | Subcontract Uncommitted | 5(02)
 | Glenbrook Packages | /hem | 5,010 | 1 | 5,010.00
 |
| | | |
 |
 | platform surface where removed for the
construction of lift pit
 | | | |
 | |
 | | | | |
 |
| 3 | 0 | Platform | 2350
 | Regrade
 | Temporary make good existing asphalt
platform surface where removed for the
construction of pad footings
 | No. | | 2,400.00 Rote o | only 6302
 | Subcontract Uncommitted | SC021
 | Glenbrook Packages | /Bem | | 1 |
 |
| 4 | | |
 |
 | Final Platform Surface Reinstatement - also
see platform regrading
 | | | |
 | |
 | | | | |
 |
| 4 | | |
 |
 | Motform Surface/Regrading - extent foc
 | | | | 248,787.70
 | |
 | | | | |
 |
| c | | |
 |
 | following are subcontract allowances,
contractor preliminaries, overheads &
margin are separately allowed for
 | | | |
 | |
 | | | | |
 |
| c | | |
 |
 | Pattorm surface regrade works are allowed
to be undertaken during possession
 | | | |
 | |
 | | | | |
 |
| c | | |
 |
 | Significant material handling to/from
platforms by Managing Contractor (Downer)
 | | | |
 | |
 | | | | |
 |
| 5 | | |
 |
 | Platform 1/2
 | | | | 144,716.58
 | |
 | | | | |
 |
| 2 | 0 | Platform | 2350
 | Regrade
 | Platform Surface Regrading from Lift to FAT-
where mill concrete to 15mm & epoxy
 | m2 | 131 | 278.85 | 36,529.35 4302
 | Subcontract Uncommitted | 5(02)
 | Glenbrook Packages | /Nem | 36,529 | 1 | 34,529.35
 |
| 2 | 0 | Platform | 2350
 | Regrade
 | topping
Platform Surface Regrading from Lift to FAT -
 | m2 | 271 | 438.13 | 118,733.23 4302
 | Subcontract Uncommitted | 5(02)
 | Glenbrook Packages | /hem | 118,733 | | 118,733.23
 |
| 2 | | Platform | 2350
 | Regrade
 | serve & replace concrete paving slabs
wher greater than 15mm
Hearing loop pit & conduits
 | Per | 2 | 1,752.00 | 3,504.00 6302
 | Subcontract Uncommitted | 5(02)
 | Glenbrook Packages | /item | 3,504 | | 3,504.00
 |
| - | | | 2350
 | Regrode
 | Modify existing plant bed stone
header/coping to suit regraded platform
 | m | 53 | 150 | 7,950.00 4302
 | Subcontract Uncommitted | SC021
 | | /hem | 7,950 | | 7,950.00
 |
| | | |
 |
 | levels Option to roise platform RL will be priced
 | | | |
 | |
 | | | | |
 |
| 5 | | |
 |
 | Separately
Mattern regrade extended to platform 2
 | | | | 102,071.12
 | |
 | | | | |
 |
| | | Platform | 2350
 | Regrade
 | (21/07/2018)
Platform Surface Regrading from Lift to FAT -
 | | 200 | | 55,770.00 6302
 | Subcontract Uncommitted | 1000
 | Glenbrook Packages | /item | 55.770 | 1 | 55,770.00
 |
| | | 1 AUTOINT | 2000
 | ABJOON .
 | where mill concrete to 15mm & epoxy
topping
 | 114 | 200 | 270.03 | 2077000 4202
 | 200010210100111100 | 30021
 | one crock i occuper | panta | 2070 | | 22,770.00
 |
| 2 | 0 | Platform | 2350
 | Regrade
 | Platform Surface Regrading from Lift to FAT-
remove & replace concrete paving slabs
wher greater than 15mm
 | m2 | 24 | 438.13 | 10,515.12 4302
 | Subcontract Uncommitted | 5C021
 | Glenbrook Packages | /item | 10,515 | 1 | 10,515.12
 |
| 2 | 0 | Platform | 2350
 | Regrade
 | Hearing loop pit & conduits
 | Per | | 1,752.00 Rate o | oniy 6302
 | Subcontract Uncommitted | SC021
 | Glenbrook Packages | /hem | | 1 |
 |
| 3 | 0 | Platform | 2350
 | Regrode
 | Modify existing plant bed stone
header/coping to suit regraded platform
levels
 | m | 17 | 150 | 2,550.00 4302
 | Subcontract Uncommitted | SC021
 | Glenbrook Packages | /ðem | 2,550 | 1 | 2,550.00
 |
| ¢ | | |
 |
 | Design Development 30/10/2018
 | | | |
 | |
 | | | | |
 |
| 3 | 0 | Platform | 2350
 | Regrade
 | Platform regrade - reduced extent of mill
only (where levels within 15mm) for
pavement replacement due to additional
 | 15 | 1 | 33,236.00 | 33,234.00 4302
 | Subcontract Uncommitted | 5(002)
 | Glenbrook Packages | /item | 33,236 | 1 | 33,234.00
 |
| 4 | | |
 |
 | design levels now provided
 | | | | 50,000.00
 | |
 | | | | |
 |
| ¢ | | |
 |
 | Following are subcontract allowances, contractor preliminaries, overheads &
 | | | |
 | |
 | | | | |
 |
| c | | |
 |
 | margin are separately allowed for
Works generally undertaken during normal
 | | | |
 | |
 | | | | |
 |
| | | |
 |
 | hours. Where works are to be undertaken
during possession or out of hours, see
"markup"
 | | | |
 | |
 | | | | |
 |
| c | | |
 |
 | Significant material handling to/from
platforms by Contractor
 | | | |
 | |
 | | | | |
 |
| 5 | | |
 |
 | Access Pathway & Stairs from Burlitt Parade
 | | | | 50,000.00
 | |
 | | | | |
 |
| 5 | | North Burfit Parade (Ramp) | 5028
 | Finishes/signage/marking
 | Landscoping
Platform
 | fem | 1 | 50,000.00 | 50,000.00 4302
 | Subcontract Uncommitted | SC021
 | Glenbrook Pockages | /hem | 50,000 | 1 | 50,000.00
 |
| 3 | 0 | Platform | 2035
 | Landscaping
 | Landscaping
 | lfem | 1 | 0 | 4302
 | Subcontract Uncommitted | SC021
 | Glenbrook Packages | /ðem | | 1 |
 |
| 4 | | |
 |
 | CSR Inground - Pits & Conduits
 | | | | 139,503.47
 | |
 | | | | |
 |
| 5 | | |
 |
 | Electricals
 | | | | 139,503.47
 | |
 | | | | |
 |
| 2 | 0 | | 2183
 | CSR
 | CSR Routes (Platform)
 | m | 50 | 563.54 | 28,177.00 4302
 | Subcontract Uncommitted | SC000
 | | | 28,177 | | 28,177.00
 |
| 2 | 0 | North Burfitt Parade (Ramp) |
 | CSR
CSR
CSR
 |
 | m
m
nos | 50
76
3 | 563.54
568.49 |
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted | 5C000
5C000
5C000
 | Subcontract Uncommitted | Sum | 28,177
43,205
15,301 | 1 |
 |
| 2
1
2 | 0
5
0
5 | North Burfit Parade (Ramp)
Platform
North Burfit Parade (Ramp) | 2183
2183
2183
 | CSR
CSR
CSR
 | CSR Rouhes (Rolform)
CSR Rouhes (Rolf Contidor)
Electrical Pils (Rolform)
Electrical Pils (Rolf Contidor)
 | m | 76
3
8 | 563.54
568.49
5,100.45
6,231.86 | 28,177.00 4302
43,205.24 4302
15,301.35 4302
49,834.88 4302
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted | 5C000
5C000
5C000
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted | Sum
Sum
Sum | 43,205
15,301
49,855 | 1 | 28,177.00
43,205.24
15,301.35
49,854.88
 |
| 2
1
2 | 0
5
0
5 | North Burfit Parade (Ramp)
Platform | 2183
2183
2183
 | CSR
CSR
 | C3R Routes (Patform)
C3R Routes (Rail Caridar)
Bectrical Pils (Platform)
 | m
nos | 76
3 | 563.54
568.49
5,100.45 | 28,177.00 4302
43,205.24 4302
15,301.35 4302
49,854.88 4302
2,945.20 4302
4302
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted | SC000
SC000
SC000
SC5000
SC5000
SC5000
SC5000
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Supply of 100mm G31 w 1.5m post
Install of 100mm G31 m new post
Supply of 100mm G31 popper | Sum
Sum
/M
/M
/ma | 43.205
15.501
49,835
8 11
8 1 | 1
1
14.45
175.4
420 | 28,177.00
43,205.24
15,301.35
47,854.88
915.6
1,411.20
168
 |
| 2
1
2 | 0
5
0
5 | North Burfit Parade (Ramp)
Platform
North Burfit Parade (Ramp) | 2183
2183
2183
 | CSR
CSR
CSR
 | CSR Rouhes (Rolform)
CSR Rouhes (Rolf Contidor)
Electrical Pils (Rolform)
Electrical Pils (Rolf Contidor)
 | m
nos | 76
3
8 | 563.54
568.49
5,100.45
6,231.86 | 28,177.00 6302
43,205.24 6302
15,301.33 6302
49,854.88 6302
2,965.20 6302
6302
6302
6302
6302
6302
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted | SC000
SC000
SC000
SC5001
SC5002
SC5003
SC5003
SC5004
SC5005
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Supply of 100mm G31 vs 1.5m post
Instald at 120mm G31 compare
Instald at 120mm G31 compare
Instald of 120mm G31 compare
Instald of 120m G31 pogtanism | 50m
50m
700
700
700
700
700
700
700 | 43.205
15.301
49,355
8 11
8 1
2 | 1
1
1
44.45
420
577.5
420
577.5
420
577.5 | 28,177.00
43,205.24
15,301.35
47,854.88
915.6
1.411.20
 |
| 2
1
2 | 0
5
0
5 | North Buffit Parade (Romp)
Platform
North Buffit Parade (Romp)
North Buffit Parade (Romp) | 2183
2183
2183
2183
 | C38
C38
C38
C38
 | C3R Rouhes (Parliam)
C3R Rouhes (Nai Cansko)
Bachtad Phy (Parliam)
Bachtad Phy (Parliam)
Cast Rouhes (Itali Cansko)
 | m
nos | 76
3
8 | 563.54
568.49
5,100.45
6,231.86
370.65 | 28,177.00 4302
43.005.24 4352
15.501.34 4352
2,965.20 4302
49.854.88 4302
4302
4302
4302
4302
4302
4302
4302
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted | 5000
5000
5000
5000
5000
5000
5000
500
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Supply of 100mm G31 vs. 3 m post
Instal of 100mm G31 vs. 3 m post
Instal of 100mm G31 Deoper
Instal of 100mm G31 Deoper
Instal of G31 big Installion
Supply of G31 vs. 1 monitory
Instal of G31 big Installion | Sum
Sum
MA
MA
Intera
Intera
Intera
Intera
Intera
Intera | 43.005
15.301
49.555
8 11
8 1
2
120
120 | 1
1
14.45
72.4
420
57.5
420 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
1
2 | 0
5
5
5
5 | North Buffit Parade (Romp)
Platform
North Buffit Parade (Romp)
North Buffit Parade (Romp) | 2183
2183
2183
 | CSR
CSR
CSR
 | Cit Rover (Hafran)
Cit Rover (Hafran)
Becker (Hafran)
Becker (Hafran)
Becker (Hafran)
Cit Rover (Hafran)
Dirden Tools Cheshing
Additional CIR Rover (Harrysteining of
 | m
nos | 76
3
8 | 563.54
568.49
5,100.45
6,231.86 | 281.177.00 4302
43.205.24 4302
13.301.33 4302
49.854.88 4302
49.854.88 4302
49.854.88 4302
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
40.00
 | Subconhact Uncommitted
Subconhact Uncommitted | 5C000
5C000
5C000
5C5000
5C50003
5C50004
5C50004
5C50004
5C50005
5C50005
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subplier (100mm Gdf w. 3.5 mpc)
Supplier (100mm Gdf Uncoper
Supplier) (100mm Gdf Uncoper
Subcontract Uncommitted | Sum
Sum
Mill
And
Anno
Anno
Anno
Anno
Anno
Anno
Anno | 43.005
15.301
49.555
8 11
8 1
2
120
120 | 1
1
14.45
177.4
420
377.5
420
377.5
30.00 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
1
1
1
1
1 | 0
5
5
5
5
0 | North Surfit Parade (Romp)
Platform
North Surfit Parade (Romp)
North Surfit Parade (Romp)
Platform
Platform | 2183
2183
2183
2183
2183
 | C28
C38
C38
C38
C38
 | Ciff Rovie (Maform)
Ciff Rovies (Rail Contacy)
Bectical Phi (Malform)
Bectical Phi (Malf Contacy)
Ciff Rovies (Rail Contacy)
 | m
nos
m
m | 76
3
8 | 563.54
568.49
5,100.43
6.231.86
370.65 | 281,177,00 4300
43,205,34 4500
13,501,33 4500
47,554,88 4500
49,554,88 4500
4500
4500
4500
4500
4500
4500
4500
 | Subconheat: Uncommitted
Subconheat: Uncommitted | \$C000
\$C000
\$C000
\$C5001
\$C5002
\$C5003
\$C5005
\$C5005
\$C5000
\$C5000
\$C5000
 | Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subcontract Uncommitted
Subplied I Otom GM on new pool
Supply of Oto Sub Company
Instel of Otom GM Despen
Instel of CM Subtraction
Subcontract Uncommitted
Subcontract Uncommitted | Sam
Sam
Min
Mi
Mi
Mi
Mi
Mi
Mi
Mi
Mi
Mi
Mi
Mi
Mi
Mi | 43.005
15.301
49.555
8 11
8 1
2
120
120 | 1
1
14.45
775.4
400
775.5
400
775.5
400
775.5
400
945 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | | North Ardff Parada (Ramp)
Partiam
North Ardff Parada (Ramp)
North Ardff Parada (Ramp)
Partiam
Partiam | 2183
2183
2183
2183
2183
2183
2183
 |
 | Cit Rover (Hellow)
Cit Rover, Hell Cantado
Beccard Hyll Cantado
Beccard Hyll Cantado
Cit Rover, Hell Cantado
Cit Rover, Hell Cantado
Under Tool Cantago
Additional Cantado Hyll Rover, Hard Hyll Cantado
androg Harden Station (Cit Rover, Hyrl Rover, Hyll Cantado
Cantador Stational Cantado Hyrl Partieller)
Edditional Stational Cantado Hyrl Partnerich
 | m
nos
m
m | 76
3
8 | 543.34
548.49
3.100.45
4.231.84
370.45
12.330.00 Role of
543.34 Role of
3.102.45 Role of | 28.177.00 452
43.003.4 450
15.501.33 450
49.854.88 450
49.854.88 450
49.854.88 450
450
450
450
450
450
450
450
450
450
 | Advanted becommended
Advanted becommended | 5000
3000
3000
3000
3000
3000
3000
3000
 | Saconhad Texamilia
Extransa Texamilia
Saconhad Texamilia
Saconhad Texamilia
Saconhad Texamilia
Saconhad Texamilia
Saconhad Texamilia
Saconhad Texamilia
Saconhad Texamilia
Saconhad Texamilia | Sam
Sam
Ma
Ma
Ma
Ma
Ma
Ma
Ma
Ma
Ma
Ma
Ma
Ma
Ma | 4305
13301
8 11
8 1
3
3
3
3
3
3 | 1
1
44.6
420
420
420
420
420
420
420
420
420
420 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 0
5
5
5
5
0
0
0 | North Surfit Parade (Romp)
Platform
North Surfit Parade (Romp)
North Surfit Parade (Romp)
Platform
Platform | 2183
2183
2183
2183
2183
2183
2183
 | C2F
C5F
C4F
C4F
C4F
C4F
C4F
C4F
C4F
 | Call Routes (Hallow)
Call Routes (Hall Canada)
Routes and Pay (Hallow)
Routes (Hall Canada)
Call Routes (Hall Canada)
Call Routes (Hall Canada)
Additional Call Routes (Hall Routes)
Additional Call Routes (Hall Routes)
 | m
nos
m
m | 76
3
8 | 563.54
566.49
3,102.45
4,231.86
370.45
12,300.00 Role of
563.54 Role of | 28.177.00 4322
43.203.24 4322
13.20.33 602
43.503
43.502
43.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
42.502
 | Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter
Accorded becomenter | \$C000
\$C000
\$C000
\$C5001
\$C5002
\$C5003
\$C5005
\$C5005
\$C5000
\$C5000
\$C5000
 | Accentral toxomited
Sciences toxomited | Sam Sam Sam Sam A A A A A A A A A A A A A A A A A A A | 4325
13391
8 1
8 1
12
12 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | | North Ardff Parada (Ramp)
Partiam
North Ardff Parada (Ramp)
North Ardff Parada (Ramp)
Partiam
Partiam | 2183
2183
2183
2183
2183
2183
2183
 |
 | Cit Rover (Hellow)
Cit Rover, Hell Cantado
Beccard Hyll Cantado
Beccard Hyll Cantado
Cit Rover, Hell Cantado
Cit Rover, Hell Cantado
Under Tool Cantago
Additional Cantado Hyll Rover, Hard Hyll Cantado
androg Harden Station (Cit Rover, Hyrl Rover, Hyll Cantado
Cantador Stational Cantado Hyrl Partieller)
Edditional Stational Cantado Hyrl Partnerich
 | m
nos
m
m | 76
3
8 | 543.34
548.49
3.100.45
4.231.84
370.45
12.330.00 Role of
543.34 Role of
3.102.45 Role of | 28.1172 483
43.2554 403
43.2554 003
43.2554 003
43.255
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
43.25
 | Accorded becommined
belacented becommined |
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000 | Accentral treammine
Second to the second se | Sam Sam An | 4325
1330
4035
8 1
9
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
1
1
2
2
2
2
3
3
3
3
3
3
3
3
3
3
3
3
3 | | North Ardff Parada (Ramp)
Partiam
North Ardff Parada (Ramp)
North Ardff Parada (Ramp)
Partiam
Partiam | 2183
2183
2183
2183
2183
2183
2183
2183
 |
 | Cit Rover (Hellow)
Cit Rover, Hell Cantado
Beccard Hyll Cantado
Beccard Hyll Cantado
Cit Rover, Hell Cantado
Cit Rover, Hell Cantado
Under Tool Cantago
Additional Cantado Hyll Rover, Hard Hyll Cantado
androg Harden Station (Cit Rover, Hyrl Rover, Hyll Cantado
Cantador Stational Cantado Hyrl Partieller)
Edditional Stational Cantado Hyrl Partnerich
 | m
nos
m
m | 76
3
8 | 543.34
548.49
3.100.45
4.231.84
370.45
12.330.00 Role of
543.34 Role of
3.102.45 Role of | 32.17.20 600 43.03.34 600 43.03.44 600 45.04 600 45.04 600 42.05.44 600 42.05.44 600 42.05.44 600 400 400 <td>Advantus beammine
Advantus beammine</td> <td>1000
1000
1000
1000
1000
1000
1000
100</td> <td>Locartes l'ocarrente Locartes l'ocart</td> <td>Sam Sam Sam Sam Sam Sam Sam Sam Sam Sam</td> <td>4325
13391
8 11
8 11
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td> <td>1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1</td> <td>28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8</td>
 | Advantus beammine
Advantus beammine | 1000
1000
1000
1000
1000
1000
1000
100 | Locartes l'ocarrente Locartes l'ocart | Sam
 | 4325
13391
8 11
8 11
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8 |
| 2
2
2
2
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3 | | Nach Jarih Panala (Rang)
Padiam
Nach Jarih Panala (Pana)
Nach Jarih Panala (Pana)
Padiam
Padiam
Nach Jarih Panala (Pang) | 2183
2183
2183
2183
2183
2183
2183
2035
 | ca
ca
ca
ca
ca
ca
ca
ca
ca
ca
ca
ca
ca
c
 | Cit Ruose (Hosten)
Cit Ruose (Host Cites)
Ruckard Pa (Hosten)
Cites (Hosten (Hosten)
Cites (Hosten (Hosten)
Additional (Scholar (Hosten)
Additional (Scholar (Hosten)
Additional (Scholar (Hosten)
Additional (Scholar (Hosten)
Cites | н
пол
по
по
по
по
по
по
по
по
по
по
по
по
по | 76
3
8 | 53.34
54.47
5.100.45
4.231.84
370.45
370.45
8.100.45
8.100.45
8.100.45
8.100.45
8.100.45
 | 12,117.00 240.00 4,20.00.00 40.00 12,01.10 40.00 2,245.40 40.00 2,245.40 40.00 4,000.00 40.00
 | Advantus bearmined
Advantus bearmined | 1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000 | Accenter Learning and the second and | Sam
Sam
Sam
Ma
Ma
Ma
Ma
Sam
Sam
Sam
Sam
Sam
 | 4325
13391
8 11
8 11
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1 1 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8 |
| 2
2
2
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3 | | Nach Anfil Pansis (Ramp)
Patiem
Nach Anfil Pansis (Ramp)
Nach Anfil Pansis (Ramp)
Patiem
Patiem
Patiem
Patiem
Nach Aufil Pansis (Ramp) | 2183
2183
2183
2183
2183
2183
2183
2035
 | cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
c
 | Cit Ruwa (Hatwa)
Cit Ruwa (Hatwa)
Ruskuch Na (Hatwa)
Cit Ruwa (Hat Cursis)
Cit Ruwa (Hat Cursis)
Under host Cursing
Analyza (San Kathan (Hatwa)
Analyza (San Kathan)
Cit Ruwa (Hat Cursis)
Cit Ruwa (Hat Cursis)
 | н
пол
по
по
по
по
по
по
по
по
по
по
по
по
по | 76
3
8 | 54334
546.49
3.100.45
4.231.86
3.70.45
3.70.45 Role of
3.70.45 Role of
12.300.05 Role of
12.300.00 Role of | 12,117.00 2000 4,2003.00 400 4,2003.00 400 4,2003.00 400 4,2003.00 400 4,2003.00 400 4,2003.00 400 4,2003.00 400 4,2003.00 400 4,000 400
 | Adorshal beamful
Adorshal beamful |
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000 | Accentral treammine
Accentral | Sam Sam Sam An | 4325
13391
8 11
8 11
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1 1 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8
 |
| 2
2
2
2
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3 | | Nach Anfil Pansis (Ramp)
Patiem
Nach Anfil Pansis (Ramp)
Nach Anfil Pansis (Ramp)
Patiem
Patiem
Patiem
Patiem
Nach Aufil Pansis (Ramp) | 2183
2183
2183
2183
2183
2183
2183
2035
 | cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
c
 | Cit Roves (Marken)
Cit Roves (Marken)
Backscart Ry (Marken)
Cit Roves (Marken)
Cit Roves (Marken)
Cit Roves (Marken)
Additional Cit Roves for selected on
Additional Cit Roves for selected on
Cit Roves (Marken)
Cit Rov | н
пол
по
по
по
по
по
по
по
по
по
по
по
по
по | 76
3
8 | 54334
546.49
3.100.45
4.231.86
3.70.45
3.70.45 Role of
3.70.45 Role of
12.300.05 Role of
12.300.00 Role of
 | 11.1112 200.1 4.200.2 400 4.200.2 400 11.111.1 400 2.445.2 400 2.445.2 400 4.200
 | Adorshal beamful
Adorshal beamful | 1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000 | Accentral treammine
Accentral treammine
Accentral treammine
Accentral treammine
and accentral treammine
Accentral treammine
Accen | Sam Sam Sam An
 | 4325
13391
8 11
8 11
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1 1 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8 |
| 2
3
3
3
4
3
3
3
3
3
3
3
3
3
3
3
3
3
3
3 | | Nach Anfil Pansis (Ramp)
Patiem
Nach Anfil Pansis (Ramp)
Nach Anfil Pansis (Ramp)
Patiem
Patiem
Patiem
Patiem
Nach Aufil Pansis (Ramp) | 2183
2183
2183
2183
2183
2183
2035
2035
 | cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
cs
c
 | Cit Roves (Muters) Cit Roves (Mu | | 76
3
8 | 54334
546.49
3.100.45
4.231.86
3.70.45
3.70.45 Role of
3.70.45 Role of
12.300.05 Role of
12.300.00 Role of
 | 11.1112 200.1 4.200.2 400 4.200.2 400 11.111.1 400 2.445.2 400 2.445.2 400 4.200
 | Adorshal beamful
Adorshal beamful | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | Adapted (Learning)
Adapted (Learning)
Adapte | Sam Sam Sam An
 | 4325
13391
8 11
8 11
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1 1 1 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 | 28,177.00
43,205.24
15,301.35
49,854.88
915.6
1,411.30
108
231
100.8 |
| | | Indebulli Panala (Bars)
Panam
Nath Ball Panala (Bars)
Indebulli Panala (Bars)
Panam
Panam
Panam
Nath Ball Panala (Pana)
Indebulli Panala (Pana)
Indebulli Panala (Pana) | 2183
2183
2183
2183
2183
2183
2183
2035
2035
2035
2037
2047
2047
2047
2047
2047
2047
 | C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C
 | Cit Ruce (Helsen) Cit Ruce (He | | 76
3
8
8
8 | 1334
1364
1304
1304
1304
1304
1304
1304
1304
100
100
 | 32.17.28 ABB 42.95.34 ABB 42.95.44 ABB 2.43.25 ABB 2.43.25 ABB 4.99 ABB 4.99 <td< td=""><td>Adorbed beambined
Adorbed beambined</td><td>1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000</td><td>Accentral transmitter Accentral transmitter</td><td>Sam Sam Sam Sam Sam Sam Sam Sam Sam Sam</td><td>4305
1530
#33
* 1
* 1
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3</td><td>1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1</td><td>28.17720
43.023.04
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.17.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26</td></td<>
 | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000 | Accentral transmitter | Sam | 4305
1530
#33
* 1
* 1
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 |
28.17720
43.023.04
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.17.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26 |
| 2
2
2
2
2
2
2
2
2
2
2
2
2
2
2
2
2
2
2 | | Nach Jaciff Pasala (Bars)
Patian
Nach Jaciff Pasala (Bars)
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian
Patian | 2183
2183
2183
2183
2183
2183
2183
2035
2035
2035
2037
2047
2047
2047
2047
2047
2047
 | C3
C4
C4
C4
C4
C4
C4
C4
C4
C4
C4
 | Cit Route (Huters) Cit Route (Huters) Cit Route (Hut Cantos) Cit Rou | | 76
3
8
8 |
13334
14647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367 | A.1012 A ADB A.2012 A ADB A.2012 A ADB J.3012 A ADB J.3012 A ADB J.2012 A ADB ADB ADB <
 | Adorded beamful a | 1000
2000
2000
2000
2000
2000
2000
2000 | Accentral transmitter
 | Sam | 4305
1530
8 1
3
3
3
3
3
3
0
1
3
1
3
1
3
1
3
1
3
1
3 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28.1770
43.2554
43.2554
49.5548
14.1120
21
21
21
21
21
21
21
21
21
21
21
21
21 |
| | | Indeb Addit Pasada (Barq)
Padiam
Narth Addit Pasada (Barq)
Andh Addit Pasada (Barq)
Padiam
Padiam
Padiam
Narth Addit Pasada (Barq)
Narth Addit Pasada (Barq)
Narth Addit Pasada (Barq)
Narth Addit Pasada (Barq)
Narth Addit Pasada (Barq) | 2183
2183
2183
2183
2183
2183
2183
2035
2035
2035
2037
2047
2047
2047
2047
2047
2047
 | C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C
 | Cit Ruos (Putron)
Cit Ruos (Putron)
Ruccarto (Putron)
Cit Ruos (Put | | 76
3
8
8
8 |
13334
14647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.33647
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367
1.3367 | A.10.10.1 A A.20.10.2 A
 | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000 | Lacartard Incomined
Lacartard
Incomined
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
Development
De | Sam | 4305
1530
#33
* 1
* 1
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28.17720
43.023.04
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.17.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26 |
| | | Indek kell Parake (kars)
Parlam
Indek kell Parake (kars)
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
P | 2183
2183
2183
2183
2183
2183
2183
2183
 | C3
C4
C4
C4
C4
C4
C4
C4
C4
C4
C4
 | Cit Ruos (Mutani) Cit Ruos (Mu | | 76
3
8
8
8 | 1334
1404
1004
1004
1004
1004
1000 feet
1000 feet
1000 feet
1000
100
100
100
 | Ja. 17. 12 AB A.2002. M AB A.2002. M AB J.2.44. M AB J.2.44. M AB J.2.44. M AB A.2002. M AB AB AB
 | Advanted beammined
Advanted beammined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | Adapted Fourther
 | Sam | 4305
1530
#33
* 1
* 1
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28.17720
43.023.04
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.17.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26 |
| | | Indekkell Paradas (karas)
Parlam
Indekkell Paradas (karas)
Parlam
Parlam
Parlam
Parlam
Parlam
Indekkell Paradas (karas)
Parlak kell Paradas (karas)
Parlak kell Paradas (karas)
Parlam
Parlam | 2183
2183
2183
2183
2183
2183
2183
2183
 | C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C
 | Cit Ause (Marian) Cit Ause (Ma | | 76
3
8
8
8 | 1334
1404
1004
12050 fete
3334
12050 fete
3334 fete
3334 fete
3334 fete
3334 fete
3334 fete
3334 fete
3334 fete
 | Ja. 17. 12 AB A.2002. M AB A.2002. M AB J.2.44. M AB J.2.44. M AB J.2.44. M AB A.2002. M AB AB AB
 | Adorded beamfail
Adorded beamfail | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotexted i searched biotexte | Sam Sam Sam A A A A A A A A A A A A A A A A A A A
 | 4305
1530
#33
* 1
* 1
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3
* 3 | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 28.17720
43.023.04
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.17.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26
97.16.26 |
| | | Indebaddi Pasada (Bara)
Padam
North Melli Pasada (Bara)
Padam
Padam
Padam
Padam
Padam
Padam
Padam
Pada (Bara)
Pada | 2133
2143
2143
2143
2143
2143
2143
2143
 | C3
C4
C4
C4
C4
C4
C4
C4
C4
C4
C4
 | Citatus (Maran)
Citatus (Maran)
Citatus (Maran)
Citatus (Maran)
Citatus (Maran)
Citatus (Maran)
Adduct Citatus (Maran)
Adduct (Maran)
Citatus (Maran) | | 76
3
8
9
24
1
9 | | Sulfation Autore Autore Autore

 | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotection to constrain the section of the section | kan kan | 4305
1330
1330
13
1
8
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | I I |
24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03 |
| | | Indebaddi Pasada (Bara)
Padaa
North Matti Pasada (Bara)
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Padaa
Pada | 2123
2123
2123
2123
2123
2125
2125
2125
 | C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C
 | Citatus (Marian) Citatu | | 76
3
8
9
24
1
9 |
 | Jali Jali Jali Jali Jali Jali Jali Jali
 | Adorbed beambaile
Adorbed beambaile | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotection to constrain the section of the section | kan kan
 | 4335
1339
6 33
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | I I | 21.172
4.353.4
4.353.4
1.435.4
1.112
1.12
1.12
1.12
1.12
1.12
1.12
1 |
| | | Indekkell Paradas (Bares)
Parlam
Indekkell Paradas (Bares)
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam
Parlam | 2133
2143
2143
2143
2143
2143
2143
2143
 | C3
C4
C4
C4
C4
C4
C4
C4
C4
C4
C4
 | Citava (Mara)
Citava | | 76
3
8
9
24
1
9 |
 | Sulfation Autore Autore Autore
 | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotection to constrain the section of the section | kan kan | 4305
1330
1330
13
1
8
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | I I |
24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03 |
| | | Nuchardi Parata (ana)
Partam
Nuchardi Parata (ana)
Partam
Partam
Partam
Partam
Partam
Partam
Nuchardi Parata (ana)
Parta hardi Parata (ana)
Parta | 2133
2133
2133
2133
2133
2135
2135
2135
 | C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C
 | Citava (Mara)
Citava | | 76
3
8
9
24
1
9
9 | | Sulfation Autore Autore Autore

 | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotection to constrain the section of the section | kan kan | 4305
1330
1330
13
1
8
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | I I |
24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03 |
| | | Nuchardi Parata (ana)
Partam
Nuchardi Parata (ana)
Partam
Partam
Partam
Partam
Partam
Partam
Nuchardi Parata (ana)
Parta hardi Parata (ana)
Parta | 2183
2183
2183
2183
2183
2183
2183
2183 | ся
ся
ся
ся
ся
ся
ся
ся
ся
ся | Circus (Mules) Circus (| | 76
3
8
8
1
1
9
1
1
1
1 | 1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1 | A.10.12 A ABA A.20.25 A A.20.25 A </td <td>Adorbed beambined
Adorbed beambined</td> <td>1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2</td> <td>biotection to constrain the section of the section</td> <td> kan kan</td> <td>4305
1330
1330
13
1
8
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td> <td>I I</td> <td>24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03</td> | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotection to constrain the section of the section | kan kan | 4305
1330
1330
13
1
8
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | I I | 24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03 |
| | | Nuchardi Parata (ana)
Partam
Nuchardi Parata (ana)
Partam
Partam
Partam
Partam
Partam
Partam
Nuchardi Parata (ana)
Parta hardi Parata (ana)
Parta | 2133 2143 <td>ся
ся
ся
ся
ся
ся
ся
ся
ся
ся</td> <td>Circus (Mules) Circus (</td> <td></td> <td>76
3
8
8
1
1
9
1
1
1
1</td> <td>1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1</td> <td>A.1015 A ABA A.2015 A</td> <td>Adorbed beambined
Adorbed beambined</td> <td>1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2</td> <td>biotection to constrain the section of the section</td> <td>Sam Sam Sam <!--</td--><td></td><td></td><td>24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03</td></td> | ся
ся
ся
ся
ся
ся
ся
ся
ся
ся | Circus (Mules) Circus (| | 76
3
8
8
1
1
9
1
1
1
1 | 1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1 | A.1015 A ABA A.2015 A | Adorbed beambined
Adorbed beambined | 1000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
200
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2000
2 | biotection to constrain the section of the section | Sam Sam </td <td></td> <td></td> <td>24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03</td> | | | 24.1729
43.8324
13.933
93.434
93.43
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03
13.03 |
| | | Inde Aufil Pausia (Bars)
Padiam
Inde Aufil Pausia (Bars)
Padiam
Padram
Padram
Padram
Padra Pausia (Paus)
Padra Pausia (Paus)
Padra Pausia (Paus)
Padra Pausia (Paus)
Padra Pausia (Paus)
Padra Pausia (Paus)
Padram
Padram Pausia (Paus)
Padram
Padram Pausia (Paus)
Padram
Padram Pausia (Paus)
Padram
Padram Pausia (Paus)
Padram Padram Pausia (Paus)
Padram Padram | 2123
2123
2123
2123
2123
2123
2123
2123
 | C3
C4
C4
C4
C4
C4
C4
C4
C4
C4
C4
 | Cirkus (Mara) | | 76
3
8
8
1
1
9
1
1
1
1
1 |
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14
1.0.14 | Suito 20 Aussi 20 Aussi 20 A
 | Adorhed beaming in a second beaming in a secon | 1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
100
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1000
1 | biotectical incominents
incominent incominent
incominent incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominent
incominen | Sam Sam </td <td></td> <td></td>
<td>24.17.27
44.325.34
44.325.34
44.324.34
14.12
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.</td> | | | 24.17.27
44.325.34
44.325.34
44.324.34
14.12
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10.21
10. |
| | | hashadi Pasak (kan)
Padam
Induk Hali Pasak (kan)
Padam
Padam
Induk Hali Pasak (kan)
Padam
Padam
Padam
Padam Pasak (kan)
Padam Padam Padam Pasak (kan)
Padam Padam | 2023 2023 2023 2023 2023 2023 2025 2025 2027 2028 2029 <td>C3 C4 C5 C6 C7 C6 C7 C7 <td>Citolau (Mulan) Citolau (Mulan) Citol</td><td></td><td>76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td><td></td><td>Jali Jali Jali Jali Jali Jali Jali Jali</td><td>blooken bernmannen
blooken bernmannen
blook</td><td></td><td>Austration Austration A</td><td>Sam Sam Sam <!--</td--><td></td><td></td><td>24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.21 2
1.2</td></td></td> | C3 C4 C5 C6 C7 C6 C7 C7 <td>Citolau (Mulan) Citolau (Mulan) Citol</td> <td></td> <td>76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td> <td></td> <td>Jali Jali Jali Jali Jali Jali Jali Jali</td> <td>blooken bernmannen
blooken bernmannen
blook</td> <td></td> <td>Austration Austration A</td> <td>Sam Sam Sam <!--</td--><td></td><td></td><td>24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.21 2
1.2</td></td> | Citolau (Mulan) Citol | | 76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | | Jali Jali Jali Jali Jali Jali Jali Jali | blooken bernmannen
blooken bernmannen
blook | | Austration A | Sam Sam </td <td></td> <td></td> <td>24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.21 2
1.2</td> | | | 24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.21 2
1.2 |
| | | hashadi badi padak (panj
pada badi Padak (panj | 2023 2023 2023 2023 2023 2023 2025 2025 2027 2028 2029 <td>ся
ся
ся
ся
ся
ся
ся
са
са
са
са
са
са
са
са
са
са</td> <td>Circus (Mutan) Circus (</td> <td></td> <td>76
3
8
8
1
1
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td> <td>1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1</td> <td>Jali Jali Jali Jali Jali Jali Jali Jali</td> <td>bicedeta becomeda bicedeta be</td> <td></td> <td>biotectical incomination of the section of the sect</td> <td>Sam Sam <td< td=""><td></td><td></td><td>24.173 74
4.353 24
4.353 24
1.243 24
1.243 24
1.253 25
1.243 24
1.253 24
1.254 24
1.</td></td<></td> | ся
ся
ся
ся
ся
ся
ся
са
са
са
са
са
са
са
са
са
са | Circus (Mutan) Circus (| | 76
3
8
8
1
1
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | 1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1.1.4
1.1 | Jali Jali Jali Jali Jali Jali Jali Jali | bicedeta becomeda bicedeta be | | biotectical incomination of the section of the sect | Sam Sam <td< td=""><td></td><td></td><td>24.173 74
4.353 24
4.353 24
1.243 24
1.243 24
1.253 25
1.243 24
1.253 24
1.254 24
1.</td></td<> | | | 24.173 74
4.353 24
4.353 24
1.243 24
1.243 24
1.253 25
1.243 24
1.253 24
1.254 24
1. |
| | | hashadi Pasak (kan)
Padam
Induk Hali Pasak (kan)
Padam
Padam
Induk Hali Pasak (kan)
Padam
Padam
Padam
Padam Pasak (kan)
Padam Padam Padam Pasak (kan)
Padam Padam | 2023 2023 2023 2023 2023 2023 2025 2025 2027 2028 2029 <td>C3 C4 C5 C6 C7 C6 C7 C7 <td>Circus (Puice) Circus (</td><td></td><td>76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td><td></td><td>A.102.03 ABA A.202.03 ABA A.202.04 ABA</td><td>bicontext becomental bicontext becomental bicontex</td><td></td><td>Austration Austration A</td><td>Sam Sam Sam <!--</td--><td></td><td></td><td>24.173 4
4.353 4
4.353 4
4.353 4
1.423 4
1.423 4
1.025 1
1.025 1
1.025</td></td></td> | C3 C4 C5 C6 C7 C6 C7 C7 <td>Circus (Puice) Circus (</td> <td></td> <td>76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td> <td></td> <td>A.102.03 ABA A.202.03 ABA A.202.04 ABA</td> <td>bicontext becomental bicontext becomental bicontex</td> <td></td> <td>Austration Austration A</td> <td>Sam Sam Sam <!--</td--><td></td><td></td><td>24.173 4
4.353 4
4.353 4
4.353 4
1.423 4
1.423 4
1.025 1
1.025 1
1.025</td></td> | Circus (Puice) Circus (| | 76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | | A.102.03 ABA A.202.03 ABA A.202.04 ABA | bicontext becomental bicontex | | Austration A | Sam Sam </td <td></td> <td></td> <td>24.173 4
4.353 4
4.353 4
4.353 4
1.423 4
1.423 4
1.025 1
1.025 1
1.025</td> | | | 24.173 4
4.353 4
4.353 4
4.353 4
1.423 4
1.423 4
1.025 1
1.025 |
| | | hashadi Pasak (kan)
Padam
Induk Hali Pasak (kan)
Padam
Padam
Induk Hali Pasak (kan)
Padam
Padam
Padam
Padam Pasak (kan)
Padam Padam Padam Pasak (kan)
Padam Padam | | C3 C4 C5 C6 C7 C6 C7 C7 <td>Circule (House) Circule (House) Circu</td> <td></td> <td>76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1</td> <td></td> <td>Jali Jali Jali Jali Jali Jali Jali Jali</td> <td>bicontext becomental bicontext becomental bicontex</td> <td></td> <td>Austration Austration A</td> <td>Sam Sam Sam <!--</td--><td></td><td></td><td>24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.213 1
1.112 1
1.023 1
1.023</td></td> | Circule (House) Circu | | 76
3
8
8
8
9
7
4
1
7
9
7
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1
1 | | Jali Jali Jali Jali Jali Jali Jali Jali | bicontext becomental bicontex | | Austration A | Sam Sam </td <td></td> <td></td> <td>24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.213 1
1.112 1
1.023 1
1.023</td> | | | 24.173 2
4.353 4
4.353 4
4.353 4
1.413 2
1.213 1
1.112 1
1.023 |
| | | Inde And II Parata (Para)
Partine
Inde And II Parata (Para)
Partine
Inden
Inden
Inden
Inden Inden (Para)
Inden Inden (Para)
Inden Inden (Para)
Inden Inden (Para)
Inden Inden (Para)
Inden Inden Inden (Para)
Inden Inden Inden (Para)
Inden Inden Inden (Para)
Inden Inden Inden Inden
Inden Inden Inden Inden Inden
Inden Inden Inden Inden Inden
Inden Inden Inden Inden Inden
Inden Inden Inden Inden Inden Inden
Inden Inden In |
 | C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C3
C
 | Circule (Refau) Circu | | |
 | A.101.01 A A
 | Aborbed becomested
becomested becomested
bec | | biotecte i conserve de la conserve d | Imm Imm </td <td></td> <td></td> <td>24.17.24
4.32.34
4.32.34
4.34.34
4.34.34
1.32
1.32
1.32
1.32
1.32
1.32
1.32
1.32</td> | | | 24.17.24
4.32.34
4.32.34
4.34.34
4.34.34
1.32
1.32
1.32
1.32
1.32
1.32
1.32
1.32
 |

15	North Burfit Parade (Ramp)		Landscaping	Kerb and Gutter- K+G Type	m	60.1	184.87	11,110.69 6302	Subcontract Uncommitted	SC23104	Kerb and Gutter (Bearrs Ave): K		40	184.87	11,110.49
15	North Burfitt Parade (Ramp)		Landscaping	Concrete Footpath	m2	32.4	147.43	4,776.73 6302	Subcontract Uncommitted	5C23102	Concrete Footpath (North Para		32	147.43	4,776.73
15	North Burfitt Parade (Ramp) North Burfitt Parade (Ramp)		Landscaping	Raised Pedestrian Crossing Linemarking & Signages	nos	,	42,635.00 Rote	5,000.00 6302	Subcontract Uncommitted	5C23112 5C006	New Raised Pedestrian Crossing	ea /hem	5,000	42,635.00	5,000.00
	non com racon (kanp)	2020	Lanacoping	Design development 30/10/2018			3,000.00	3,00000 8302	accontect or continuing	30000	Chinada	Jumin	3,000		2,000.00
15	North Burfitt Parade (Ramp)	2035	Landscaping	Miling, re-sheeting road surface, regrade associated footpath access on both sides &	hem	1	17,100.00	17,100.00 6302	Subcontract Uncommitted	50006	Civil Works	/hem	17,100	1	17,100.00
				associated footpath access on both sides & add tactle indicators at crossing											
4				Paving & Finishes											
4				Bicycle Rocks/Shellers											
4				Sheet Furniture											
4				Bolustrades & Screens											
4	Project Wide	2035	Landscaping	Fencing Polisade Fence	m		469.51 Rote	only 6302	Subcontract Uncommitted	50006	Civil Works	/hem		1	
4				External Stormwater				45,370.43				1			
5				Burlitt Parade				45,370.63							
15	North Burfit Parade (Ramp)	2035	Landscaping	New 375mm dia RCP Drainage Pipes	m	8	432.94	3,463.52 6302	Subcontract Uncommitted	5C23109	New Drainage Line (450mm dia	RCI m	8	432.94	3,463.52
15	North Burfit Parade (Ramp)		Landscaping	New SA Kert inlet Pit	nos	1	3,935.00	3,935.00 4302	Subcontract Uncommitted	5C23110	New Drainage Pits (Kerbs Inlet)		1	3,935.00	3,935.00
15	North Burfitt Parade (Ramp)	2035	Landscaping	Rock Channel Lining and Rip Rap (D=50=100)	m2		255.53 Rote	only 6302	Subcontract Uncommitted	5C000	Subcontract Uncommitted	Sum		1	
15	North Burfit Parade (Ramp)	2035	Landscaping	Replace existing Sealed Covers with Durham Class D Heelguard Grating & frame	m	9	695.79	6,262.11 6302	Subcontract Uncommitted	5C000	Subcontract Uncommitted	Sum	6,262	1	4,242.11
				Cas o needoara Graing & name											
c				Design development 30/10/2018											
15	North Burfit Parade (Ramp)	2035	Landscaping	Additional 375mm dia RCP & pits along Buffit Parade	15	1	12,060.00	12,060.00 6302	Subcontract Uncommitted	SC50102	Civil Work	/bem	12,060	1	12,040.00
15	North Burfitt Parade (Ramp)	2035	Landscaping	Additional 250mm dia UPVC pipes & pits nea entrance	r 13	1	19,650.00	19,650.00 6302	Subcontract Uncommitted	SC50102	Civil Work	/bem	19,650	1	19,650.00
4				Other Services (electrical, water, sewer,											
4				gas) Landscoping											
3				Linascoping				908,411.13							
4				Insitu Concrete Structures				47,929.71							
e				following are subcontract allowances,											
				contractor preliminaries, overheads & margin are separately allowed for											
c				Works generally undertaken during normal hours. Where works are to be undertaken											
				during passession or out of hours, see "markup"											
c				Temporary pump line conduits from pump location to platforms by Downer,											
				subcontractor to run pump lines as required											
c				Temporary concrete washout facility/provisions by Managing Contractor (Dense), actuationalise to a second line as											
				(Downer), subcontractor to run pump lines as required											
c				Significant material handling to/from platforms by Contractor											
c				Scaffolds to lift cores, footbridge & stairs											
				provided by Contractor, other installation scattalds (modular & mobile types) by each respective trade subcontractor											
5				Lift 1 - Platform				47,929.71							
c				Concrete											
20	Platform	2401	Shuctural FRP	In-situ blinding layer - 50mm thick	m2	33	159.31	5,257.23 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	5.257	1	5,257.23
20	Platform	2401	Structural FIP	40MPa concrete in Lift Pit Base/Pile Cap, Xypex	m3	14	989.75	13,856.50 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	13,857	1	13,856.50
20	Platform	2401	Shuctural FRP	40MPa concrete in lift pit wals, Xypex	m3	9	1,302.62	11,723.58 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	11,724	1	11,723.58
20	Platform	2401	Structural FIP	40MPa concrete in lift shaft walls - 1200mm high	m3	4	2,019.60	8,078.40 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	8,078	1	8,078.40
				rign Formwork											
20	Platform	2401	Structural FRP	Formwork to sides of Lift Pit Base/Pile Cap	m2	11	250	2,750.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/hem	2,750	1	2,750.00
	Platform	2401	Structural FRP	600 deep form sump in pit base	No.	,	350	350 6302	Subcontract Uncommitted	50021	Gienbrook Packages	/hem	350	1	350
20	Platform	2401	Shuchard FRP	formwork to sides of lift pit walls	m2	39	250	9,750.00 4302	Subcontract Uncommitted	50021	Glenbrook Packages	/bern	9,750	1	9,750.00
20	Platform	2401	Structural FRP	Formwork to sides of lift shaft walls	m2	31	250	7,750.00 4302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	7,750	1	7,750.00
20	Platform	2401	Structural FRP	Form opening in wall approx. 1100 wide x 1200 high	No.	1	450	450 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	450	1	450
				Reinforcement											
20	Platform	2401	Structural FIP	Reinforcement in Lift Pit Base/Pile Cap	t.	1.5	3,600.00	5,400.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	5,400	1	5,400.00
20	Platform	2401	Structural FRP	Reinforcement in lift pit walls	t.	1.5	3,600.00	5,400.00 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	5,400	1	5,400.00
20	Platform	2401	Structural FRP	Reinforcement in lift shaft walk	t.	0.6	3,600.00	2,160.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/bem	2,160	1	2,160.00
c				Concrete Joints											
20	Platform	2401	Structural FRP	Watestop joint in lift pit	m	14	160	2,240.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/tem	2,240	1	2,240.00
20	Platform	2401	Structural FRP	Expansion joint between new landing slab (lift lobby) and existing footbridge including cover plate	and	3	750	2,250.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	, dem	2,250	1	2,250.00
20	Platform	2401	Structural FRP	Tie in works with new / existing structures	Item	,	1,500.00	1,500.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	1,500	1	1,500.00
¢				Cast Ins											
20	Platform	2401	Structural FRP	Cost in Lift unstruts - insitu	Shaft	1	900	900 6302	Subcontract Uncommitted		Glenbrook Packages	/item	900	1	900
20	Platform	2401	Structural FRP	Stray monitoring point	Item	1	500	500 6302	Subcontract Uncommitted	SC021	Gienbrook Packages	/item	500	1	500
e 20	Platform	2401	Structural FRP	Design Development 30/10/2018 Reduce IIII shaft height by 735mm	15		-12,386.00	-12,386.00 6302	Subcontract Uncommitted		Glenbrook Packages	(tem	-12,386		-12,386.00
20 5	- Nerverth	-	and and PRP	Reduce lift shaft height by 735mm OHW Support Stanchion			-1.06.UJ	12,200,00 6302	avacontract uncommitted	accust 1	Uner La VOK POCKOges	,	-12,300	1	-12,386.00
				Awailing design for OHW Support Stanchion -											
				allow 750mm pile with 1200x 1200x 600mm deep pile cap											
¢				Assume concurrent with Lift pit works Concrete											
20	Matform	2401	Structural FRP		m2		159.31 Rote	only 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/hem		1	
20	Matform	2401	Structural FRP		m3		2,019.60 Rote		Subcontract Uncommitted		Glenbrook Packages	/item		1	
20	Matform	2401	Structural FRP	Formwork to sides of Pile Cap 600 deep Reinforcement	m2		250 Rote	only 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/hem		1	
20	Nation	2401	Structural FIP				3,600.00 Rote	only 6302	Subcontract Uncommitted	SC021	Gienbrook Packages	/item		1	
5				Salar Panel Mounting Foundations											
c				Location of Solar Panel Mounting to be advised, if located on south bank of rail											
				conidor (as currently proposed) will require foundations for panel mounting frame - FLUG											
4				allowed in FLING trade Precast Concrete Structures				11,205.42							
				following one subcontract discoverses				**,202/82							
				contractor preliminaries, overheads & margin are separately allowed for											
c				Works generally undertaken during normal hours. Where works are to be undertaken											
				hours. Where works are to be undertaken during possession or out of hours, see "markup"											
c				Significant material handling to/from											
				platforms by Contractor											
-				Scaffolds to lift cores, footbridge & stairs provided by Contractor, other installation scatfolds (modular & mobile types) by each											
				respective trade subcontractor											
c				Erection III by subcontractor				11 505 42							
5 20	Platform	2401	Structural FRP	Ult 1 - Platform Precast concrete slab to lift landing - 200mm	m2	,	576	11,205.42 5,184.00 4302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	5,184	1	5,184.00
				thick											
20	Platform	2401	Structural FRP	Adjustment made to Subcontract Pricing Assessment (Rev2)	tem	1	6,021.42	6,021.42 6302	Subcontract Uncommitted	SC50102	Civil Work	/item	6,021	1	6,021,42
4				Structural Sheel				177,901.26							
c				following are subcontract allowances, contractor preliminaries, overheads &											
				margin are separately allowed for											

c					Works generally undertaken during normal hours. Where works are to be undertaken during possession or out of hours, see "markup"											
c					Significant material handling to/from platforms by Contractor											
c					Scaffolds to III cores, footbridge & stairs provided by Contractor, other installation											
					scattolds (modular & mobile types) by each respective trade subcontractor	•										
с с					Erection lift by subcontractor All exposed steel is to be hot dipped											
					golvanised finish unless otherwise stated, refer to Pointing trade for point finish as required											
c					Tonnages are measured nett, rate to includ for all attached & loose connections	•										
	5				Lift 1 - Platform				177,901.26							
¢	20	Platform	4101		Shop Drawings	Dem		6,720.00	6.720.00 6302	Subcontract Uncommitted		Gienbrook Pockoges	/item	6.720	1	4,720.00
c	20	Platform	4101	Shuchard Steel - general all	Shop Drawings Steel shucture for Lift Shaft Incl. foolbridge Landing	hem	1	6,720.00	6,720.00 6302	Subcontract Uncommitted	3C021	Glenbrook Pockoges	/item	6,720	1	4,720.00
	20	Matform	4101	Structural Steel - general all	HDG Columns	,	2.7	20,068.75	54,185.63 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	54,186	1	54,185.43
	20 20	Platform	4101	Structural Steel - general all	HDG Beams	•	4.2	20,068.75	84,288.75 4302	Subcontract Uncommitted		Glenbrook Packages	/item /item	84,289	1	84,288.75
	20	Platform	4101	Structural Steel - general all	Purlims - C15019 incl. bridging	m	15	78	1,170.00 4302	Subcontract Uncommitted	5C021	Glenbrook Pockoges	/item	1,170	1	1,170.00
¢	20	Matform	4101	Shuctural Steel - general all	Design Development 30/10/2018 Revised structural steel design to lift shaft &	LL LL	1	13,475.00	13,475.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	13,475	1	13,475.00
					landing. Added structural steel to SSER cell	ng										
c	1				Masony following are subcontract allowances,				19,459.00							
					contractor preliminates, overheads & margin are separately allowed for											
c					Works generally undertaken during normal hours. Where works are to be undertaken during passession or out of hours, see											
c					"markup" Significant material handling to/from platforms by Contractor											
					Lift 1 - Platform				19,459.00							
	20 20	Platform Platform	5028 5028	finishes/signage/marking	Face brick wall to outer skin of lift shaft		39 22	319 319	12,441.00 4302 7,018.00 4302	Subcontract Uncommitted Subcontract Uncommitted		Glenbrook Packages	/item /item	12,441	1	12,441.00
					above concrete shaft wall				5,202.00							
c					following are subcontract allowances, contractor preliminaries, overheads & margin are separately allowed for											
c					Works generally underfaken during normal											
					hours. Where works are to be undertaken during possession or out of hours, see "markup"											
¢					Significant material bandling to/from platforms by Contractor											
¢					Scaffolds to lift cores, footbridge & stairs provided by Contractor, other installation scaffolds (modular & mobile types) by eac											
					respective inde subcontractor				5,202.00							
	20	Platform	2401	Structural FIP	Tanking to lift pit base & walls incl. sheet protection - external	m2	44	81	3,564.00 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	3.564	1	3,544.00
	20	Platform	2401	Structural FIP	Tanking to lift pit base & walls - internal	m2	26	63	1,638.00 4302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	1,438	1	1,638.00
c					Rooling following are subcontract allowances, contractor preliminaries, overheads &				18,305.00							
					margin are separately allowed for											
c					Works generally undertaken during normal hours. Where works are to be undertaken during possession or out of hours, see											
c					"markup" Significant material handling to/from											
c					platforms by Contractor Scattolds to lift cores, footbridge & stairs											
					provided by Contractor, other installation scattalds (modular & mobile types) by each respective trade subcontractor	•										
: c	5				Lift 1 - Platform				18,305.00							
c					Lift shaft root											
	20	Platform	4101	Structural Steel - general all	Colourbond Custom Orb metal roof to lift shaft roof including insulation on wire mesh	m2	12	210	2,520.00 6302	Subcontract Uncommitted		Glenbrook Packages	/item	2,520	1	2,520.00
c	20	Platform	4101	Structural Steel - general all	Colourbond roof capping Rainwater Goods	m	14	127.5	1,785.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	1,785	1	1,785.00
	20	Platform	4101	Structural Steel - general all	Colourbond eaves gutter	m	4	142.5	570 4302	Subcontract Uncommitted		Glenbrook Pockages	/item	570	1	570
c	20	Platform	4101	Shuchural Steel - general all	Galvanised steel downpipe to new roof Roof Access & Anchorage System	m	11	210	2,310.00 4302	Subcontract Uncommitted	5C021	Glenbrook Pockoges	/item	2,310	1	2,310.00
	20	Platform	4101	Structural Steel - general all	Roof Access & Anchorage System Temporary Roof Safety Barrier System	Item	1	1,500.00	1,500.00 4302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	1,500	1	1,500.00
¢	20	Platform	4101	Structural Steel - general all	Temporary Roof Safety Barrier System	hem	1	0	6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item		1	
с с					Lift Awning Roof Lift awning roof - see Glazing trade											
c					Rainwater Goods											
	20 20	Platform	4101	Structural Steel - general all	Stainless sheel box gutter Galvanised sheel downpipe to new roof	m	8	475 210	5,400.00 4302 2,520.00 4302	Subcontract Uncommitted		Glenbrook Packages	/item /item	5,400	1	5,400.00
c					Roof Access & Anchorage System											
	20	Platform	4101	Structural Steel - general all	Roof Access & Anchorage System	hem	2	850	1,700.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	 1,700	1	1,700.00
¢					following are subcontract allowances, contractor preliminaries, overheads &											
c					margin are separately allowed for Works generally undertaken during normal hours. Where works are to be undertaken											
					during possession or out of hours, see "markup"											
¢					Significant material handling to/from platforms by Managing Contractor (Downe	r)										
					Lift 1 - Piotform											
	20	Platform	4101	Structural Steel - general all	framed & clad inner venner wall to lift shaft inside face of brick wall where above concrete shaft wall - see MASCNRY element		51	0	6302	Subcontract Uncommitted	SC021	Glenbrook Pockoges	/item		1	
					Canoples (package)				47,384.00							
	20	Platform	4101	Structural Steel - general all	framed awning over entry to FAT incl. cantilevered frame, roofing, gutter,	tem	1	4,500.00	4,500.00 6302	Subcontract Uncommitted	SC:50102	Civil Work	/item	4,500	1	4,500.00
c					downpipe, soffit - apprax 1500 x 2500mm Design Development 30/10/2018											
	20	Platform	4101	Structural Steel - general all	Add canopy to FAT - allowance for wall hu awning in TBE - Revised FAT awning structur	ng Bern e	1	64,886.00	64,886.00 6302	Subcontract Uncommitted	SC:50102	Civil Work	/item	64,886	1	64,886.00
	ı				Glazing				110,437.54							
c					following are subcontract allowances, contractor preliminaries, overheads & margin are separately allowed for											
¢					Allow prefabricate off site, deliver & install during possession											
¢					Erection lift by subcontractor											
¢					Scaffolds to lift cares, footbridge & stairs provided by Contractor, other installation scaffolds (modular & mobile types) by eac											
:	8				respective trade subcontractor				190,437.54							

с 20	Platform	4101	Structural Steel - general all	Lift Shaft Glass cladiding to lift shaft, Viidian Supergreem, or expail and approved,	m2	90	1,548.27	139,344.30 4302	Subcontract Uncommitted	SC021	Gienbrook Pockages	/bem	139,344	1	139,344.30
ŗ				Supergreen, or equal and approved, laminated safety gan, laminated with 1.3mm PVB intelayer. High recardly film to glas, powdercool finished Caprol 300 narrowline frame Liff Avening Roof											
20	Platform	4101	Shuchural Steel - general all	Glazed lift owning roof - type Iba	m2	19	1,548.28	29,417.32 4302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	29,417	1	29,417.32
20	Platform	4101	Shuchural Steel - general all	Glazed weather screen to footbridge level lift lobby	m2	14	1,548.28	21,675.92 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	21,676	1	21,675.92
4				Tilling/Applied Finishes To External Walkways Metatwork	•			105,213.70							
¢				following are subcontract allowances, contractor preliminaries, overheads &											
c				margin are separately allowed for Works generally undertaken during normal											
				hours. Where works are to be undertaken during possession or out of hours, see "markup"											
c				Significant material handling to/from platforms by Contractor											
c				Scattalds to litt cares, footbridge & stairs provided by Contractor, other installation scattalds (modular & mobile types) by each respective trade subcontractor											
5				Lift 1 - Piolform				49,501.32							
с с				Uit Ventilation Louvre											
20	Platform	4101	Structural Steel - general all	Lift shaft louve, aluminium anodised with two stage weatherproof system, 120mm thick, equal to Austrial Marsoon AME 50 - approx, 2900mm wide x 1000mm high	No.	2	5,437.50	10,875.00 4302	Subcontract Uncommitted	50021	Gienbrook Pockoges	/item	10,875	1	10,875.00
20	Platform	4101	Structural Steel - general all	Lift shaft louvre, aluminium anodised with two stage weatherproof system, 120mm thick, equal to Austral Monsoon AME 50 -	No.	2	5,850.00	11,700.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	11,700	1	11,700.00
20	Platform	4101	Structural Steel - general all	approx, 3120mm wide x 1000mm high Lift shaft louvre, aluminium anodised with two slage weatherproof system, 120mm thick, equal to Austral Morsoon AME 50 -	No.	1	4,050.00	4,050.00 4302	Subcontract Uncommitted	5(0021	Glenbrook Packages	/item	4.050	1	4,050.00
e 20				approx, 1200mm wide x 1800mm high Lift Shaft framed Panels							Glenbrook Packages	_			
c 20	Platform	4101	Structural Steel - general all	framed frantage at doors with cladding (msd. over doors to allow for reveals) Access Match	m2	29	800	23,200.00 4302	Subcontract Uncommitted	SC021	Glenbrook Pockoges	/item	23,200	1	23,200.00
20 C	Platform	4101	Structural Steel - general all	53 access hatch to lift shaft - approx. 850 x 850mm Air Pienum	No.	1	1,650.00	1,650.00 6302	Subcontract Uncommitted	5/02/1	Glenbrook Packages	/tem	1,650	1	1,650.00
20 C	Platform	4101	Structural Steel - general all	fibre cement lined plenum with frame, seal	hem	1	7,540.00	7,540.00 4302	Subcontract Uncommitted	50021	Gienbrook Packages	/ðem	7,540	1	7,540.00
20 C	Platform	4101	Structural Steel - general all	Lift landing latham mat	m	3	750	2,250.00 6302	Subcontract Uncommitted	SC021	Gienbrook Packages	/item	2,230	1	2,250.00
e 20	Polform	4101	Structural Steel - general all	Balustrades & Handrails HDG balustrade with handrail, 1100mm high	s, m	6	870	5,220.00 4302	Subcontract Uncommitted	5C021	Glenbrook Pockages	/hem	5,220	1	5,220.00
20	Platform	4101	Structural Steel - general all	match in with existing Make good new balustrades with existing		1	1,500.00	1,500.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/bem	1,500	1	1,500.00
e 20	Platform	4101	Structural Steel - general all	Kickplate HDG EA kickplate or similar to edge of lift	m	6	252.72	1,516.32 6302	Subcontract Uncommitted	\$C021	Glenbrook Packages	/hem	1516	1	1,514.32
¢				lobby (below balustrade/handral) Anti-Throw Screens											
c .				Advised that there is NO Anti-Throw Screens to be allowed for											
۰ د				Existing Footbridge Balustrades & Handralis				14,379.88							
с 20	Platform	4101	Structural Steel - general at	Assume existing balushade to remain New 35 handrail fixed to existing balustrade	m	22	416	9,152.00 4302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	9,152	1	9,152.00
e	81.05cm	4101	Structural Steel - general all	Kickplate HDG EA kickplate or similar to edge of	m	22	328.54	7,227.88 6302	Subcontract Uncommitted	3C021	Glenbrook Packages	filmer	7,228		7,227.88
20		401	STOCIOLISTINE - GENELA DI	existing footbridge (below balushade/handrail) Anti-Throw Screens			30.54	7,227.00 0.002	addening, or common	30041	de cocrocoger	jumi	2,440		7,447.000
c				Advised that there is NO Anti-Throw Screens to be allowed for											
5				Existing Slaits to Matform Balustrades & Handralis				14,332.50							
e e				Assume existing balastrade to remain											
20	Plotform	4101	Structural Steel - general all	Remove existing non compliant handrail to existing balustrade & replace with new compliant 55 handrail	m	25	526.5	13,162.50 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	13,163	1	13,142.50
20	Platform	4101	Structural Steel - general all	Ditto but termination end	No.	2	585	1,170.00 6302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	1,120	1	1,170.00
c c				Anti-Throw Screens Advised that there is NO Anti-Throw Screens to be allowed for											
¢				Under Stalt Enclosure											
20	Platform	4101	Shuchural Steel - general all	No Under Stair Enclosure shown on drawing confirm	s- m2		0	6302	Subcontract Uncommitted	\$C021	Glenbrook Packages	/item		1	
5 20	Patiam	4101	Structural Steel - general all	Station Passenger Information Display Mounting frame & Canopy Station Passenger Information display	No.		7,184.06 Rot	fe only 6302	Subcontract Uncommitted	50121	Gienbrook Packages	/item		1	
20 5	- Administ	woll		Station Passenger Information display mounting frame & canopy incl. footing, pai finished steal frame, canopy cover Platform Suitiding Air Conditioner Unit	nd		., weak its	5,000.00			and another a sold get	,			
20	Platform	4101	Structural Steel - general all	Coge/Enclosure Platform Building Air Conditioner Unit Cage/Enclosure	Tem	1	5,000.00	5,000.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	5,000	1	5,000.00
4				Painting (incl. anti grafilit)				34,064.00							
c				following are subcontract allowances, contractor preliminaries, overheads & margin are separately allowed for											
c				Works generally undertaken during normal hours. Where works are to be undertaken during passession or out of hours, see											
c				"markup" Scaffolds to lift cores, footbridge & stairs											
c				provided by Contractor, other installation scattalds (modular & mobile types) by each respective inade subcontractor No allowance for painting to existing	1										
c .				structures / elements											
¢				existing surfaces No allowance for anti-grafitti coatings to steel framing members or metalwork.											
				steel framing members or metalwork members (eg/ balustrades, anti-throw screens)											
с 5				Painting				19,520.00							
c 6				Apply proprietary paint system to : Lift 1 - Platform				8,425.00							
20	Platform	5028	Finishes/signage/marking	Exposed sheel lift shaft frame	m2	123	65	7,995.00 6302	Subcontract Uncommitted		Glenbrook Pockages	/hem	7,995	1	7,995.00
20 20	Platform	5028	Finishes/signage/marking	HDG balustrade with handral, 1100mm high match in with existing HDG EA kickplate or similar to edge of lift		6	85 20	510 4302	Subcontract Uncommitted		Glenbrook Packages Glenbrook Packages	/item	510	1	510
6			and the second	lobby (below balushode/handral) Existing footbidge				2,310.00							140
20	Platform	5028	Finishes/signage/marking	Balustrades & Handraits Existing balustrade to remain		22	85	1,870.00 4302	Subcontract Uncommitted		Glenbrook Pockages	/item	1,870	1	1,870.00
20	Platform	5028	Finishes/signage/marking	HDG EA kickplate or similar to edge of existing footbridge (below balustrade/handrail)	m	22	20	440 4302	Subcontract Uncommitted	5C021	Glenbrook Pockages	/item	440	1	44D
4				Existing Stairs to Platform				2,125.00							

20															
4	Matform	5028	finishes/signage/marking	Disting balastrade to remain Access Pathway & Stairs from Burlitt Parade	m	25	85	2,125.00 6302 6,460.00	Subcontract Uncommitted	3C021	Glenbrook Packages	/hem	2,125	1	2,125.00
20 5	Platform	5028	finishes/sigrage/making	HDG balushade	m	76	85	6.460.00 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/8em	6,460	1	4,460.00
¢				Apply and graffit cooling equal to Sure Sec Graffit Shield to :-	el			10,000							
6				Lift 1 - Platform				2,448.00							
20	Platform	5028	finishes/sigrage/marking	Face brick wall to outer skin of lift shaft Access Pathway & Staks from Burlitt Parade	m2	68	36	2,448.00 6302 12,0%6.00	Subcontract Uncommitted	3C021	Glenbrook Packages	/item	2,448	1	2,448.00
20	Platform	5028	Finishes/sigrage/marking	Coloured split face block walls	m2	336	36	12,094.00 4302	Subcontract Uncommitted	SC021	Gienbrook Packages	/hem	12,094	1	12,0%6.00
۰ د				following are subcontract allowances,				15,04230							
c				contractor preliminaries, overheads & margin are separately allowed for Works generally undertaken during normal hours. Where works are to be undertaken											
				hours. Where works are to be undertaken during possession or out of hours, see "markup"											
5 20	Platform	5028	Finishes/sigrage/marking	Existing Stains to Matform Bernove existing & instal new stair nosings	-	85	139.5	11,857.50 11,857.50 6302	Subcontract Uncommitted	10000	Glenbrook Packages	/item	11,858	1	11,857.50
5	Planoim	3026	rmaneu/sgroge/making	to existing storin (SN-01) Storin from Burfill Foroide	-	65	139.5	3,185.00	SUBCONFIDET UNCOMMENSE	30021	Genorook hockoges	/nem	11,038		11,857.30
20	Platform	5028	finisher/signage/marking	Stair nosings to concrete stairs (SN-01)	m	49	65	3,185.00 4302	Subcontract Uncommitted	5C021	Gienbrook Packages	/hem	3,185	1	3,185.00
4 c				factle indicators following are subcontract allowances,				107,940.00							
				contractor preliminaries, overheads & margin are separately allowed for Works generally undertaken during promot											
				Works generally undertaken during normal hours. Where works are to be undertaken during possession or out of hours, see "markup"											
5	Platform			Lift 1 - Platform		5		2,700.00	Subcontract Uncommitted				2700	1	
20 5	Platform	5028	finisher/signage/marking	Tactile indicators 400mm wide to IPI entry- pathfinder 35 with concentric circles (TG-05 Existing Stain to Platform	, m	3	540	2,700.00 4302 8,100.00	Subcontract Uncommitted	30021	Glenbrook Packages	/hem	2,700		2,700.00
20	Platform	5028	Finishes/sigrage/marking	Tactile indicators 600mm wide to existing stair - pathfinder 55 with concentric circles	-	10	810	8,100.00 4302	Subcontract Uncommitted	5C021	Glenbrook Pockoges	/Bem	8,100	1	8,100.00
5				(TC-02) Ramp/Staks from Burlitt Parade				5,940.00							
20	Platform	5028	finishes/signage/marking	Tactile indicators 600mm wide to stair - pathfinder SS with concentric circles (IG-02	, m	11	540	5,940.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/hem	5,940	1	5,940.00
s c				Flatform Advised by Nicolal Clousen (11/09/2018) #	rat			\$1,200.00							
				the existing blue plotform toctiles are non compliant and to allow new compliant toctiles to total platform length, similar											
			# 14	toctile to existing (plug in, not tile type) but different colour			60		Subcontract Uncommitted			44		1	
20	Platform	5028	Finishes/sigrage/marking	Remove existing platform factlies (where platform to be regraded) Tactile indicators 600mm wide to platform	m m	380	40 180	22,800.00 6302 68,400.00 6302	Subcontract Uncommitted Subcontract Uncommitted	SC021	Glenbrook Packages Glenbrook Packages	/item	22,800	1	22,800.00
				incorporating 100mm yellow band - type to (1G-01)											
4	Platform	5028	Finishes/signage/marking	Waylinding Signage Waylinding Signage	Item	1	50,000.00	50,000.00 4302	Subcontract Uncommitted	5C021	Gienbrook Packages	/item	50,000	1	50,000.00
4	Platform	5028	Finishes/sigrage/marking	Signage (other) Heritage Interperative	Item	1	25,000.00	28,000.00 25,000.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	(tiem	25,000	1	25,000.00
20	Platform	5028	Finishes/sigrage/marking	Regulatory	lfem	1	3,000.00	3,000.00 4302	Subcontract Uncommitted	5C021	Glenbrook Pockages	/item	3,000	1	3,000.00
4 c				Station Furniture & Platform Garden Beds Following are subcontract allowances,				8,325.00							
				contractor preliminaries, overheads & margin are separately allowed for Works generally undertaken during normal											
				hours. Where works are to be undertaken during passession or out of hours, see "markup"											
¢				Significant material handling to/from platforms by Contractor											
5				Platform Furniture	-			4,225.00							
				to remove existing platform furniture for platform DDA regrade & reinstall on	-										
				completion					Subcontract Uncommitted	5C021	Gienbrook Packages	/hem			
20	Platform	5028	Finishes/signage/making	completion Allow to remove existing platform furniture for platform DDA regrade & reinstall on	llem	1	6,225.00	6,225.00 6302					6,225	1	4,225.00
20 5	Platform	5028	Finishes/signage/marking	completion Allow to remove existing plotform furniture	llem	1	6,225.00	6,225.00 6302 2,100.00					6.225	1	4,225.00
	Platform	5028 5028	Fniheu/igrage/making Fniheu/igrage/making	completion Allow to remove existing platform furniture for platform DDA negrade & reinstat on completion incl. new footings as required		1	6.225.00 2,100.00		Subcontract Uncommitted	SC021	Glenbrook Pockages	/ðem	4,225	1	
5				competition Advoir to service a satisfing piloform fumbus torport to both regression at Anteinia to competition inclusive footings or regulated Modify exelling Platform Gorden Seck Modify exelling Platform Gorden Seck Modify exelling Platform Gorden Asets to sub pitofform regressive where regulated Vermit/Bite Cachel - excluded Vermit/Bite Cachel - advised		1		2,100.00	Subcontract Uncommitted	SC021	Glenbrook Packages	/item			
5 20 4				completion Allow to sensore easing plotform fumbure for plotform DDA regards & relevant on completion incl. new boltrying as required Pollorm Garden Back Modify weiting Plotform Garden Back to up plotform regrade where required Vermin/Brd Casted - excluded		1		2,100.00	Subconhact Uncommitted	5C021	Gienbrook Packages	/ken			
5 20 4 c 3 4				completion constraints constr	t fem	1		2,100.00 2,100.00 4302	Subcontract Uncommitted	50021	Glentrook Packages	/Jem			
5 20 4 C				completion completion completion for an ending stafform for any ending completion for an ending stafform for any ending completion for an ending any ending completion for any ending any ending completion regions and ending completion complet	t fem	1		2,100.00 2,100.00 4302 434,807.42	Subcontract Uncommitted	SC0221	Giandrook Pockoges	Jhan.			
5 20 4 c 3 4				complete	t fem	•		2,100.00 2,100.00 4302 434,807.42	Subcontract Uncommitted	5C021	Gentrook Rockages	/lam			
5 20 4 6 3 4 6 6				anythin anythin Schwartschaft gehöfen hanne en son son son son son son son son son so	t fem	1		2,100.00 2,100.00 4302 434,807.42	Subcontract Uncommitted	30221	Gentroix Packagen	jan.			
5 20 4 c 3 4 c				complete	2 Jam	1		2,100.00 2,100.00 4302 434,807.42	Adcontract Uncommitted	10271	Clerbrook Packages	/am			
5 20 4 6 7 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				experience	2 Jam	1		2,100.00 2,100.00 4302 434,807.42	Lubconhact Uncommitted	30291	Gentrook Packages	βan.			
20 4 4 4 4 6 4 6 7 7 7 7 7 7 7 7 7 7 7 7 7				experience	2 Jam	1		3,100,00 800 2,100,00 800 44,607,62 34,607,64	Jubconfract Uncommitted	sco21	Gentrook Packagen	jun.			
5 20 4 6 7 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				expetition And be stored and stor	9 km 9			2,100.00 2,100.00 4302 434,807.42	Advantaci Unconnelled	30091	Gentreid Packagen	Jan.			
20 4 4 4 4 6 4 6 7 7 7 7 7 7 7 7 7 7 7 7 7				expetition And Part and Annual	9 km 9			3,100,00 800 2,100,00 800 44,607,62 34,607,64	Advantaci Unannihed	30221	Geréneit Peskape				
20 4 4 4 4 6 4 6 7 7 7 7 7 7 7 7 7 7 7 7 7				expetime exp	9 km 9			3,100,00 800 2,100,00 800 44,607,62 34,607,64	Advantact treamstiled	10221	Geréneit Peslage				
20 4 4 4 4 6 4 6 7 7 7 7 7 7 7 7 7 7 7 7 7				expelies engines Aber berner welding site hardweit for sufferen (Schwarzsche Alexander um expelient en der welding anterpelie Aber berner welchen anterpelie der einer songene Antere welchen aber einer aller einer aller aller aber einer aller	9 km 9			3,100,00 800 2,100,00 800 44,607,62 34,607,64		1031	Cientros Ruchago	βan.			
20 4 4 4 6 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				 canyota canyota canyota Alera tararana safag satatan bahara sarara safag satatan bahara sarara safag satatan bahara sarara safag satatan bahara satatan sa	 a a b a a 			3,100,00 800 2,100,00 800 44,607,62 34,607,64		1007	Cientros Ruckages	jun			
20 4 4 4 6 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				englini englin	 a a b a a 			3,100,00 800 2,100,00 800 44,607,62 34,607,64		1007	Gentresk Packagen	Jan.			
20 4 4 4 6 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				engine en	 a a b a a b a b b c c			3,100,00 800 2,100,00 800 44,607,62 34,607,64		1027	Ciertenia Pachagan	Jan.			
20 4 4 4 6 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				engine en	 a a b a a b a b b c c			3,100,00 2,100,00 44,607,62 34,607,64		5221	Circlensis Pechagon				
8 20 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Rim	528	Reeutgoogenooting	 campion campion Allow target and statistical target and statisti	 a a a a a a a a b a b c c		2.1000	1.100 0 2.1000 0 24.002 4 24.002 4 24.002 4					2.02		
5 20 4 4 6 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7 7				 campion campion on the selection of the	 a a b a a b a b b c c	1	2.1000	1100 0 21000 457 2 24,022 4			Genérati Postagen	iт.			
5 20 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Rim	2028	Releasing	 c.mpion c.mpion c.mpion control series and galaxies and the series of control series and control ser	* tem • • • • • • • • • • • • • • • • • • •	112	2.00.0	1100 0 21000 407 0 24402 4 24402 4 24502 4 24502 4 24500 4 21100 0 21100 0		1014			2.02		
5 20 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Rubum	2028	Releasing uncoding	 c.mpint c.mpint c.mpint Aller tarum staffig patients halfing staffing staff	* tem 0 0 1 0 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	112	2.00.0	1100 0 2100 0 2407 0 2407 0 2407 0 2407 0 2407 0 2407 0 2100 0 210000000000		1014			2.02		
5 20 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Rubum	2028	Releasing	 c.mpint c.mpint c.mpint Aller tarter and gal patients halfer an experiment of the second patient of the second patient	* tem • • • • • • • • • • • • • • • • • • •	112	2.00.0	1100 0 2100 0 2407 0 2407 0 2407 0 2407 0 2407 0 2407 0 2100 0 210000000000		1014	Adding Works		2.00		2.05.02
5 20 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Rubum	2028	Releasing uncoding	 c.mpin c.mpin c.mpin Aller tarent contrasting safet and safe	8 km	112	2.00.0	1103 0 2100 0 4449 4 4449 4		1014	Adding Works		2.00		2.05.02
5 20 4 3 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4 4	Refers	528 	neesgeegenning	 c.mpint c.mpint c.mpint Aller tarent and galating tarburd being an expand Aller tarent and galating tarburd being an expand Aller tarent and galating tarburd being an expand Manna and an expand tarburd being tarburd bei	 a a	19	2.000 4 4.000 102 102	1103 0 2100 0 4449 4 4449 4		1014 1014	Adding Works		2.00		2.05.02

20	Patform	9302	Station Buildings	Electrical Services : cop off & temporary Tem disconnect for demolition works	2,553.60 Rote	only 6302	Subcontract Uncommitted SC014	Building Works	/hem			
e				Concrete Slob								
e 20	Platform	9302	Station Buildings	Concrete Prepare subgrade, sand fill to Rs, WPM m2	<u>33 439.6</u>	14,506.80 6302	Subcontract Uncommitted SC014	Building Works	/item	14,507		14,506.80
20	Platform	9302	Station Buildings	30MPa concrete in slab on ground to internal m3 rooms	8 1,460.69	11,485.52 4302	Subcontract Uncommitted \$C014	Building Works	/item	11,686	1	11,685.52
20	Matform	9302 9302	Station Buildings Station Buildings	tuolotion joint Bern Dowel joint Bern	1 812 1 2,352.00	812 4302	Subcontract Uncommitted SC014 Subcontract Uncommitted SC014	Building Works Building Works	/ðem /ðem	812 2,352	1000 1000	812 2,352.00
20	Pation	9302	Station Buildings	Surface finish m2	33 Inclu		SUBCOMPACI UNCOMPANIES SLU14	Building works	/item	2,332		2,332.00
e 	Potform	9302	Station Buildings	formwark formwark slab edge m	Not	and as and						
c	Partorn	1302	station autoings	Reinforcement	NOT	pricied						
20	Platform	9302	Station Buildings	Reinforcement to slob, 3282 mesh m2 Edisting Wols	53 <i>87.5</i>	2,887.50 6302	Subcontract Uncommitted SC014	Building Works	/item	2,885	1	2,887.50
20	Platform	9302	Station Buildings	Work to existing external walls of buildings - m2 no works	Exc).	ded						
20	Platform	9302	Station Buildings	Make good existing (assumed brickwork) m	69 175	12,075.00 4302	Subcontract Uncommitted \$C014	Building Works	/item	12,075	1	12,075.00
20	Platform	9302	Station Buildings	changed, to match existing walls above	25 280	7,000.00 6302	Subcontract Uncommitted SC014	Building Works	/item	7.000		7,000.00
20	Platform	9302	Station Buildings	Male good existing internal words where PFL in is changed, to match existing walk above Adjust threshold step to door of change in	2 700	1,400.00 6302	Subcontract Uncommitted SC014	Building Works	/item	1,400		1,400.00
c				floor level Masony								
20	Platform	9302	Station Buildings	Face brick soven wall m2	14 446.6	6,252.40 6302	Subcontract Uncommitted SC014	Building Works	/item	6,252	1	6,252,40
e 20	Platform	9302	Station Buildings	Stud frames Stud frame internal wats m2	Not	priced						
20	Platform	9302	Station Buildings	Stud frame internal riser walls m2	9 210	1,890.00 4302	Subcontract Uncommitted SC014	Building Works	/item	1,890	1	1,890.00
20 c	Matform	9302	Station Buildings	Stud frame internal fate wall m2 Insulations	18 210	3,780.00 4302	Subcontract Uncommitted SC014	Building Works	/item	3,780	1	3,780.00
20	Platform	9302	Station Buildings	Wall insulation m2	27 42	1,134.00 4302	Subcontract Uncommitted SC014	Building Works	/item	1,134	1	1,134.00
c c				Picaterboard & Fibre Cement Wals								
20	Platform	9302	Station Buildings	Fibre cement wall linings to framed walts m2	27 140	3,780.00 4302	Subcontract Uncommitted \$C014	Building Works	/item	3,780	1	3,780.00
20	Platform	9302	Station Buildings	Baline axisting internal wals for new finish - m2 allow fibre cement with batten frame or cement render	59 176.4	10,407.60 6302	Subcontract Uncommitted SC014	Building Works	/item	10,405	1	10,407.60
c		9302	Station Buildings	Ceiling: Surpended platerboard ceiling with m2	19 260	5,320.00 6302	Subcontract Uncommitted SC014	Building Works	/item	5,320		5,320.00
20	Partorn	1302	station suidangs	Surpended plasherboard ceiling with m2 corrice/trims	17 280	5,520.00 6302	Subconnact uncommitted SLU14	Building works	/item	3,380		3,320,00
20	Platform	9302	Station Buildings		2 4,459.00	8,918.00 4302	Subcontract Uncommitted SC014	Building Works	/item	8,918		8,918.00
				Nerrow door, lower door opening to suit No. new Pft, entroge develop to provide StOrm clear door leaf opening, new ingle leaf enternal grade doorset complete with hardware								
c				Windows								
20	Platform	9302	Station Buildings	Privacy film to existing windows m2 Waterproofing	10 140	1,400.00 6302	Subcontract Uncommitted \$C014	Building Works	/item	1,400	1	1,400.00
20	Platform	9302	Station Buildings	Waheproofing to wet area floars, upturn m2 1500mm above floar	54 97.02	5,239.08 6302	Subcontract Uncommitted SC014	Building Works	/item	5,239	1	5,239.08
c				Tiling								
20	Platform	9302	Station Buildings	Wall Hing to well areas - Gilennon Tiles W310 m2 300 x 100mm with epoxy grout	72 349.44	25,159.68 6302	Subcontract Uncommitted \$C014	Building Works	/item	25,160	1	25,159.68
20	Platform	9302	Station Buildings	Hoor tiling to wet areas - Glennon Tiles m2 GN13140.600 x 300mm with epoxy grout	18 556.64	10,019.52 6302	Subcontract Uncommitted SC014	Building Works	/item	10,020	1	10,019.52
20	Platform	9302	Station Buildings	Coved skifting tiling to wet areas - Glennon m Tiles to match floor files with epoxy grout	24 222.66	5,343.84 6302	Subcontract Uncommitted SC014	Building Works	/item	5.344	1	5,343.84
20 c	Platform	9302	Station Buildings	Threshold Sie m Fistures & Milings	2 560	1,120.00 6302	Subcontract Uncommitted SC014	Building Works	/item	1,120	1	1,120.00
c				Staff Ambelant WC								
20	Platform	9302	Station Buildings Station Buildings	Hand dryer - Dyson Aitblades V Code Ab12 No. white	1 2,093.00	2,093.00 6302	Subcontract Uncommitted SC014 Subcontract Uncommitted SC014	Building Works	/item	2,093		2,013.00
20	Platform	9302 9302	Station Buildings	Tailet Roll Holder - Babrick 82890 No. 55 gratnalis to staff ambulant WC No.	1 <u>332.5</u> 1 910	332.5 6302 910 6302	Subcontract Uncommitted SC014 Subcontract Uncommitted SC014	Building Works Building Works	/item /item	333 910	1	332.5 910
20	Platform	9302	Station Buildings	Soap Dispenser - Kimberley Clark Aquarius No. Hand Cleanser Dispenser White/1 litre 6/480	1 164.5	164.5 6302	Subcontract Uncommitted \$C014	Building Works	/item	145	1	164.5
20	Platform Platform	9302 9302	Station Buildings Station Buildings	Coat hook - 555 Mellom ML4159 No. Auminium framed 55 mirror, secured to No.	1 84.7	84.7 4302	Subcontract Uncommitted SC014 Subcontract Uncommitted SC014	Building Works Building Works	/hem	85		84.7
20	Partorn	1302	station suidangs	concealed wall hanger with theft resistant mounting equal to Sobrick - 1000H x 600W	1 1,0000	1,030.00 6302	SUBCOMPACI UNCOMPANIES SLU14	Building works	/item	1,00		1,050.00
e 	Halforn	9302	Station Buildings	FAT Hand dryer - Dyson Aitblades V Code AB12 No. white	1 2,093.00	2,093.00 4302	Subcontract Uncommitted SC014	Building Works	/item	2,093		2,093.00
20	Platform	9302	Station Buildings	Tothe dryw - Dyton Artabolit v Cobe Asi z - No. white Tollet Roll Holder - Bobrick \$2890 No.	1 332.5	332.5 4302	Subcontract Uncommitted SC014	Building Works	/item	2,073		332.5
20	Platform	9302	Station Buildings	55 graterals to FAT WC No.	1 1,120.00	1,120.00 4302	Subcontract Uncommitted \$C014	Building Works	/bem	1,120		1,120.00
20	Platform	9302	Station Buildings	Soop Dispenser - Kimberley Clark Aquarkus No. Hand Cleanser Dispenser White/1 litre 69480	1 164.5	164.5 6302	Subcontract Uncommitted SC014	Building Works	/item	145	1	164.5
20	Platform	9302	Station Buildings	Baby Change Table - Metlam Foldable - Code No. ME9100EH	1 1,330.00	1,330.00 6302	Subcontract Uncommitted SC014	Building Works	/item	1,330	1	1,330.00
20 20	Halforn Halforn	9302 9302	Station Buildings Station Buildings	Coat hook - 555 Metlam ME4159 No. Aluminium framed 55 mirror, secured to No.	1 84.7	84.7 4302 1,050.00 4302	Subcontract Uncommitted SC014 Subcontract Uncommitted SC014	Building Works Building Works	/item /item	85	1000 1000	84.7
				concealed wall hanger with theft resistant mounting equal to Babrick - 1000H x 600W								
20	Platform	9302	Station Buildings	Sanitary bin - Canon Hygeine 53 Modesty No. Itay	1 749	749 6302	Subcontract Uncommitted \$C014	Building Works	/item	749	1	749
20	Halform	9302	Station Buildings	Nappy disposal bin - Canon Hygeine nappy – No. disposal bin	1 749	749 6302	Subcontract Uncommitted SC014	Building Works	/item	749	1	749
20	Platform	9302	Station Buildings	Sharps bin (Installed at existing tollets at No. atter stations - not scheduled - no allowance)	Exc).	ded						
c	Potform	9302	Station Buildings	Existing Access Ramp Cupboard Relocate existing access ramp cupboard No.	2 476	952 6302	Subcontract Uncommitted SC014	Building Works	(item	952		952
c	· Amorni	9302	sunon suidings	Relocate existing access ramp cupboard No.	476	Pox 6302	and a scole	Jalong Works	/Sen	452		732
c				Allow politing to new works only								
с 20	Matform	9302	Station Buildings	Apply point system to :- Internal walk linings m2	14 59.2	548.8 6302	Subcontract Uncommitted SC014	Building Works	/item	549	1.0	548.8
20	Holform Holform	9302 9302	Station Buildings Station Buildings	Internal ceiling linings m2 Single leaf external grade doorset No.	19 47.6 2 336	904.4 6302 672 6302	Subcontract Uncommitted SC014 Subcontract Uncommitted SC014	Building Works Building Works	/bem /bem	904 472	1000 1000	904.4 672
20	Platform	9302	Station Buildings	Internal windows m2	5 119	595 4302	Subcontract Uncommitted SC014	Building Works	/tem	872 395		595
c				Apply anti graffiti cooling equal to Sure Seal Gentfiti Shield to (opply to internat public accessible room anty) >								
20	Platform	9302	Station Buildings	Woll filing to well creas - Giernon Tiles f725 m2. 600 x 300mm with epoxy grout	72 50.4	3,628.80 6302	Subcontract Uncommitted \$C014	Building Works	/item	3.629	1	3,628.80
20	Platform	9302	Station Buildings	Door leaf No.	2 332.64	665.28 6302	Subcontract Uncommitted \$C014	Building Works	/hem	445	1.0	465.28
e 20	Platform	9302	Station Buildings	Signage Door signage as required (per door) No.	2 224	448 6302	Subcontract Uncommitted SC014	Building Works	/item	448	1	448
c				Building Services								
c				Building Services - refer to respective services trades								
4				5522 / Stoff Room - upgrade existing commu/stoff amenifies for new 5522, upgrade existing staff room with new		38,440.40						
e				klichenette as per original design Demattion								
20	Platform	9302	Station Buildings	Ship out doors, walk, finishes, fixtures, etc., Item form openings as required	1 14,070.00	14,070.00 4302	Subcontract Uncommitted SC014	Building Works	/item	14,070	1	14,070.00
20	Platform	9302	Station Buildings	Hydraulic Services : cap off & temporary litern disconnect for demolition works	1 2,553.60	2,553.60 6302	Subcontract Uncommitted SC014	Building Works	/item	2,534	1	2,553.60
20	Platform	9302	Station Buildings	Electrical Services : cap off & hemporary Ifem disconnect for demolifion works	2,553.60 Rote	only 6302	Subcontract Uncommitted SC014	Building Works	/item		1	

20	Platform	9302	Station Buildings	Services Penetration Int SSER	Bern	1	4,530.40	4,530.40 4302	Subcontract Uncommitted	SC014	Building Works	/item	4,530	1	4,530,40
c .				services entry point into SSER											
20	Platform	9302	Station Buildings	Close up existing window, leaving external	No.		1,122.80	1,122.80 4302	Subcontract Uncommitted	SC014	Building Works	/item	1,123	1	1,122.80
c				untouched, fire rate infil on the inside											
c				Wolk											
20	Platform	9302	Station Buildings	new SSER : allow frame, shaft liner or	m2	57	420	23,940.00 6302	Subcontract Uncommitted	SC014	Building Works	/item	23,940	1	23,940.00
c				fyrcheck Ceilings											
20	Platform	9302	Station Buildings	Two hour fire rated ceiling with cornice/trim	ns m2	15	420	6,300.00 6302	Subcontract Uncommitted	SC014	Building Works	/Nem	6,300	1	4,300.00
c				Doors Permanently close existing door		2									
20 20	Platform	9302 9302	Station Buildings Station Buildings	Single leaf 2 hour FRL fire doorset complete	ND.	2	148	336 6302 2,800.00 6302	Subcontract Uncommitted	SC014 SC014	Building Works Building Works	/item /item	336	1	336 2,800.00
c				with hardware											
20	Platform	9302	Station Buildings		m2	15	420	6,300.00 6302	Subcontract Uncommitted	SC014	Building Works	/item	6,300	1	4,300.00
				framed floor					Subcontract Uncommitted			/Nem			
20	Platform	9302	Station Buildings	static dissipative, 2mm		15	252	3,780.00 4302	Subcontract Uncommitted	SC014	Building Works	/item	3,780	1	3,780.00
20	Platform	9302	Station Buildings	Vinyi floor to staff affice & meak room - Tarkett IQ Granit Range, 2mm - assume existing to remain	m2		No	f priced							
c				Fixfures & Fiffings											
e 20	Platform			Staff Office Staff office work station with benchtop,	tem			9,800.00 4302	Subcontract Uncommitted			/item	9,800		9,800.00
		9302	Station Buildings	mobile pedestal, task chair		I	9,800.00				Building Works			I	
20	Platform	9302 9302	Station Buildings	Staff office coat hook ship Babrick 8-232 x 2 Staff office lockers - Interlock Type 8 : allow		1	329 5,824.00	329 4302 5,824.00 4302	Subcontract Uncommitted	SC014 SC014	Building Works	/item	329 5,824	1	329 5,824.00
20	Platform	9302	Station Buildings	bank of 8 Staff kitchenette joinery	Item		12,600.00	12,600.00 6302	Subcontract Uncommitted	SC014	Building Works	/Bern	12,600	1	12,600.00
20	Platform	9302	Station Buildings	Staff kitchenette splashback	item	1		12,0000 6302	Demonstration of the second se						
20	Platform	9302	Station Buildings	Staff kitchenette applances : microwave (Electrolux freestanding NNRFS74SQPQ) ; ba	item ar	1	1,061.20	1,041.20 4302	Subcontract Uncommitted	5C014	Building Works	/8em	1,061	1	1,061.20
c				fidge (Holer 75 Ir HBP80)											
20	Platform	9302	Station Buildings	Fre Edinguisher	No.	1	448	448 6302	Subcontract Uncommitted	5C014	Building Works	/item	448	1	448
e 6				Fainling											
с с				Allow pointing to new works only Apply point system to :-											
20	Platform	9302	Station Buildings	Internal walls linings	m2	112	39.2	4,390.40 6302	Subcontract Uncommitted		Building Works	/Hem	4,390	1	4,390,40
20 20	Platform	9302 9302	Station Buildings Station Buildings	Internal ceiling finings Single leaf external grade doorset	m2 No.	30 2	47.6	1,428.00 6302 672 6302		SC014 SC014	Building Works	/item /item	1,428	1	1,428.00
20	Platform	9302	Station Buildings	Internal windows	m2	4	119	476 6302	Subcontract Uncommitted		Building Works	/item	476	1	47.6
c				Apply anti graffil coating equal to Sure Sea Graffil Shield to (apply to internal public	al I										
				occessible room only) > NL Signage											
20	Platform	9302	Station Buildings	Door signage as required (per door)	No.	2	224	448 6302	Subcontract Uncommitted	SC014	Building Works	/item	448	1	448
c				Building Services											
c				Building Services - refer to respective services trades											
e 20	Platform	9302	Station Buildings	# Design Development 30/10/2018 Add SSER A/C condensate drain pump (x	13	1	89,752.00	89,752.00 6302	Subcontract Uncommitted	SC014	Building Works	átem	89,752	1	89,752.00
				3] Add outdoor air supply to SSER. Add hot water to FAJ, ambulant WC & existing female. etc.											
c				1011.00.00.											
				# Descope dated 30/10/2018											
20	Platform	9302	Station Buildings		15	1	-154,301.00	-154,301.00 4302	Subcontract Uncommitted	SC014	Building Works	/bem	-154,301	1	-154,301.00
20	Platform	9302	Station Buildings	Delete construction of new SSER, delete convert shaft room to shaft office Hydroxlic Services - Building Works	15	1	-154,301.00	-154,301.00 6302 97,085.00	Subcontract Uncommitted	SC014	Building Works	/tiem	-154,301	١	-154.301.00
	Platform	9302	Station Buildings	Delete construction of new 352R, delete convert staff room to staff office Mydaulic Senices - Sulding Works	ц	1	-154,301.00		Subcontract Uncommitted	SC014	Building Works	/tiem	 -154,301	,	
4	Platform	1902	Station Buildings	Delete construction of new SSR, delete convert stoff room to stoff office Hydroudic famices - Building Works Following are subcontract allowances, contractor preliminatina, overheads & mangin are separative glowances.		1	-154,501.00		Subcontract Uncommitted	SC014	Building Works	/item	 -154,301	1	
4	Platform	9302	Skation Buildings	Delete contruction of new 328, delete convert staff room to staff office Hydroxic Services - Building Works Following are subcontract diamances, contractor preliminarie, overheads L margin are separately allowed for		1	-154,201.00		Subcontract Uncommitted	SC014	Building Works	/item	 -154,301	1	
4	Plafform	9302	Station Buildings	Delete construction of new SSR, delete convert staff come to staff office Hydrodic Enrices - Staff office controls of the staff of the staff of the margin are selectative of the staff of the margin are separately adverted for Works generally underlinke adving normal hours. Where earls are to be underlaken adving possession or or of a hours, see		1	-154,301.00		Subcontract Uncommitted	SC014	Building Works	Atem	 -154,301	1	
4	Platform	9302	Station Buildings	bedrack and the other of the set of the		1	-154.301.00		Subconfract Uncommitted	50214	Ruliding Works	Atem .	 -154,301	1	
4	Pation	7352	Station Bulkings	Database constructions of new 1385, aduated connert of an own to suit of richors Medicate Servers - Anding Watch Andrease Servers - Anding Watch and Servers - Andrease - Andrease - Andrease Andrease - Andrease - Andrease - Andrease Andrease - Andrease - Andrease - Andrease Andrease - Andrease - Andrease - Andrease - Tabase - Tabase - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andrease - Andre		1	-154.301.00		Subcontract Uncommitted	50014	Building Works	,ðam	 -154,301	1	
4 c c c				Debate conduction of new 2000, adults Departed information of and adults Departed information of adults Departed information of adults Departed information of adults adults and adults adu				77,681.00							
4 c c	Padam Padam Padam	932	Stater Auling	Detection of the out of the control of the		1 245 245	-154301.00 750 750	77,685.00	Subcontract Occumentities		Bulding Works	Alem Alem Alem	-154,301 1.068	1	
4 c c c 5 20	Patian	9002	Dote kåling	Eables catalucture of new 1995, subset Monitor Service - Andrew 2005 Monitor Service - Andrew 2005 Catalucture - Catalucture - Andrew 2005 Monitor - And	h	245	730	77,681.00 7,77160 1.987.30 4302	Subcontract Disconneilled	3.C021 3.C021	Gerkont-Puckages	/ðem	1.985	1	197.5
4 c c c 2 20 20	Padam Palam	9002	Sofor Bálling Zofor Bálling	Bobsensetwickling for an 24 pp. 44 pp.	b m m	245	750 730	77,581.00 7,771.00 1.987.30 4302 1.987.30 4302	Subcontract Viccommitted	3.C021 3.C021	Clarifonsk Pockages Glarifonsk Pockages	/item /item	1.985	1	1997 SP 1997 SP
4 c c c c 20 20 20 20 20 20	Padam Palam	9002	Sofor Bálling Zofor Bálling	Control of the second of the	b m m	245	750 730	77384.00 7775.00 1.961.30 4.00 1.961.30 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.00000 4.00000 4.00000 4.00000 4.00000 4.00000 4.000000 4.00000000	Subcontract Viccommitted	3.C021 3.C021	Clarifonsk Pockages Glarifonsk Pockages	/item /item	1.985	1	1.99-50 1.99-50 1.99-35 4.000.00
4 c c c c 20 20 20 20 20 20	Padam Palam	9002	Sofor Bálling Zofor Bálling	 Another and start and s	b m m	245	750 730	7736600 797560 1.38730 602 1.38730 602 4.0000 602	Subcontract Viccommitted	3.C021 3.C021	Clarifonsk Pockages Glarifonsk Pockages	/item /item	1.985	1	1.99-50 1.99-50 1.99-35 4.000.00
4 c c c c 20 20 20 20 20 20	Padam Palam	9002	Sofar Balling Sofar Balling Sofar Balling	 Beastering of an all starts and starts and	m m Burn	245	730 730 4.000.00	77384.00 7775.00 1.961.30 4.00 1.961.30 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.00.00 4.00 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.00000 4.00000 4.00000 4.00000 4.00000 4.00000 4.000000 4.00000000	Subcontract Viccommitted	5C021 5C021 5C021	Clarifonsk Pockages Glarifonsk Pockages	/item /item	1.988 1.988 4.000	1	1.997-39 1.997-39 4.092.09
د د د د 20 20 20 20 5 د 20	Police Police Police	900 950 950 950	Solar Adag Solar Adag Solar Adag Solar Adag	Bobsenetor un der auf gehandlich und der	m m Burn	245 245 1	750 750 4.000.00 12.600.00	775550 77750 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602	Subcentrad Seconverted Subcentrad Seconverted Subcentrad Seconverted	SC091 SC091 SC091 SC091 SC091	Clarifont Poctoges Clarifont Poctoges Clarifont Poctoges Clarifont Poctoges Clarifont Poctoges	Jaan Jaan Jaan	1.988 1.988 4.000 12.660 3.660	1	1.007.00 1.007.00 4.000.00 1.000.00
د د د د 20 20 20 20 20 20 20 20 20 20 20 20 20	Police Police Police	1000 1000 1000 1000 1000	Sudor Adarga Sudor Adarga Sudor Adarga Sudor Adarga	babes careful and an effect a state and an effect and	n m m bern Fern tau	245 228 1 1 1	750 750 4.0500 4.0500	778550 779560 199736 400 199736 400 199736 400 811360 1996050 400 1996050 400 1996050 400	Subcontract Disconnelling Subcontract Disconnelling Subcontract Disconnelling Subcontract Disconnelling	102271 102271 102271 102271 102271	Gerbrook Packages Gerbrook Packages Gerbrook Packages	flam Jaam Jaam Jaam	1.585 1.585 1.585 1.585 1.260 1.260		1,947 35 1,949 35 4,000 30 1,2400 40 5,000 40
• c c c c c c c c c c c c c c c c c c c	Polium Polium Polium Polium	900 950 950 950	Solar Adag Solar Adag Solar Adag Solar Adag	 Bobsenerging of an elegation of a	m m Burn	245 245 1	750 750 4.000.00 12.600.00	775550 77750 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602 1.9215 602	Subcentrad Seconverted Subcentrad Seconverted Subcentrad Seconverted	102271 102271 102271 102271 102271	Clerbrosh Poctages Clerbrosh Poctages Clerbrosh Poctages Clerbrosh Poctages Clerbrosh Poctages	Jaan Jaan Jaan	1.988 1.988 4.000 12.660 3.660	1	1.007.00 1.007.00 4.000.00 1.000.00
د د د 2 20 20 20 20 20 20 20 20 20 20 20 20 2	Rufum Rufum Rufum Rufum Rufum	9352 9552 9552 9552 9552 9552	Solor Addrog Solor Addrog Solor Addrog Solor Addrog Solor Addrog	 bases careful careful or de radio a careful c	n m m parm parm seam	245 245 1 1 1 1 2 2 2 2	720 720 4.02020 1.600.00 4.02020	775550 777560 1.94736 802 1.94736 802 843000 802 8431060 802 1.94058 802 1.94058 802 1.94058 802 1.94058 802 1.94058 802 1.94058 802	Acontect Seconnified	10091 10091 10091 10091 10091	Centrosit Packages Centrosit Packages Centrosit Packages Centrosit Packages	Alam Alam Alam Alam Alam Alam	1.988 1.988 4.000 1.000	· · · · · · · · · · · · · · · · · · ·	1.897.30 1.997.30 4.000.00 1.2400.00 1.2400.00 1.2400.00 1.2400.00
د د د د 20 20 20 20 20 20 20 20 20 20 20 20 20	Rufum Rufum Rufum Rufum Rufum	932 932 933 933 935 935	Solor Addrog Solor Addrog Solor Addrog Solor Addrog Solor Addrog	 Descention of an effective of an	n m m parm parm seam	245 245 1 1 1 1 2 2 2 2	720 720 4.02020 1.600.00 4.02020	774550 79750 1.923.0.02 1.923.0.02 1.923.0.02 1.923.0.00 2.9400.0.02 1.9400.0.02 1.9400.0.02 1.9400.0.02 1.9400.0.02 1.9400.0.02 1.9400.0.02	Acontect Seconnified	10091 10091 10091 10091 10091	Centrosit Packages Centrosit Packages Centrosit Packages Centrosit Packages	Alam Alam Alam Alam Alam Alam	1.988 1.988 1.985	· · · · · · · · · · · · · · · · · · ·	1.82.5 1.82.5 1.82.5 4.55.5 1.865.5 1.865.5 1.865.5 1.865.5 1.865.5 1.865.5 1.865.5 1.865.5 1.865.5 1.865.5
د د د د 2 20 20 20 20 20 20 20 20 20	Rufum Rufum Rufum Rufum Rufum	952 952 952 953 955 955 955 955 955 955 955	Sudar Adarg Sudar Adarg Sudar Adarg Sudar Adarg Sudar Adarg	 bases careful careful or de radio a careful c	n m m parm parm seam	245 245 1 1 1 1 2 2 2 2	720 720 4.000000 4.00000 4.00000 4.00000 4.00000 4.00000 4.00000000	17.8550 7.9750 1.90120 402 1.90120 400 1.90120 400 1.901200 1.90120 400 1.90120 400 1.90120 400 1.90120 400 1.90120 400 1.90120 400 1.90120 400 1.90120 400 1.90120 4000 1.90120 40000000000000000000000000000000000	Acontect Seconnified	1.031 2.031	Ciertessis Paciages Ciertessis Paciages Ciertessis Paciages Ciertessis Paciages Ciertessis Paciages Ciertessis Paciages	Alam Alam Alam Alam Alam Alam	1.988 1.988 4.000 1.9.000 1.9.000 1.9.000 1.9.000 1.9.000 1.9.000 1.9.0000 1.9.0000 1.9.0000000000	· · · · · · · · · · · · · · · · · · ·	1.987.30 1.997.30 4.000.00 1.888.00 1.888.00 1.388.00 1.388.00 1.388.00
 د c c d 20 20<!--</td--><td>Portum Portum Portum Portum Portum Portum Portum Portum Portum Portum</td><td>955 955 955 955 955 955 955 955 955 955</td><td>Sudor Adarge Sudor Adarge</td><td> Ideated sector and and and and and and and and and and</td><td>н н н н н н н н н н н н н н н н н н н</td><td>245 245 1 1 1 1 2 2 2 2</td><td>720 720 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000</td><td>778500 779500 19932 400 19932 400 19932 400 40000 400 193000 400 1930000000000000000000000000000000000</td><td>Advantus (second) Advantus (second) Advantus (second) Advantus (second) Advantus (second) Advantus (second) Advantus (second)</td><td></td><td>Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages</td><td>Jaan Jaan Jaan Jaan Jaan Jaan Jaan Jaan</td><td>1,348 1,948 1,948 4,000 12,400 12,400 12,400 12,400 12,400 12,400 12,400 12,400 12,400 12,400 14,4000 14,4000 14,400 14,400 14,4000 14,4000 14,4000 1</td><td></td><td>1,80°,50 1,50°,50 4,000,00 5,600,00 1,2,600,000,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,000,00 1,2,600,000,000,000,000,000,000,000,000,0</td>	Portum Portum Portum Portum Portum Portum Portum Portum Portum Portum	955 955 955 955 955 955 955 955 955 955	Sudor Adarge Sudor Adarge	 Ideated sector and and and and and and and and and and	н н н н н н н н н н н н н н н н н н н	245 245 1 1 1 1 2 2 2 2	720 720 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000	778500 779500 19932 400 19932 400 19932 400 40000 400 193000 400 1930000000000000000000000000000000000	Advantus (second) Advantus (second) Advantus (second) Advantus (second) Advantus (second) Advantus (second) Advantus (second)		Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages Cardronal Pactages	Jaan Jaan Jaan Jaan Jaan Jaan Jaan Jaan	1,348 1,948 1,948 4,000 12,400 12,400 12,400 12,400 12,400 12,400 12,400 12,400 12,400 12,400 14,4000 14,4000 14,400 14,400 14,4000 14,4000 14,4000 1		1,80°,50 1,50°,50 4,000,00 5,600,00 1,2,600,000,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,00 1,2,600,000,00 1,2,600,000,000,000,000,000,000,000,000,0
د د د د 2 20 20 20 20 20 20 20 20 20	Patan Patan Patan Patan Patan Patan Patan Patan	900 900 900 900 900 900 900 900 900 900	Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog Sofer Addrog	 bases can subscription of an extra structure of a str	м п. п. п. п. п. п. п. п. п. п. п. п. п.	245 245 1 1 1 1 2 2 2 2	700 720 4.0000 4.0000 4.0000 4.0000 4.0000 700 700	778500 777500 1.0012 0.001 1.0012 0.001 1.0012 0.001 1.0010 0.001 1.0010 0.001 1.0010 0.001 1.0000 0.001 1.0000 0.001 1.0000 0.001 1.0000 0.001 1.0000 0.001 1.0000 0.001	Advantual Securitika Subcentrad Securitika Subcentrad Securitika Subcentrad Securitika Subcentrad Securitika Subcentrad Securitika Subcentrad Securitika		Clarifoldi Pacilogia Clarifoldi Pacilogia Clarifoldi Pacilogia Clarifoldi Pacilogia Clarifoldi Pacilogia	Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.988 1.988 4.000 1.9.000 1.9.000 1.9.000 1.9.000 1.9.000 1.9.000 1.9.0000 1.9.0000 1.9.0000000000		1.00/30 1.90/30 4.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00
 د ۵ 4 20 20<	Patan Patan Patan Patan Patan Patan Patan Patan Patan Patan		Sudor Addrog Sudor Addrog	 Bostenstrate dans dans das das das das das das das das das da	۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰ ۰	245 245 1 1 1 1 2 2 2 2	70 70 4.000 4.000 4.000 4.000 4.000 70 70 70 70 70 70 70 70 70 70 70 70	778500 777500 1.977500000000000000000000000000000000000	Adonhad Secondition A		Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos	Alam Alam Alam Alam Alam Alam Alam Alam	1.988 1.988 4.000 12.0000 12.000 12.00000 12.00000 12.0000000000		1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93
	Patan Patan Patan Patan Patan Patan Patan Patan		Sudar Addag Sudar Addag Sudar Addag Sudar Addag Sudar Addag Sudar Addag Sudar Addag Sudar Addag	 basenerstenden sin seine sein	м п. п. п. п. п. п. п. п. п. п. п. п. п.	245 245 1 1 1 1 2 2 2 2	720 730 4.42000 5.4000 4.42000 4.42000 4.42000 4.42000 4.42000 4.42000 4.42000 4.42000 4.42000 4.42000	77850 77850 1.025 4.000 4.000 4.000 1.040 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.00000 4.0000 4.0000 4.0000 4.00000 4.00000000	Advantual Seconselled		Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.085 1.985 4.000 12.0000 12.00000 12.00000 12.0000000000		1.00.90 1.00.20 1.00.0
 د ۵ 4 20 20<	Police Police Police Police Police Police Police Police Police Police		Sudor Addrog Sudor Addrog	 Bostenstrate dans dans das das das das das das das das das da	а а а а а а а а а а а а а а а а а а а	245 245 1 1 1 1 2 2 2 2	70 70 4.000 4.000 4.000 4.000 4.000 70 70 70 70 70 70 70 70 70 70 70 70	778500 777500 1.977500000000000000000000000000000000000	Adonhad Secondition A		Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos Ciertoso Poctogos	Alam Alam Alam Alam Alam Alam Alam Alam	1.988 1.988 4.000 12.0000 12.000 12.00000 12.00000 12.0000000000		1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93 1.92.93
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	Image: Control of the Contro of the Control of the Control of the Control of the Control of th	а а а а а а а а а а а а а а а а а а а	245 245 1 1 1 2 2 2 2 2 2 2 3 2 3 2 3 2 3 3 3 1 1 1 1	70 70 4.000 4.000 4.000 4.000 4.000 4.000 4.000 4.000 4.000 4.000 70 4.000 70 70 70 70 70 70 70 70 70 70 70 70	774550 77750 1.1013 1.1013 1.1013 1.1013 1.1013 1.1013 1.10100 1.10100 1.10100 1.10100 1.10100000000	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.000000 2.00000000		1.50 .5 1.50 .5 4.00.0 1.200.0
	Police Police Police Police Police Police Police Police Police Police		Sutor Adarg Sutor Adarg	 basessensetsens ensetse	а а а а а а а а а а а а а а а а а а а	245 245 1 1 1 1 2 2 2 2	725 726 4.0000 4.0000 4.0000 720 4.0000 720 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000 4.0000	77550 77750 14739 44749 44739 44749 447494444444444	Adcorbed Second Me Second Me Second Second Me Second Me Second Second Me Second Me Second Second Me Second Me Second Me Secon		Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages Ciertosis Pestages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.988 1.988 4.000 12.0000 12.000 12.00000 12.0000 12.00000 12.00000 12.0000000000		1.00° 30 1.00° 30 1.0
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	Image: Section of the section of t	а а а а а а а а а а а а а а а а а а а	245 245 1 1 1 2 2 2 2 2 2 2 3 2 3 2 3 2 3 3 3 1 1 1 1	200 200 4 (2000) 4 (2	7/44500 7/97400 1.927.02 4.927.02 4.927.02 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.910 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.91000 7.910000 7.91000000000000000000000000000000000000	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.000000 2.00000000		1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00 1.00.00
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	 basessensetsens ensetse	а а а а а а а а а а а а а а а а а а а		200 200 4 (2000) 4 (2	77550 77750 1.0125 1.0125 0.0000 0.00000 0.0000 0.0000 0.0000 0.00000 0.00000 0.000000	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.00000000		
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	Image: Section of the section of t	а а а а а а а а а а а а а а а а а а а		200 200 4 (2000) 4 (2	77550 77750 1.0125 1.0125 0.0000 0.00000 0.0000 0.0000 0.0000 0.00000 0.00000 0.000000	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.00000000		1.92.93 1.92.93 1.92.93 1.22.03.93 1.23.03.03.03 1.23.03.03.03 1.23.03.03.03.03.03.03.03.03.03.03.03.03.03
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	 Ideated and an advance of a second advance of a secon			200 200 4 (2000) 4 (2	77550 77750 1.9735 1.9735 2.9750 7.9750 7.9750 7.9750 7.9750 7.9750 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.00000000		1.92.93 1.92.93 1.92.93 1.22.03.93 1.23.03.03.03 1.23.03.03.03 1.23.03.03.03.03.03.03.03.03.03.03.03.03.03
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	 Ideates and and any offention of any offention offention			200 200 4 (2000) 4 (2	77550 77750 1.9735 1.9735 2.9750 7.9750 7.9750 7.9750 7.9750 7.9750 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.00000000		1.00.00 1.00.00 1.200.000 1.200.000 1.200.000 1.200.0000000000
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	 Identified and set of a default of a default			200 200 4 (2000) 4 (2	77550 77750 1.9735 1.9735 2.9750 7.9750 7.9750 7.9750 7.9750 7.9750 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.00000 2.00000000		1.00.00 1.00.00 1.200.000 1.200.000 1.200.000 1.200.0000000000
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	 Ideational of the second second			200 200 4 (2000) 4 (2	77550 77750 1.9735 1.9735 2.9750 7.9750 7.9750 7.9750 7.9750 7.9750 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.000000 2.00000000		1.00.00 1.00.00 1.200.000 1.200.000 1.200.000 1.200.0000000000
	Roton Roton		Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag Suin Adag	 Ideated and an and and			200 200 4 (2000) 4 (2	77550 77750 1.9735 1.9735 2.9750 7.9750 7.9750 7.9750 7.9750 7.9750 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500 7.9500	Advantus (seamintus)		Ciertos Poctages Ciertos Poctages	Jam Jam Jam Jam Jam Jam Jam Jam Jam Jam	1.985 1.985 4.000 12.000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.0000 2.000000 2.00000000		1.00.00 1.00.00 1.200.000 1.200.000 1.200.000 1.200.0000000000

c				fire detection to platform building - see Electrical Services trade										
4				fire Hydrant Service - site										
c				Kevin Waters has raised this - tbc										
4 c				Mechanical Services - Building Works Following are subconhoct allowances,			57,300.00							
				contractor preliminaries, overheads & margin are separately allowed for										
c				Works generally undertaken during normal hours. Where works are to be undertaken during passession or out of hours, see										
				"markup"										
c				Significant material handling to/from platforms by Contractor										
c				Scattolds to lift cores, footbridge & stairs provided by Contractor, other installation scattolds (modular & mobile types) by each										
				respective trade subcontractor			14,000.00							
5 20	Malform	9302	Station Buildings	Mechanical air supply to lift shaft the	n 1	16,000.00	14,000.00 4302	Subcontract Uncommitted	SC021	Glenbrook Packages	/item	16,000	1	14,000.00
5				Notiorm Building Alterations			41,300.00							
c				No reference to any air conditioning upgrade to existing Staff Office & Meals Room - assume existing to remain										
20	Platform	9302	Station Buildings	Air conditioning to SSER the	n 1	22,400.00	22,400.00 6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item	22,400	1	22,400.00
20	Platform	9302	Station Buildings	Mechanical what to Staff ambulant WC the		6,300.00	6,300.00 6302	Subcontract Uncommitted	5C021	Glenbrook Packages	/item	6,300	1	4,300.00
20	Platform	9302	Station Buildings Station Buildings	Mechanical exhaust to FAT then Mechanical exhaust to cleaners room them	n 1 n 1	6,300.00	6,300.00 6302	Subcontract Uncommitted	SC021 SC021	Glenbrook Packages	/item /item	6,300	1	4,300.00 4,300.00
4				Lifts - engaged by the Mincipal			14,400.00							
5				Lift 1 - Platform			14,400.00							
c				Supply & installation of lift by Principal Contractor										
e 20	Platform	9302	Station Buildings	Ultranic Interface	n 1	0	6302	Subcontract Uncommitted	50021	Gienbrook Packages	/hem		1	
-				see Downer Pheliminaries Attendence at Sydney Trains Inspection & No						Glenbrook Pockoges	/item			
20	· with the	9302	Station Buildings	obtain workcover certificates	. 1	14,400.00	14,400.00 6302	accompact uncommitted	SC021		, eelim	14,400	1	14,400.00
20	nation	9302	Station Buildings	Temporary power to the sequirement of the Littraric		0	6302	Subcontract Uncommitted	50021	Glenbrook Packages	/nem		1	
20	Platform	9302	Station Buildings	Protection of lift shaft & temporary Ben hoardings/gates	n 1	0	6302	Subcontract Uncommitted	50021	Glenbrook Packages	/item		1	
4				Existing Structures Make Good/Treatments ELECTRICAL - LV & COMMS, STATION			457,061.68							
				ELECTRICAL - LV & COWNS, STATION SYSTEMS, EARTHING & BONDING Electrical - LV & Commis, Station Systems,										
4				Earthing & Bonding			457,061.68							
с с				ELECTRICAL & COMMS										
5				Station Lighting			77,614.00							
60	Project Wide	7085	Electrical LV	Supply and mount new recessed LED lights ea on structures and complying to the drawings	. 1	14,000.00	14,000.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	14,000	1	14,000.00
60	Project Wide	7085	Bechical LV	and finishes schedule Supply and mount new emergency lights on ea structures and complying to the finishes	. 1	33,768.00	33,768.00 6302	Subcontract Uncommitted	50001	Bechical, CCTV and Comms	/item	33,768	1	33,768.00
				schedule										
60	Project Wide	7085	Bechical LV	Supply and install the new cabling (please LS refer to the Glenbrook cable schedule)	1	8,350.00	8,350.00 4302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	8,350	1	8,350.00
60	Project Wide	7085	Bechical LV	Identify and remove all redundant cables 13	1	6,400.00	6,400.00 6302	Subcontract Uncommitted		Bechical, CCTV and Comms	/item	6,400		6,400.00
60	Project Wide	7085	Bechical LV	Supply and install new cable containment LS where needed (please specify)	1	8,696.00	8,696.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	8,694	1	8,696.00
60	Project Wide	7085	Electrical LV	Remove any cable containment and LS associated parts made redundant by the works	1	6,400.00	6,400.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	6,400	1	6,400.00
5				Power Dishibution			147,962.00							
60	Project Wide	7085	Bechical LV	Supply and initial a new ISMS8 in the LS proposed SSER in existing building.	1	24,400.00	24,400.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	24,400	1	24,400.00
60	Project Wide	7085	Electrical LV	Supply and install a new DB in the Booking Office		12,955.00 Ro	te only 6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/item		1	
60	Project Wide	7085	Bechical LV	Identify all circuits existing in MSB and DB 1, LS located in the existing station marker office	1	2,615.00	2,615.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	2,615	1	2,615.00
60	Project Wide	7085	Bechical LV	Identify all other circuits located in the LS	1	1,700.00	1,700.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	1,700	1	1,700.00
60	Project Wide	7085	Bechical LV	existing station master office	1	850	850 6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/item	850	1	850
40	Project Wide	7085	Bechical LV	existing tollet block Disconnect and remove all circuits located 13		1,765.00	1,765.00 6302	Subcontract Uncommitted	5C001	Electrical, CCTV and Comms	/item	1,765		1,745.00
				in the existing toilet block										0.000
60	Project Wide	7085	Bechical LV	Fit out the New Stations Systems Equipment LS Room (SSER)		13,788.00 Ro		Subcontract Uncommitted		Bechical, CCIV and Comms	/item		1	
60	Project Wide	7085	Bechical LV Bechical LV	fit out the New Family Access Tollet (FAT) LS Disconnect and remove all circuits LS	1	31,788.00	31,788.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms Bechical, CCTV and Comms	/item /item	31,788		31,788.00
60	Project Wide	7085		associated with D81 Remove fiftings, outlets, containment, LS	1	6,930.00	6,930.00 6302	Subcontract Uncommitted		Bechical, CCIV and Comms		6,930		4,930.00
80	Hoject wide	7465	Bechical LV	cabling made redundant by modifications to rooms		6,930.00	6,930.00 6302	subconnact uncommined	scoor	becinca, CCIV and Comma	/item	6,750	1	6,930.00
60	Project Wide	7085	Bechical LV	Provide electrical cabling, lighting and LS outlets to modified rooms	1	15,000.00	15,000.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	15,000	1	15,000.00
60	Project Wide	7085	Bechical LV	Supply and initial the new cabling (please LS refer to the Glenbrook cable schedule)		0	6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/item		1	
60	Project Wide	7085	Bechical LV	Identify and remove all redundant cables		0	6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/item		1	
60	Project Wide	7085	Bechical LV	Supply and install new cable containment for LS the lift essential services cabling (please	1	7,940.00	7,940.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	7,940	1	7,940.00
60	Project Wide	7085	Bechical LV	specify) Supply and install new cable containment LS	1	7,000.00	7,000.00 6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/item	7,000	,	7,000.00
60	Project Wide	7085	Bechical LV	where needed (please specify) Remove any cable containment and LS		4,050.00	4,050.00 4302	Subcontract Uncommitted	50001	Bechical, CCIV and Comms	/item	4,050		4,050.00
		, ma		Remove any cable containment and LS associated parts made redundant by the works	1	-,uality		account of Committed		dha comma	,	4,030	1	4030.00
60	Project Wide	7085	Bechical LV	Supply and install cable for new Wayfinding T LS Modular Signs		1,397.00 Ro	te only 6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/hem		1	
60	Project Wide	7085	Bechical LV	Supply and install the new cabling (please LS refer to the Glenbrook cable schedule - Lith)	1	36,474.00	36,474.00 6302	Subcontract Uncommitted	SC001	Bechical, CCIV and Comms	/hem	36,474	1	36,474.00
5				CCTV - COMMS			43,527.00							
60	Project Wide	7701	Communications (CCTV)	CCTV & Help Points Supply and install of CCTV LS	1	És:	43,527.00							
				cameras and Help Point by Interface Contractor										
60	Project Wide	7701	Communications (CCTV)	Supply and install the new cabling (please LS refer to the Glenbrook cable schedule - CCTV & Help Points) (on this line install = install	1	5,000.00	5,000.00 4302	Subcontract Uncommitted	5C001	Bechical, CCTV and Comms	/item	5,000	1	5,000.00
60	Project Wide	7701	Communications (CCTV)	+ terminate + test + commission) Identify and remove all redundant cables Lot		4,050.00	4,050.00 6302	Subcontract Uncommitted	5C001	Bechical, CCTV and Comms	/item	4,050	1	4,050.00
60	Project Wide	7701	Communications (CCIV)	Supply and initial new cable containment Lat	1	4,050.00	4,050.00 4302	Subcontract Uncommitted		Bechical, CCTV and Comms	/item	6,154		4,154.00
				where needed (please specify the containment route per cable run)										
60	Project Wide	7701	Communications (CCTV)	Remove any cable containment and Lot associated parts made redundant by the works (please specify)	1	2,615.00	2,615.00 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item	2,615	1	2,615.00
60	Project Wide	7701	Communications (CCTV)	Supply and install / mount Security Door ea	. 1	9,360.00	9,360.00 6302	Subcontract Uncommitted	50001	Bechical, CCTV and Comms	/hem	9,360	1	9,340.00
60	Project Wide	7701	Communications (CCTV)	Contacts Supply and install / mount Duress Alarm ea	. 1	8,980.00	8,980.00 4302	Subcontract Uncommitted	50001	Bechical, CCTV and Comms	/hem	8,980	1	8,980.00
60	Project Wide	7701	Communications (CCTV)	Supply and install / mount Duress Alarm Lot Pushbutton with shroud	1	0	6302	Subcontract Uncommitted		Bechical, CCTV and Comms	/item		1	
60	Project Wide	7701	Communications (CCTV)	Supply and instal / mount PIR Detectors ea		6,240.00 Ro		Subcontract Uncommitted	SC001	Electrical, CCTV and Comms	/item		1	
60 60	Project Wide	7701	Communications (CCTV)	Supply and install security system LS Works involved in stration old CCDV system LS		23,400.00 Ro 7,368.00	fe only 6302 7,368.00 6302	Subcontract Uncommitted		Bechical, CCTV and Comms	/item /item	7.368	1	7,368.00
	rroject Wide	7701	communications (CCIV)	Works involved in staging old CCTV system LS to new system	1	7,368.00	7,368.00 6302	supcontract Uncommitted	50001	pecifical, CCTV and Commi	/nem	7,368	1	7,348.00
5 60	Project Wide	7085	Bechical LV	HDs Relocate equipment in existing 3M-PA rack ea		42,495.00 Ro	te only 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item		1	
60	Project Wide	7085	Electrical LV	Supply and install the new cabling (please LS refer to the Glenbrook cable schedule - PDs)		15,205.00 Ro		Subcontract Uncommitted			/item		1	
				(on this line install = install + terminate + test + commission)										
60	Project Wide	7085	Electrical LV	Identify and remove all redundant cables Lot (please specify)		3,530.00 Ro	te only 6302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/item		1	

60	Project Wide	7085	Bechical LV	Supply and install new cable containment Lot where needed (please specify the containment route per cable run)	2,371.00 Rote only 4302	Subcontract Uncommitted SC001	Bechicol, CCIV and Comma	/bem	1
60	Project Wide	7085	Bechical LV	Remove any cable containment and Lot associated parts made redundant by the works (please specify)	915 Rote only 4302	Subcontract Uncommitted SC001	Bechical, CCIV and Comms	/ðem	1
5				PA/DVA					
60 60	Project Wide	7701	Communications (CCTV)	Supply and install / mount new speakers ea. Supply and install NAM ea.	9,850.00 Rate only 6302 28,950.00 Rate only 6302	Subcontract Uncommitted SC001 Subcontract Uncommitted SC001	Bectrical, CCTV and Comms Bectrical, CCTV and Comms	/ðem	1
40	Project Wide	7701	Communications (CCTV)	Supply and install / mount Ambient Noise ea. Sensor	0 4302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/ðem	1
40	Project Wide	7701	Communications (CCTV)	Supply and install the new cabling (please Lot refer to the Clenbrook cable schedule - PA(DVA) (on this fine install = terminole = test + commission)	4,001.00 libite only \$302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/bem	1
40	Project Wide	7701	Communications (CCTV)	Identify and remove all redundant cables Lot	1,765.00 Itale only 6302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/ðem	1
40	Project Wide	7701	Communications (CCTV)	(please specify) Supply and install new cable containment Lat	5,928.00 Rate only 6302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/item	1
				where needed (please specify the containment route per cable run)					
40	Project Wide	7701	Communications (CCTV)	Remove any cable containment and Lot associated parts made redundant by the works (please specify)	2,350.00 ltate only 6302	Subcontract Uncommitted SC001	Bectrical, CCTV and Comms	/bem	1
5				Electronic Tickeling (OCR and Vending)	14,811.00				
60 60	Project Wide	7085	Electrical LV Electrical LV	Relocate the ETS Racks ea. Supply and install / mount new Opal Tap & ea.	0 4302	Subcontract Uncommitted SC001 Subcontract Uncommitted SC001	Bechical, CCTV and Comms Bechical, CCTV and Comms	/tem /tem 3,48	1 6 1 3,486.00
40	Project Wide	7085	Electrical LV	Go Supply and install the new cabling (please Lot	1 9,769.00 9,769.00 6302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/8em 9,76	
				refer to the Glenbrook cable schedule - OCR and Vending) (on this line install = install = terminate = test = commission)					
60	Project Wide	7085	Electrical LV	Identify and remove all redundant cables Lot (please specify)	1 3,556.00 3,556.00 6302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/8em 3,55	6 1 3,556.00
40	Project Wide	7085	Electrical LV	Supply and install new cable containment Lot where needed (please specify the containment route per cable run)	0 6302	Subcontract Uncommitted \$C001	Bectrical, CCTV and Comms	/tem	1
40	Project Wide	7085	Electrical LV	Remove any cable containment and Lot associated parts made redundant by the works (please specify)	0 4302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/8em	1
5 60	Project Wide	7085	Electrical LV	Heating Loops Supply and install the new cabling (please Lot	\$1,945.00 1 59,575.00 59,575.00 6302	Subcontract Uncommitted SC001	Electrical, CCTV and Comms	/bem 59,57	5 1 59,575.00
40	Project Wide	7085	Electrical LV	refer to the Gaentrook cobies schedule - Hearing Loop) (on this fice install = histall = Henrinolde = feat = commission) Supply and install new cable containment Lot	1 2,371.00 2,371.00 4302	Subcontract Uncommitted \$C001	Bechical, CCIV and Comms	/8em 2,37	
				suppy and initial new cable containment . Lot where needed (please specify the containment route per cable run)	approximate			2,5	. a,ur : 100
5 60	Project Wide	7085	Bechical LV	Station fibre Optic and LAN Perform activities and provide components Lot not specifically by the Interface Contractivit to issiful / mount and power	0 6302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/hem	1
60	Project Wide	7085	Electrical LV	the components required. Remove fittings, outlets, containment, Lot	3,400.00 Rate only 6302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/hem	1
				cabling made redundant by modifications to Station, platform, building and rooms.					
60	Project Wide	7085	Electrical LV	Supply and install cabling and outlets to new Lat / servised Station, platform, building and rooms.	22,553.00 Itate only 6302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/ðem	1
40	Project Wide	7085	Electrical LV	Remove filtings, outlets, containment, Lot cabling made redundant by modifications to Station, platform, building and nooms.	0 4302	Subcontract Uncommitted SC001	Bechical, CCIV and Comms	/hem	1
60	Project Wide	7085	Electrical LV	Supply and install cabling and outlets to new Lot / revised Station, platform, building and rooms.	0 4302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/item	1
40	Project Wide	7085	Electrical LV	Supply and install cabling and outlets to new Lot / revised Station, platform, building and	0 4302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/item	1
60	Project Wide	7085	Electrical LV	scorms. Supply and install the new cabiling (please Lot refer to the Clentrock cable schedule - Station Filter Optic and LAN ((on this line	0 6302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/8em	1
		-	B	install = install + terminate + test + commission)				0	
40	Project Wide	7085	Electrical LV	Identify and semare all redundant cables Lot (please specify)	0 4302	Subcontract Uncommitted \$C001	Bechical, CCIV and Comms	/item	1
60	Project Wide	7085	Electrical LV	Supply and install new cable containment Lot where needed (please specify the containment route per cable run)	5,509.00 Role only 6302	Subcontract Uncommitted \$C001	Bechical, CCIV and Comms	/item	1
60	Project Wide	7085	Bechical LV	Remove any cable containment and Lot associated parts made redundant by the works	4.475.00 Italie only 4302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/bem	1
5				works Preliminaries Glenbrook	70,222.00				
60	Project Wide	7085	Bechical LV	Preliminaries 13	1 12,510.00 12,510.00 6302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/bem 12,51	
60	Project Wide	7085	Bechical LV	Mobilisation and Demobilisation of plant, item equipment and labour	1 5,402.00 5,402.00 6302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/bem 5,40	2 1 5,402.00
60	Project Wide	7085	Bechical LV	Waste Disposal - not included as part of Item MCC casts	1 13,000.00 13,000.00 4302	Subcontract Uncommitted SC001	Bechical, CCTV and Comms	/8em 13.00	0 1 13,000.00
60 60	Project Wide	7085	Bechical LV Bechical LV	Construction Plant and Equipment Was Temporary Services including CCTV, Lighting, Bern	1 6,760.00 6,760.00 6302	Subcontract Uncommitted \$2001 Subcontract Uncommitted \$2001	Bectrical, CCTV and Comms Bectrical, CCTV and Comms	/hem 6.76	0 1 4,740.00
6	Project Wide	7085	Bechical LV	Tolets & Office Supply & Initial CSR as per drawings m	Excluded	addenia i dicentina di actor	Lacinca, echi una commi	,mm	
60	Project Wide	7085	Bechical LV	Supply & Initial Fits as per drawings Each	Eccluded				
60	Project Wide	7085	Bechical LV	Supply & Install lighting footings (450dia x Each 2m)	Excluded				
60	Project Wide	7085	Bechical LV	Supply & Initial lighting footings (450dia x Each 2m)	Excluded				
5				Additional items	40,979.48				
60	Project Wide	7085	Bechical IV	SPUPA Rack Works & Hearing loop equipment Each	0				
60 60	Project Wide	7085	Bechical LV Bechical LV	S&I digital clocks and cabling Each New Commit rack (combined services) Each	0				
60	Project Wide	7085	Bechical IV	Additional lighting poles for replacing of Each existing poles	2 6,000.00 12,000.00 4302	Subcontract Uncommitted \$C001	Bechical, CCTV and Comms	/8em 12,00	0 1 12,000.00
60 60	Project Wide	7085 7085	Bechical LV Bechical LV	Additional foolings for Light Pales (Matfam) Each Supply & Instal LV Cable from ISM8 to Signal - Rem	2 4,489.84 8,979.68 6302 1 20,000.00 20,000.00 6302	Subcontract Uncommitted SC000 Subcontract Uncommitted SC001	Subcontract Uncommitted Biechical, CCTV and Comms	Sum 8,98 /Nem 20,00	
4				Solar Power					
5	Basilos * **** *	gaar	Realized ***	Solar Panels and Associated System					
60	Project Wide	7085	Bechical LV	Supply and install / mount a solar panels - 15 (fake out price for the supply and install as include in Building package??)	o				
60	Project Wide	7085	Bechical LV	Supply and instal / mount solar panel 15 isolation enclosures and inverter	0				
40	Project Wide	7085	Bechical IV	Supply and install a suitably rated and LS compliant insetter/controller for the solar system in the SSER room	o				
60 60	Project Wide	7085	Bechical LV Bechical LV	Supply and install a Battery storage system IS Supply and install the new cabling (please IS	0				
60	Project Wide	7085	Bechical LV	refer to the Glenbrook cable schedule) Lighting Control System 13	13,770.00 Rote only 4302	Subcontract Uncommitted \$2001	Bechical, CCIV and Comms	/ðem	1
5 60	Project Wide	7085	Bechical LV	Other Associated Works Temporary shuckural hoarding within rail bern conider for construction of panel	54,000.00 Rate only 6302	Subcontract Uncommitted 3C021	Gienbrook Packages	/hem	1
60			Bectrical LV	foundations, mounting frame	10,000.00 litate only 6302	Subcontract Uncommitted \$C021	Glenbrook Pockoges	/ðem	1
	Project Wide	7085							
60	Project Wide Project Wide	7085 7085	Bechical LV Bechical LV	Solar panel mounting frame foundations - Item allowance of \$60,000 for piling/pad footings	40,000.00 Rate only 4302	Subcontract Uncommitted SC021	Glenbrook Packages	/tem	1
	Project Wide	7085	Bechical IV	allowance of \$40,000 for piling/pad footings fbc					1
60 60				alowance of \$40,000 for pling/pad footings		Subcontract Uncommitted SC021 Subcontract Uncommitted SC021 Subcontract Uncommitted SC021	Glenbrook Packages Glenbrook Packages Glenbrook Packages	/kem /kem	1
60	Project Wide	7085 7085	Bechical LV	allowance of \$40,000 for piling/pad footings lbc Panel mounting frame Item	0 6302	Subcontract Uncommitted SC021	Glenbrook Packages	/ham	1
40 40	Project Wide	7085 7085	Bechical LV	alterance of \$40,000 for psingstroad footings floc Panel mounting forme Rem C3R form east bank under nail to platform SSRR Rem	0 4352 0 4352	Subcontract Uncommitted SC021	Glenbrook Packages	/ham	1 1 1

60	Project Wide	7060	HV Instantiation General	Supply all hardware and jewellery including, but not limited to, cross arms, insulaton, earth wire supports and all other necessary fittings and micelianeous hardware for installation and commissioning.	15	1	24,722.10	24,722.10 4302	Subcontract Uncommitted	SC009	ASP/HV Works	/ðem	24,722	1	24,722.10
60	Project Wide	7060	HV Ironsmission General	Re-register feeders onto existing pole	No	2	6,521.73	13,043.46 6302	Subcontract Uncommitted	SC009	ASP/HV Works	/hem	13,043	1	13,043.46
60	Project Wide	7060	HV Inanemission General	Supply and install 20m earth electrodes at existing UGOH pole.	No	2	11,862.22	23,724.44 6302	Subcontract Uncommitted	SC009	ASP/HV Works	/bem	23,724	1	23,724.44
40	Project Wide	7060	HV Transmission General	Remove CHW line between Poles and replace with new 240AL3 11kV Cable.	13	1	13,043.46	13,043.46 6302	Subcontract Uncommitted	SC009	ASP/HV Works	/hem	13,043	1	13,043.46
40	Project Wide	7060	HV Transmission General	Test new 11kV conductors in preparation for and in advance for possession	15	1	29,669.60	29,669.60 6302	Subcontract Uncommitted	SC009	ASP/HV Works	/Nem	29,670	1	29,669.60
40	Project Wide	7060	HV Inansmission General	Connect and commission new 1 IkV conductors from UCOH pole to new fransformer, de-commission existing aerial feaders from pole 780 to existing Transformer	13	1	154,387.63	154,287.63 6302	Subcontract Uncommitted	5C009	ASP/HV Works	(ðem	154,388	1	154,387.63
60	Project Wide	7040	HV Iransmission General	Remove redundant cierial feeders from pole	span	4	972.54	3,890.16 6302	Subcontract Uncommitted	5C009	ASP/HV Works	/bem	3,890	1	3,890.16
60	Project Wide	7060	HV Instantiation General	Transport reclundant 11Kv cables and equipment to Sydney Trains Chullora location.	13	1	6,434.36	6,434.36 6302	Subcontract Uncommitted	SC009	ASP/HV Works	/item	6,434	1	6,434.36
60	Project Wide	7060	HV Transmission General	Supply, Installation Testing and Commissioning of Isolation Transformer and padmount substation	15	1 :	230,000.00	230,000.00 4302	Subcontract Uncommitted	SC009	ASP/HV Works	/item	230,000	1	230,000.00
40	Project Wide	7040	W Innersian General	Pan and prepare commissioning documentation and plana partor to wolk and commission of alements and stages of works including compatibion of selevant commissioning documentation Commission event plan hour by hour all tell documents at assemment Mathodology Commission manager	13	1	21,429.05	21,629.05 4302	Subcontract Uncommitted	SC009	ASP/HV Works	Jäen:	21,629	I	21,629.05
40	Project Wide	7060	HV Transmission General	As Built / As Commissioned design documentation	15	1	3,400.00	3,400.00 6302	Subcontract Uncommitted	5C009	ASP/HV Works	/Nem	3,400	1	3,400.00
4				High Voltage Electrical - 11kVa				64,531.00							
60	Project Wide	7060	HV Transmission General	Low voltage supply cables between padmount transformer and BMS8	13	1	58,031.00	58,031.00 4302	Subcontract Uncommitted	SC001	Bechical, CCTV and Comms	/Bem	58,031	1	58,031.00
40	Project Wide	7060	HV Transmission General	Low Voltage temporary cable between 5X58 and old M58	15	1	6,500.00	6,500.00 6302	Subcontract Uncommitted	50001	Electrical, CCTV and Comms	/hem	6,500	1	4,500.00
3				RAIL SYSTEMS				52,034.00							
4				Signalling & Support				20,000.00							
40	Project Wide	7060	HV Transmission General	Signaling Support during possession	Item	1	20,000.00	20,000.00 6302	Subcontract Uncommitted	SC003	Signaling Works	/item	20,000	1	20,000.00
4 SYSTEM				Modification of Overhead Wiring Systems				32,034.00							
c				Revised works as per price/programme workshop 17/09/2018 (yet to be redesigned) Existing OHW to remain	ŀ										
60	Project Wide	7060	HV Ironsmission General	Survey & monitor	hem	1	5,120.00	5,120.00 6302	Subcontract Uncommitted	SIC50102	Civil Work	/item	5,120	1	5,120.00
60	Project Wide	7060	HV Transmission General	Temporary bracing (require power out)	hem	1	5,896.00	5,894.00 6302	Subcontract Uncommitted	SC:50102	Civil Work	/item	5,894	1	5,896.00
60	Project Wide	7060	HV Transmission General	Electrical check & ensure sufficient tralation	Item	1	3,000.00	3,000.00 6302	Subcontract Uncommitted	SC50102	Civil Work	/Nem	3,000	1	3,000.00
60	Project Wide	7060	HV Transmission General	Earthing/bonding	Item	1	4,000.00	4,000.00 4302	Subcontract Uncommitted	SC50102	Civil Work	/hem	4,000	1	4,000.00
40	Project Wide	7060	HV Transmission General	Allow for polycarbonate cladding of existing OHW at platform to isolate	tem	1	4,720.00	4,720.00 4302	Subcontract Uncommitted	SC:50102	Civil Work	/bem	4720	1	4,720.00
60	Project Wide	7060	HV fransmission General	Extra Over for canopy roof to be built around stanchion & flash in	tem	1	400	400 4302	Subcontract Uncommitted	SC50102	Civil Work	/Nem	400	1	400
c				Design Development 30/10/2018											
60	Project Wide	7040	HV Transmission General	Add persepex cladding to existing CHW stanchion	Item	1	8,900.00	8,900.00 6302	Subcontract Uncommitted	SC:50102	Civil Work	/hem	8,900	1	8,900.00
3				Contingencies (Reimbursement Cost)				484,994.00							
60	Project Wide	9703	Stage 2 Conlingency	Inherent Risks	Item	1	132,334.00	132,334.00 4961	Project Confingency	1003	Risks and Corrligencies	/item	132,334	1	132,334.00
60	Project Wide	9703	Stage 2 Confingency	Confingent Risks	ltern	1 3	517,850.00	517,850.00 4961	Project Confingency	1003	Rsks and Corrigencies	/item	517,850	1	517,850.00
60	Project Wide	9703	Stage 2 Confingency	Price Escalation	Item	1	34,810.00	34,810.00 4961	Project Confingency	1003	Risks and Corrigencies	/item	34,810	1	34,810.00
2				Management Fee											
80	Management fee	0901	Management Fee	Management Fee		1	0	4304	ManagementFee	1002	Management Fees	/hem		1	

RE: RFQ - Glenbrook Station Building Works

- From: Ryan Camilleri <ryan.camilleri@downergroup.com>
- To: Mal Helweh <mal@maizegroup.com.au>
- Cc: Bishoy Abdelnour

 bishoy.abdelnour@downergroup.com>, Andrew Gayed <andrew.gayed@downergroup.com>
- **Date:** Tue, 21 May 2019 07:19:33 +1000

Hi Mal, Just chasing up your quotation. Regards, **Ryan Camilleri** Site Engineer Transport and Infrastructure



Relationships creating success



E | Ryan.Camilleri@downergroup.com Ground Floor, Shop 3, 77 Pacific Highway North Sydney NSW 2060

www.downergroup.com



Think before you print

From: Ryan Camilleri Sent: Tuesday, 7 May 2019 6:36 PM To: mal@maizegroup.com.au Cc: Bishoy Abdelnour <Bishoy.Abdelnour@Downergroup.com> Subject: RE: RFQ - Glenbrook Station Building Works Hi Mal, Further to the below, please see attached;

- Downer Short Form Contract Template
 - BOQ (revised) to price against
 - Contractor Evaluation Form that will need to be satisfied prior to works commencing.

Comments regarding BOQ;

- Downer to supply some permanent materials, not all. Refer to BOQ
- Consider that rubbish will either be disposed from station building by Downer, rubbish to be stored within Downer supplied bags.
- Future Family Accessible Toilet (FAT) floor option 2 to be advised once obtained from Designer. Concrete slab is 200mm thick slab (Downer to supply reo and concrete, subbie to steel fix and finish concrete).

Drawings

Drawings Complete Package - <u>https://www.dropbox.com/sh/9hf60ry01pc860o/AACJKHIEeSM5rLhTZw0wx2nAa?dl=0</u>
 Works to Start – 3rd June 2019

Works to Finish – 30th August 2019

Could you please submit your price by Monday 20th May 2019 COB.

Any questions, please give me a call or send across an email.

Ryan Camilleri Site Engineer

Transport and Infrastructure





E | <u>Ryan.Camiller(@downergroup.com</u> Ground Floor, Shop 3, 77 Pacific Highway North Sydney NSW 2060

www.downergroup.com

Think before you print



From: Ryan Camilleri Sent: Monday, 6 May 2019 2:52 PM To: mal@maizegroup.com.au Cc: Bishoy Abdelnour < Bishoy.Abdelnour@Downergroup.com > Subject: RFQ - Glenbrook Station Building Works Hi Mal. I am currently working on the Glenbrook Station Upgrade project and would like you to give me a quote on the Building Works. Dropbox link to drawings; https://www.dropbox.com/sh/eulr2yrm7b5hk3g/AACw0LF6R2OaAHBHLJgi8BJka?dl=0 Drawings in particular are pages; 6,11,12,13,14,15. Also attached is Dower's Subcontract Short Form template and the BOQ to price against (please note Downer will supply all permanent fixtures). Could you please submit your price by Monday 20th May 2019 COB. Regards, Ryan Camilleri Site Engineer Transport and Infrastructure



Relationships creating success

T | 7347 **M** | 7347

E | <u>Ryan.Camiller(@downergroup.com</u> Ground Floor, Shop 3, 77 Pacific Highway North Sydney NSW 2060 **www.downergroup.com**



Think before you print

Downer

This message is for the named person's use only. It may contain confidential, proprietary or legally privileged information. Downer EDI and its subsidiaries do not waive any confidentiality, copyright or legally privileged information by any transmission. If you receive this message in error, please immediately delete it and all copies of it from your system, destroy any hard copies of it and notify the sender. You must not, directly or indirectly, use, disclose, distribute, print, or copy any part of this message if you are not the intended recipient. Downer EDI and any of its subsidiaries each reserve the right to monitor all e-mail communications through its networks. Any views expressed in this message are those of the individual sender, except where the message states otherwise and the sender is authorized to state them to be the views of any such entity.

RE: Glenbrook Station BOQ

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
Date:	Tue, 21 May 2019 16:38:31 +1000
Attachments:	Glenbrook - Building BOQ.xlsx (25.05 kB)

Hey bro, Please find attached. Call me if you want to go through it or we can have argileh at Gebrans. Thanks

Regards, Mal Helweh

MANNEN MAIZE GROUP PTY LTD Phone: (02) 9773 1027

Email: mal@maizegroup.com.au Website: www.maizegroup.com.au This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at info@maizegroup.com.au or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you. From: Andrew Gayed <andrew@mansionbuilding.com.au> Sent: Tuesday, 16 April 2019 10:26 AM To: Mal Helweh <mal@maizegroup.com.au> Subject: Glenbrook Station BOQ Hi Mal, Please see attached as discussed. Apologies, actual budget is approx. \$330k, I've highlighted it in yellow for you. Cheers

Andrew Gayed Mansion Building Pty Ltd P: (02) 9606 6206 M: 0 815 E: andrew@mansionbuilding.com.au

Bill Code Code	Bill Code Description	Task code Code	Task code Description	Bill description	Unit	Bill Quantity*	Net Rate	Net Amount	
P	atform	9302	Station Buildings	Station Building Strip out doors, walls, finishes, fixtures,etc.,	ltem	1	32 540 00	32.540.00	
	atform	9302	Station Buildings	remove walls, form openings as required Remove existing timber framed floors, reduce floor height so new slab (msd.	Item	1	6210	6,210.00	
PI	atform	9302	Station Buildings	elsewhere) is level threshold with platform Remove existing brick privacy screen at male toilet & part concrte platform for AC	Item	1	4600	4,600.00	
10 PI	iatform	9302	Station Buildings	enclosure Hydraulic Services : cap off & temporary disconnect for demolifion works	ltem	1	3,200.00	3,200.00	
) PI	atform	9302	Station Buildings	Electrical Services : cap off & temporary disconnect for demolition works	Item		3,200.00	0.00	Rate Only for To
				Concrete Slab Concrete					
20 PI	atform	9302	Station Buildings	Prepare subgrade, sand fill to RL, WPM	m2	33	405	13,365.00	
0 PI	atform	9302	Station Buildings	32MPa concrete in slab on ground to	m3	8	1,600.00	12,800.00	
D PI	atform	9302	Station Buildings	internal rooms Isolation joint	Item	1	500	500.00	
	atform	9302	Station Buildings	Dowel joint	Item		550.00	550.00	
P	atform	9302	Station Buildings	Surface finish	m2	33	350		This item has be
				Formwork					
0 P	atform	9302	Station Buildings	Formwork slab edge	m				
20 PI	atform	9302	Station Buildings	Reinforcement Reinforcement to slab, SL82 mesh	m2	33	65	2,145.00	
			-	Existing Walls					
	latform	9302	Station Buildings	Work to existing external walls of buildings - no works					
20 PI	latform	9302	Station Buildings	Make good existing (assumed brickwork) external walls where platform level is changed, to match existing walls above	m	69	150	10,350.00	
D PI	latform	9302	Station Buildings	Make good existing internal walls where FFL is changed, to match existing walls above	m	25	249	6,225.00	
D P	atform	9302	Station Buildings	Adjust threshold step to door at change in floor level	leaf	2	1200	2,400.00	
) Pi	atform	9302	Station Buildings	Masonry Face brick screen wall	m2	14	380	5.320.00	
, PI	anom	7302	aranan bullaings	Face brick screen wall Stud Frames	inz	14	380	a,320.00	
0 PI	atform	9302	Station Buildings	Stud frame internal walls	m2				
D PI	atform	9302	Station Buildings	Stud frame internal riser walls	m2	9	160	1,440.00	
P	atform	9302	Station Buildings	Stud frame internal false wall	m2	18	160	2,880.00	
PI	atform	9302	Station Buildings	Insulations Wall insulation	m2	27	32	864.00	
P				Plasterboard & Fibre Cement					
				Walls					
	atform	9302	Station Buildings	Fibre cement wall linings to framed walls	m2	27	150	4,050.00	
P	atform	9302	Station Buildings	Reline existing internal walls for new finish - allow fibre cement with batten frame or cement render	m2	59	160	9,440.00	
P	iatform	9302	Station Buildings	Cellings Suspended plasterboard ceiling with comice/trims	m2	19	250	4,750.00	
				Doors					
P	atform	9302	Station Buildings	Remove door, lower door opening to suit new FFL, enlarge opening to provide 850mm clear door leaf opening, new single leaf external grade doorset complete with hardware	No.	2	2,650.00	5,300.00	
20 PI	atform	9302	Station Buildings	Windows Privacy film to existing windows	m2	10	240	2,400.00	
				Waterproofing					
D PI	latform	9302	Station Buildings	Waterproofing to wet area floors, upturn 1500mm above floor	m2	54	88	4,752.00	
20 PI	atform	9302	Station Buildings	Tiling Wall tiling to wet areas - Glennon Tiles	m2	72	350	25,200.00	
20 PI	atform	9302	Station Buildings	W310 300 x 100mm with epoxy grout	m2	18	380	6.840.00	
	attorm	9302	Station Buildings	GN13140 600 x 300mm with epoxy grout Coved skirling tiling to wet areas -	m2 m	24	380	6,000.00	
0 P	atform	9302	Station Buildings	Glennon Tiles to match floor tiles with epoxy grout Threshold tile	m	2	650	1,300.00	
				Fixtures & Fittings		-			
D PI	atform	9302	Station Buildings	Staff Ambulant WC Hand dryer - Dyson Airblades V Code A812	No.	1	480.00	480.00	
	atform	9302	Station Buildings	white Toilet Roll Holder - Bobrick B2890	No.	1	150.00	150.00	Install Only, to be
	attorm attorm	9302	Station Buildings	SS grabrails to staff ambulant WC	NO.	1	150.00	150.00	Install Only, to be
) Pi	atform	9302	Station Buildings	Soap Dispenser - Kimberley Clark Aquarlus Hand Cleanser Dispenser White/1 litre 69480	No.	1	100.00	100.00	Install Only, to be
) PI	atform	9302	Station Buildings	Coat haok - SSS Metlam ML4159	No.	1	50.00	50.00	Install Only, to be
) P	atform	9302	Station Buildings	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 600W	No.	1	150.00	150.00	
				FAT					install Only, to be
0 P	latform	9302	Station Buildings	Hand dryer - Dyson Airblades V Code AB12 white	No.	1	480.00	480.00	Install Only, to be
D PI	atform	9302	Station Buildings	Toilet Roll Holder - Bobrick B2890	No.	1	150	150.00	Install Only, to be
	atform	9302	Station Buildings	SS grabrails to FAT WC	No.	1	150.00	150.00	Install Only, to be
D PI	atform	9302	Station Buildings	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480	No.	1	100	100.00	Install Only, to b
) PI	atform	9302	Station Buildings	Baby Change Table - Metlam Foldable - Code ML9100EH	No.	1	350.00	350.00	Install Only, to b
) Pi	atform	9302	Station Buildings	Code ML910UEH Coat hook - SSS Metlam ML4159	No.	1	50	50.00	Install Only, to b
			<u>.</u>						

	20	Platform	9302	Station Buildings	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant	No.	1	150.00	150.00	
					mounting equal to Bobrick - 1000H x 600W					Install Only, to be supplied by Downer
	20	Platform	9302	Station Buildings	Sanitary bin - Canon Hygeine SS Modesty	No.	1	150	150.00	initial only, to be applied by bowner
					tray					Install Only, to be supplied by Downer
	20	Platform	9302	Station Buildings	Nappy disposal bin - Canon Hygeine nappy disposal bin	No.	1	150	150.00	Install Only, to be supplied by Downer
	20	Platform	9302	Station Buildings	Sharps bin (installed at existing toilets at	No.				
					other stations - not scheduled - no allowance)					
c					Existing Acccess Ramp Cupboard					
	20	Platform	9302	Station Buildings	Relocate existing acccess ramp cupboard	No.	2	500	1,000.00	
c					Painting					
c					Allow painting to new works only					
c					Apply paint system to :-					
	20	Platform	9302	Station Buildings	Internal walls linings	m2	14	44	616.00	
	20	Platform	9302	Station Buildings	Internal ceiling linings	m2	19	44	836.00	
	20	Platform	9302	Station Buildings	Single leaf external grade doorset	No.	2	400	800.00	
	20	Platform	9302	Station Buildings	Internal windows	m2	5	120	600.00	
c					Apply anti graffili coating equal to Sure Seal Graffili Shield to (apply to internal					
					public accessible room only) :-					
	20	Platform	9302	Station Buildings	Wall tiling to wet areas - Glennon Tiles F725 600 x 300mm with epoxy grout	m2	72	60	4,320.00	
	20	Platform	9302	Station Buildings	Door leaf	No.	2	250	500.00	
c					Signage				0.00	
	20	Platform	9302	Station Buildings	Door signage as required (per door)	No.	2	257	514.00	
c					Building Services					
	1				Hydraulic Services - Building Works					
	5				Platform Building Alterations					
c					No allowance for hot water to FAT or Staff/AMB WC					
	20	Platform	9302	Station Buildings	Sewer - allowance to modify existing in	Item	1	10,650.00	10,650.00	
		Distance .	0202	Challen Duildin as	ground sewer to suit new layout		,	5 155 00	6 1 5 6 00	
	20	Platform	9302	Station Buildings	Water - allowance to modify existing water to suit new layout	ltem	I	5,155.00	5,155.00	
	5				FAT					
		Platform	9302	Station Buildings	wc	No.	2	6,100.00	12,200.00	
		Platform	9302	Station Buildings	Basin	No.	2	5,000.00	10,000.00	
		Platform	9302	Station Buildings	Floor waste	No.	2	500.00	1,000.00	
		Platform	9302	Station Buildings	Тар	No.	2	1100	2,200.00	
	5				Staff/AMB WC					
		Platform	9302	Station Buildings		No.	1	6,100.00	6,100.00	
	20	Platform	9302 9302	Station Buildings Station Buildings	Basin Floor waste	No.	1	5,000.00	5,000.00	
		Platform	9302	Station Buildings	Tap	NO.	1	1100	1 100 00	
	20	haildin	7302	sidilori bullariga	Staff Room	NO.		1100	1,100.00	
	20	Platform	9302	Station Buildings	Sink	No.	1	5,000.00	5,000.00	
	20	Platform	9302	Station Buildings	HWU	No.	1	1,750.00	1,750.00	
	20	Platform	9302	Station Buildings	Boil water unit - assume n/a	No.			0.00	
	5				Cleaners Room					
	20	Platform	9302	Station Buildings	Cleaners sink	No.	1	5,000.00	5,000.00	
	20	Platform	9302	Station Buildings	HWU	No.	1	1,750.00	1,750.00	
	5				Air Conditioner Condensor Tundish					
	20	Platform	9302	Station Buildings	Air Conditioner condensor tundish	No.	2	3,950.00	7,900.00	
	1				Mechanical Services - Building Works					
					Lift 1 - Platform					
		Platform	9302	Station Buildings	Mechanical air supply to lift shaft	Item	1		0.00	No allowance made as confirmation on lift shaft type needed
	20	Platform	9302	Station Buildings	Platform Building Alterations Mechanical exhaust to Staff ambulant WC	Item	1	6,000.00	6,000.00	
						Item	,	6.000.00	6.000.00	
		Die Maart	0200							
	20	Platform	9302	Station Buildings	Mechanical exhaust to FAT					
	20 20	Platform Platform	9302 9302	Station Buildings Station Buildings	Mechanical exhaust to FAT	ltem	1	6,000.00	6,000.00	
				-						

Preliminaries for Maize Group


Item

324,222.00

43500


43500

1



Vol 26.1

54





E19-1595-AS-02-279-PR-0001







. 5G 88

Easier for me in one but if you probably best if individual so we can get answers quicker? What you think?

Individual would be better for responses


16 Jul 2019 at 4:37 pm

Hang Up Message: 0815 reached your MessageBank on 16/07/2019 at 16:37 & did not leave a message.

23 Jul 2019 at 1:30 pm









E19-1595-AS-02-279-PR-0001

. 5G EB

្រា





30 Jul 2019 at 10:15 am

Hey bro,

Call me when you can as i am getting food ready for tomorrow and want to make sure the BBQ will be onsite so I know what I need to bring with me.

31 Jul 2019 at 7:55 am



14 Aug 2019 at 6:33 pm





Re: RIW Contractors

From:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
То:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
Deter	Mad 40 Jun 2040 40.00.04 14000

Date: Wed, 19 Jun 2019 19:09:21 +1000

Plumbing - Paul Ross

 ⁽⁰²⁾ 9625 9222 | 5 001 ▲ (02) 9625 9200

 ⁽⁰²⁾ Paul@franklinsaustralia.com.au

Electrical - Elecdata Thomas Vincenti 0456456020 Thomas Vincenti | ElecData <<u>thomas@elecdata.com.au</u>>

On Wed, Jun 19, 2019 at 6:52 PM Andrew Gayed andrew@mansionbuilding.com.au> wrote:

Studwork & Sheeting – Intra Design (intra.design@hotmail.com) Vincent Tiling – Ontrack Tiling (cos@ontracktiling.com.au) Cosimo Cinotta Hydraulic – All Hours Plumbing (sam@allhoursplumbing.net.au) Sam Qi Sheeting and glazing - Grand Eagle M: 0403 332 529 E: jack@grandeagle.com.au Tiling - Cosimo Cincotta 0425 048 003 cos@ontracktiling.com.au

Andrew Gayed Mansion Building Pty Ltd P: (02) 9606 6206 M: 0 815 E: andrew@mansionbuilding.com.au

Andrew Gayed Mansion Building Pty Ltd P: (6 6206 M: 0 815 E: andrew@mansionbuilding.com.au

From:	Andrew Gayed	<andrew@mansion< th=""><th>building.com.au></th></andrew@mansion<>	building.com.au>
-------	--------------	---	------------------

To: Mal Helweh <mal@maizegroup.com.au>

Date: Wed, 19 Jun 2019 19:01:27 +1000

- 1. "Set Out" has excluded from SOW please amend the subcontract to reflect this.
- 2. All design and drawings are by others and is the responsibility of others please delete clause 5 and remove design and drawing liability from Mansion.
- 3. Mansion will not be providing bank guarantees. please delete clause 8.1a

Salient clauses:

8.2 Retention Monies

(a) If Item 18 provides that retention monies are to be deducted in lieu of the provision of Bank Guarantees then Downer is entitled to retain 10% of each progress payment until the amount retained equals the percentage of the Subcontract Sum set out in Item 20 (10%) and such retention monies shall be security for the performance of the Subcontractor's obligations under this Subcontract.

8.4 Reduction of security

Subject to Downer's rights under this Subcontract (including clauses 8.7 and 22.8), provided that the Subcontractor has given Downer an executed Deed of Release in the form set out in Schedule 3, and subject to the exercise of any right of recourse that Downer may have to security, Downer must reduce by the percentage stated in Item 21 of the amount then held by Downer as a Bank Guarantee or as retention monies on the later of 42 days after the Date of Practical Completion for the whole of the Work (Subcontractor's Work) and the date on which all Defects identified at Practical Completion have been rectified. 8.5 Release of Security

Subject to clause 8.7 and Downer's right to exercise a right of recourse that Downer may have to security. Downer will release the balance of the amount then held as a Bank Guarantee or as retention monies under clause 8.2 on the later of 42 days after: (a) the date on which the Subcontractor gives Downer an executed Deed of Final Release in the form set out in Schedule 4; (b) the issue of the Final Certificate under clause 22.4; and

(c) the date on which all Defects identified during the Defects Liability Period have been rectified.

High Level Summary: Downer will retain 10% of each payment claim until 10% of the Subcontract Sum is retained. 50% of the value of the retention shall be released 42 days after the Subcontractor is granted PC. The final 50% shall be released 42 days after Final Certificate has been issued. Final Cert to be issued within 20 BD of the expiration of DLP.

- 4. All cranage, scaffolding is excluded from Mansion SOW please amend the subcontract to reflect this. Haulage and handling of Mansion equipment plant is Mansions responsibility (unless otherwise constrained by other site works/access impacting our ability to attend as needed.
- 5. This subcontract signs us to obligations under the Head Contract (HC). Mansion has not sighted any HC details or SOW please delete any reference that's ties Mansion to the HC from the subcontract
- 6. This subcontract signs us up for consents, permits and authorisations we have only allowed for permits/consents/authorisations for the movement of equipment etc – any other for permits/consents/authorisations will need to be covered/addressed by Downer. Please amend subcontract to reflect this.
- 7. LD's are \$5,990 per day, date for practical completion is the 22nd of Feb. Mansion requests LD's to be reduced to \$1,000/day and capped at 5% of the total subcontract value. Regarding date for practical completion we will need 120 days from the commencement of the permanent permanent. Dates TBC. Please amend the subcontract to reflect this.
- 8. Mansions Program has to be submitted to Downer formally at least 7 days prior to commencement or we are in subcontract breach (start date TBC by Downer). Please amend the subcontract to reflect this and delete the requirement to issue a program as it is mainly dependant on others' completion of works.
- 9. The subcontract says Mansion are responsible for "as built" drawings. Mansion has not allowed for any As-built surveys or drawings. This is by others. Please amend the subcontract to reflect this.
- 10. Percentage amount on overheads and profits marked at 5%. Please amend to 15%.
- 11. Mansion are responsible for the plans. All plans are created and issued by others. Mansion is only following the plans please amend the subcontract to remove responsibility from Mansion.
- 12. Protection of works, if there is any damage done to Mansions product (by others) Mansion are responsible to fix it at our expense. Please amend the subcontract to something more suitable. I'e if Mansion causes damage to piles then Mansion is to repair.

Andrew Gaved

Mansion Building Pty Ltd P: (02) 9606 6206 0 815 M @mansionbuilding.com.au E:

Subcontract Agreement Glenbrook

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	Scott Harman <scott.harman@downergroup.com></scott.harman@downergroup.com>
Cc:	Andrew Gayed <andrew.gayed@downergroup.com></andrew.gayed@downergroup.com>
Date:	Wed, 26 Jun 2019 12:36:05 +1000

Hi Scott,

Please see below comments I have added. If the contract can change to reflect this, I will have it signed and returned:

- 1. Item 17 All design and drawings are by others and is the responsibility of others please delete clause 5 and remove design and drawing liability from Maize
- 2. All cranage, scaffolding is excluded from Maize Haulage and handling of Maize equipment plant is Maize responsibility (unless otherwise constrained by other site works/access impacting our ability to attend as needed).
- 3. This subcontract signs us to obligations under the Head Contract (HC). Maize has not sighted any HC details or SOW please delete any reference that's ties Maize to the HC from the subcontract
- 4. This subcontract signs us up for consents, permits and authorisations we have only allowed for permits/consents/authorisations for the movement of equipment etc any other for permits/consents/authorisations will need to be covered/addressed by Downer.
- 5. Liquidated Damages are \$5,990 per day, date for practical completion is the 1st November 2019. Maize requests Liquidated Damages to be reduced to \$800/day and capped at 5% of the total subcontract value.
- 6. Maizes Program has to be submitted to Downer formally at least 7 days prior to commencement or we are in subcontract breach (start date TBC by Downer). Please amend the subcontract to reflect this and delete the requirement to issue a program as it is mainly dependent on others' completion of works.
- 7. The subcontract says Maize are responsible for "as built" drawings. Maize has not allowed for any As-built surveys or drawings. This is by others. Please amend the subcontract to reflect this.
- 8. Percentage amount on overheads and profits marked at 5%. Please amend to 12%.
- 9. States Maize are responsible for the plans. All plans are created and issued by others. Maize is only following the plans please amend the subcontract to remove responsibility from Maize.
- 10. Item 38 States Subcontractor's details for address as: 4/88 Victoria Street, Revesby NSW 2122. Please change to 4/88 Violet Street, Revesby NSW 2122

If you have any questions please do not hesitate to contact me. Cheers Regards,

Mal Helweh



GROUP PTY LTD Phone: (02) 9773 1027 Email: <u>mal@maizegroup.com.au</u> Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

FW: Glenbrook - Lift Exhaust System

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	Andrew Gayed <andrew.gayed@downergroup.com></andrew.gayed@downergroup.com>
Date:	Tue, 01 Oct 2019 13:52:05 +1000
Attachments:	V5 - Q850a.pdf (129.26 kB)

Hi Andrew.

As discussed, please see updated Quote. If you have any questions please do not hesitate to contact me. Cheers Regards. Mal Helweh



GROUP PTY LTD Phone: (02) 9773 1027

Email: mal@maizegroup.com.au Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at info@maizegroup.com.au or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

From: Mal Helweh

Sent: Friday, 30 August 2019 11:25 AM To: Ross Dean <Ross.Dean@Downergroup.com> Cc: Ryan Camilleri < Ryan.Camilleri@downergroup.com>; Andrew Gayed < Andrew.Gayed@Downergroup.com> Subject: Glenbrook - Lift Exhaust System Hi Ross. Please find attached quote for Glenbrook - Lift Exhaust System. If you have any questions please do not hesitate to contact me. Cheers Regards. Mal Helweh

GROUP PTY LTD Phone: (02) 9773 1027 Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at info@maizegroup.com.au or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

^EMaize Group Pty Ltd

4/88 Violet St Revesby NSW 2212 Australia accounts@maizegroup.com.au www.maizegroup.com.au ABN: 11 169 460 379

Quote: 850a

Quote

Quote date: 30/08/2019

Bill to:	Expiry:
Downer	29/09/2019
Triniti Business Campus 39 Delhi Road	
North Ryde NSW 2113	
Australia	

ITEM	DESCRIPTION	UNITS	UNIT PRICE (ex GST)	ΤΑΧ ΤΥΡΕ	AMOUNT (ex GST)
	 Scope of Works for Lift Exhaust: Allow for shop drawings. Supply and install 1 of Fantech CPEEC40 wall mounted fan to lift shaft as per plan complete with speed and temperature control. Test and commission ventilation systems. Provide O&M's on completion. Preliminiaries Note: The above fan is made to order, fan will be available in 4 weeks from date of order. 	1	20,090.00	GST	20,090.00
			Sub '	Total (av CST):	\$20,000,00

Sub-Total (ex GST):	\$20,090.00
GST:	\$2,009.00
TOTAL (inc GST):	\$22,099.00

Notes Exclusions:

- _____
- 1. Hazardous material removal (asbestos, lead etc.)
- 2. Hi-rail plant
- 3. Craneage
- 4. Scaffolding
- 5. CC/BCA certification
- 6. Temporary works design/certification
- 7. Liaising with Sydney Trains/TfNSW
- 8. Service searching/locating/NDD
- 9. Service relocation (other than shown on drawings)
- 10. Survey
- 11. Heritage works
- 12. Out of hours work
- 13. Site sheds/ablutions/laydown area
- 14. Waste disposal/skip bins
- 15. Earthing/bonding
- 16. Delays/hold ups outside of Maize's control
- 17. Ventilation louvres

18. No allowance made for electrical works from mechanical switchboard, only from lift switchboard as per notes on Mechanical Plans.

Note:

The above fan is made to order, fan will be available in 4 weeks from date of order.

Re: Glenbrook - Lift Exhaust System

From: Andrew Gayed <andrew.gayed@downergroup.com>

- To: Mal Helweh <mal@maizegroup.com.au>
- Date: Tue, 01 Oct 2019 15:34:41 +1000

Approved

Regards, Andrew

From: Mal Helweh <mal@maizegroup.com.au> Sent: Tuesday, October 1, 2019 1:52:05 PM To: Andrew Gayed <Andrew.Gayed@Downergroup.com> Subject: FW: Glenbrook - Lift Exhaust System Hi Andrew, As discussed, please see updated Quote. If you have any questions please do not hesitate to contact me. Cheers Regards, Mal Helweh

MAZE

GROUP PTY LTD Phone: (02) 9773 1027 Email: <u>mal@maizegroup.com.au</u> Website: <u>www.maizegroup.com.au</u>

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

From: Mal Helweh

Sent: Friday, 30 August 2019 11:25 AM

To: Ross Dean <Ross.Dean@Downergroup.com>

Cc: Ryan Camilleri < Ryan.Camilleri@downergroup.com>; Andrew Gayed < Andrew.Gayed@Downergroup.com>

Subject: Glenbrook - Lift Exhaust System

Hi Ross,

Please find attached quote for Glenbrook - Lift Exhaust System. If you have any questions please do not hesitate to contact me. Cheers Regards, Mal Helweh



GROUP PTY LTD Phone: (02) 9773 1027

Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

Downer

This message is for the named person's use only. It may contain confidential, proprietary or legally privileged information. Downer EDI and its subsidiaries do not waive any confidentiality, copyright or legally privileged information by any transmission. If you receive this message in error, please immediately delete it and all copies of it from your system, destroy any hard copies of it and notify the sender. You must not, directly or indirectly, use, disclose, distribute, print, or copy any part of this message if you are not the intended recipient. Downer EDI and any of its subsidiaries each reserve the right to monitor all e-mail communications through its networks. Any views expressed in this message are those of the individual sender, except where the message states otherwise and the sender is authorized to state them to be the views of any such entity.

WLS Contract

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	gayedwork@gmail.com
Date:	Mon, 26 Jul 2021 13:33:20 +1000
Attachments:	SIGNED - Subcontract Long (WLS-BLD) Maize.pdf (1.91 MB)



Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.



E19-1595-AS-2-279-PR-0001

Subcontract – Long Form

Subcontract – Long Form

Ref No: D-WLS-BLD

between

Downer EDI Works Pty Ltd

ABN 66 008 709 608

AND

Maize Group

ACN 169 460 379

for

Building Works at Wollstonecraft Station

DG-LG-TP020



Subcontract

Instrument of Agreement

Parties

Downer EDI Works Pty Ltd (ABN 66 008 709 608) of Triniti Business Campus, 39 Delhi Road, North Ryde NSW 2113 (**Downer**)

AND

Maize Group ACN 169 460 379 of 4/88 Violet Street, Revesby, NSW 2212 (Subcontractor)

Background

- A. Downer has been engaged by the Principal to carry out certain work under a Head Contract in connection with the Project.
- B. For the purposes of satisfying its obligations under the Head Contract, Downer wishes to engage the Subcontractor to carry out the Work.
- C. The Subcontractor has represented to Downer that it has the financial capacity, skill, experience, personnel, material and capability to carry out the Work in accordance with this Subcontract.
- D. The parties have agreed that the Work will be carried out by the Subcontractor in accordance with the terms and conditions of this Subcontract.

Agreement

- 1. This agreement is comprised of:
 - (a) this Instrument of Agreement;
 - (b) the attached General conditions of Subcontract including all Schedules; and
 - (c) the documents and information identified in Item 16 of the Subcontract Details,

(Subcontract Documents).

- 2. The Subcontractor shall perform the Work in accordance with the Subcontract.
- 3. In consideration of the Subcontractor performing the Work in accordance with the Subcontract and complying with its obligations under the Subcontract, Downer agrees to pay the Subcontract Sum to the Subcontractor in accordance with the terms of the Subcontract.



Executed for and on behalf of **Downer** by its duly authorised representative:

Signature

Print Name/position

Witness

Print Name

Date

Executed for and on behalf the **Subcontractor**, pursuant to s127 of the *Corporations Act 2001* (Cth)

Mal Helweh



Director

12/11/2020

Date



Contents

1	Definitions and Interpretation	6
2	The Work	10
3	Commencement	11
4	Subcontractor Warranties and Acknowledgements	11
5	Design	13
6	Subcontract Documents	14
7	Administration and Personnel	15
8	Security	16
9	Indemnity, Liability and Insurance	17
10	Assignment and Subcontracting	19
11	Legal Requirements	20
12	Site Conditions	21
13	Construction	21
14	Variations	23
15	Conduct On and in the Vicinity of the Site	24
16	Intellectual Property Rights	25
17	Reports and Approvals	25
18	Cleaning Up	25
19	Defects Liability Period	25
20	Time	26
21	Delay	28
22	Payment	29
23	Practical Completion	31
24	Industrial relations	32
25	Work Health and Safety	33
26	Environment	33
27	Default and Termination	33
28	Dispute Resolution	35
29	Claims	37
30	Goods and Services Tax	37
31	Security of Payment	38
32	General	38
33	Personal Property Securities Act	41
34	Compliance with Anti-Bribery Laws	41
35	Modern Slavery	42
36	Proportionate Liability	42
Subcor	ntract Details	44
Append	dix 1 – Form of Confidentiality Undertaking	68
Append	dix 2 – Consultant Deed of Covenant	69
Append	dix 3 – Form of Warranty	73
Append	dix 4 – Subcontractor's Statement	76
Append	dix 5 – Form of Subcontractor Deed	79
Append	dix 6 – Contractor's Certificate of Construction Compliance	82
Append	dix 7 – Contractor's Certificate of Completion	83



Appendix 8 – Schedule of Rates for Design Fee	
Appendix 9 – Form of Subcontractor Deed Poll	85
Appendix 10 – Final Subcontractor Handover Checklist	87
Exhibit G – LIST OF WARRANTIES REQUIRED FROM SUBCONTRACTORS	89
Schedule 1 – Scope of Works, Drawings, Specifications and Pricing Schedule	92
Schedule 2 – Further Purposes or Requirements	107
Schedule 3 – Deed of Release (Clause 8.4)	108
Schedule 3A – Deed of Final Release (Clause 8.5, 22.4)	110
Schedule 4 – Moral Rights Consent	112
Schedule 5 – New South Wales	
Schedule 13 - National Code	
Schedule 14 – Deed of Novation	118
Schedule 15 – Subcontractor's Warranty	122
Schedule 16 - Security of Payment	123



General Conditions of Subcontract

1 Definitions and Interpretation

1.1 Definitions

In this Subcontract:

Approval means any authorisation, assessment, accreditation, determination, registration, clearance, permit, licence, consent, certificate or other approval obtained or required or applying in connection with anything required or permitted to be done by the Subcontractor under this Subcontract;

Australian Standards means any Australian Standard (including as may be amended or replaced from time to time) issued by Standards Australia applying directly or indirectly to the Work;

Bank Guarantee means an unconditional undertaking without expiry in a form and from a financial institution approved by Downer;

Business Day means a day which is not a Saturday, Sunday or public holiday in the State or Territory in which the Work is carried out;

Claim means any claim, entitlement, action, suit, cause of action, cost, expense, demand, liability, whether by way of indemnity, under contract, in equity, under statute, in tort or otherwise and any other liability of any nature including a claim for an adjustment to the Subcontract Sum and a claim for an Extension of Time;

Collateral has the meaning given in the PPSA;

Compensable Cause means a breach by Downer of this Subcontract;

Confidential Information includes anything or document which Downer provides to the Subcontractor and any matter concerned with, or arising out of, this Subcontract, the Project or Downer which is disclosed to or learnt by the Subcontractor;

Consequential Loss means loss of use, opportunity, profit, anticipated profit, revenue, business or business opportunities and damage to goodwill, reputation or share price;

Convention on Contracts for the International Sale of Goods means the *United Nations Conventions on Contracts for the International Sale of Goods,* signed 11 April 1980, 1489 UNTS 3 (entered into force 1 January 1988);

Date for Practical Completion means the date stated in Item 2 of the Subcontract Details, as adjusted in accordance with this Subcontract but where an Extension of Time is allowed in any arbitration, litigation or expert determination binding on the Parties, it means the date resulting therefrom;

Date of Practical Completion is the date evidenced in a certificate of Practical Completion issued pursuant to clause 23.2 as being the date on which the Work reached Practical Completion or where another date is determined in any arbitration, litigation or expert determination binding on the Parties as the date on which Practical Completion was reached, that other date;

Defect means any:

- (a) error, deficiency, omission, non-conformity, fault, failure malfunction, irregularity or defect (including shrinkage, expansion, fading or settlement) in the Work or any Deliverable; and
- (b) aspect of the Work or any Deliverable that is not in accordance with the requirements of this Subcontract;

Defects Liability Period means, subject to clause 19.2, the period specified in Item 30;

Delay Costs means the costs described in clause 21.6(a);

Deliverable means documents, designs, drawings, specifications, reports and other information produced or provided (or required to be produced or provided) by or on behalf of the Subcontractor in the performance of the Work and, where clause 5 applies, includes the Design Documents;

Design Documents means the drawings, specifications and other information, samples, models, patterns and the like required by the Subcontract and created or to be created by the Subcontractor pursuant to clause 5 and includes any preliminary design and specifications prepared by or on behalf of the Principal or Downer which are to be reviewed, developed, warranted, amended and/or completed by the Subcontractor pursuant to clause 5;

Design Life means, if the Work includes an item or asset identified in this Subcontract with a design life specified, that period commencing from the Date of Practical Completion;

Direction includes agreement, approval, assessment, authorisation, certificate, decision, demand, determination, explanation, instruction, notice, order, permission, rejection, request or requirement;

Downer's Representative means the person identified as such in Item 1 of the Subcontract Details as may be replaced from time to time by Downer;

Extension of Time means an extension of the Date for Practical Completion;

Final Certificate means the certificate issued under clause 22.4(b);

Final Payment Claim means the Final Payment Claim referred to in clause 22.4(a);

Financing Change Statement has the meaning given to it in the PPSA;

Financing Statement has the meaning given to it in the PPSA;

GST Act means A New Tax System (Goods and Services Tax) Act 1999 (Cth);

DG-LG-TP020



Head Contract means the contract between Downer and the Principal as identified in Item 3, under which Downer has agreed to carry out certain work in relation to the Work;

Head Contract Requirements means:

- (a) any requirements imposed on Downer under or in connection with the Head Contract; and
- (b) Downer's obligations under or in connection with the Head Contract,

which are communicated by Downer to the Subcontractor from time to time (whether before or after the execution of this Subcontract) or which can be reasonably inferred from this Subcontract and the Project Information;

Head Contract Program means a program for the performance of the work the subject of the Head Contract as may be provided by Downer pursuant to clause 20;

Head Contract Works means the works to be performed pursuant to the Head Contract;

Insolvency Event means any one or more of the following circumstances:

- (a) the Subcontractor informs Downer in writing or creditors generally that it is or may become insolvent, unable to pay its debts when due and payable or financially unable to proceed with this Subcontract;
- (b) execution is levied against the Subcontractor by a creditor which is not satisfied, set aside or withdrawn within 14 days after execution is so levied;
- (c) the Subcontractor suspends payment of its debts;
- (d) the Subcontractor, being an individual person or a partnership including an individual person: commits an act of bankruptcy; has a bankruptcy petition presented against him or her or presents his or her own petition; is made bankrupt; makes a proposal for a scheme of arrangement or a composition; has a deed of assignment or deed of arrangement made or accepts a composition; is required to present a debtor's petition; or has a sequestration order made under Part X of the *Bankruptcy Act 1966* (Cth);
- (e) the Subcontractor, being a corporation: enters into a deed of company arrangement, scheme of arrangement or composition with creditors; has (voluntarily or otherwise) a receiver, receiver and manager, controller or administrator, liquidator or provisional liquidator appointed to it; has a winding up order made against it or an application for a winding up order against it made to the court and not stayed within 14 days; resolves by special resolution that it be wound up voluntarily or placed under official management; or has any of its property taken possession of by a mortgagee; or
- (f) something having a substantially similar effect to any of (a) or (e) happens under the law of any jurisdiction in relation to the Subcontractor which Downer reasonably believes may prejudice the Subcontractor's ability to carry out and complete the Work or to pass title in Work to Downer;

Intellectual Property Rights means all present and future rights conferred by statute, common law or equity in or in relation to copyright, trademarks, designs, patents, inventions and other results of intellectual activity in any field whether or not registrable, registered or patentable;

Intended Purpose means the purpose or purposes for which the Work is intended, including any purpose(s) which is described in, or may be reasonably inferred from, this Subcontract or the Project Information and any purpose notified by Downer to the Subcontractor (whether before or after the execution of this Subcontract);

Item means an Item in the Subcontract Details;

Legal Requirements means any Australian legislation, statute, ordinance, rules, regulation, subordinate legislation or by-law, Australian Standards, and includes any licenses, permits and consents necessary for the Subcontractor to carry out and complete the Work, those principles of common law and equity established by decisions of courts and all fees and charges payable in connection with the foregoing;

OHS Rules has the meaning as set out in the State and Territory Specific Schedules;

Moral Right means the rights conferred on authors of works by Part IX of the *Copyright Act 1968* (Cth) and all present and future rights of integrity of authorship, rights of attribution of authorship, rights not to have authorship falsely attributed, rights to alter or delete all or part of the work, rights to use work or an adaption of the work and rights of a similar nature conferred by statute anywhere in the world;

Party means a party to this Subcontract;

PPSA means the Personal Property Securities Act 2009 (Cth);

PPS Register means the Personal Property Securities Register established under the PPSA;

- Practical Completion is the stage in the carrying out and completion of the Work when:
- (a) the Work is complete except for minor Defects:
 - (i) which do not prevent the Work from being reasonably capable of being used for the Intended Purpose;
 - (ii) which Downer determines the Subcontractor has reasonable grounds for not promptly rectifying; and
 - (iii) the rectification of which will not prejudice the convenient use of the Work;
- (b) those tests which are required by this Subcontract to be carried out and passed before the Work reaches Practical Completion have been carried out and passed;
- (c) the Subcontractor has made good the Site and its surrounds and rectified any damage caused by it or those for whom it is responsible to the satisfaction of Downer;

DG-LG-TP020



- Subcontract Long Form
- (d) documents and other information required under this Subcontract which, in Downer's opinion, are essential for the use, operation and maintenance of the Work, have been supplied;
- (e) the Subcontractor has provided to Downer all warranties from Secondary Subcontractors required by the Subcontract; and
- (f) any other matter which this Subcontract states to be a requirement for Practical Completion is satisfied by the Subcontractor to Downer's reasonable satisfaction;

Principal means the person or persons that have engaged Downer under the Head Contract specified in Item 5 of the Subcontract Details and includes the Superintendent;

Probity Event means any event or thing which occurs before or after the date of this Subcontract which:

- (a) has a material adverse effect on, or on the perception of, the character, integrity or honesty of a Relevant Person;
- (b) relates to a Relevant Person and has or may have a material adverse effect on the public interest, or public confidence, in the Work; or
- (c) involves a material failure of a Relevant Person or Secondary Subcontractor to achieve or maintain:
 - (i) reasonable standards of ethical behaviour;
 - the avoidance of conflicts of interest which will have a material adverse effect on the ability of the Relevant Person or Secondary Subcontractor (as applicable) to carry out and observe its obligations in connection with the Work; or
 - (iii) other standards of conduct that would otherwise be expected of a party involved in a project of the same nature and type as the Work;

Project means the Project to which the Head Contract relates;

Project Information means any and all documents, information or materials provided by or on behalf of Downer to the Subcontractor either before or after the execution of this Subcontract;

Project Objectives means the outcomes, objectives, purposes and requirements in relation to the Project communicated by Downer to the Subcontractor or any outcomes, objectives, purposes or requirements that may be reasonably inferred from this Subcontract or the Project Information;

Qualifying Cause of Delay means:

- (a) a breach of this Subcontract by Downer;
- (b) an act or omission of Downer other than an act or omission that is expressly or impliedly permitted under this Subcontract;
- (c) subject to clause 14, the issue of a Variation Notice by Downer in accordance with clause 14.1(a); or
- (d) subject to clause 20.4(d), suspension directed by Downer pursuant to clause 20.4(a),

except to the extent caused or contributed to by any act or omission of the Subcontractor (including any Relevant Person);

Related Company means a 'related body corporate' within the meaning given to that term in section 50 of the *Corporations Act 2001* (Cth);

Relevant Person means any officer, employee, consultant, Secondary Subcontractor or agent of the Subcontractor;

Secondary Subcontractor means any of the Subcontractor's consultants, contractors, suppliers, service providers and any other person engaged by or on behalf of the Subcontractor in connection with the Work;

Security Agreement has the meaning given to it in the PPSA;

Security Interest has the meaning given to it in the PPSA;

Security of Payment Act means the relevant state or territory specific security of payment legislation and regulations applicable to the state or territory where the Work is being performed including as set out in the State and Territory Specific Schedules;

Schedule of Rates means any schedule included in the Subcontract which, in respect of any section or item of work to be carried out, shows the rate or respective rates of payment for the execution of that work and which may also include lump sums, provisional sums, other sums, quantities and prices;

Special Conditions means the special conditions set out in **Part C** of the Subcontract Details;

Standards means any codes, specifications, policies, requirements and standards (as amended or replaced), or any other policy, guideline, procedure, standard or requirement with which the Subcontractor must comply by virtue of a Legal Requirement or as directed by Downer in connection with the Work or which are otherwise applicable to the Work;

Site means the lands and other places to be made available to the Subcontractor for the purposes of this Subcontract, including as described in Item 4, and includes any improvements and structures (including the Works) located on those lands and other places;

State and Territory Specific Schedules means the Schedules to this Subcontract setting out provisions that apply with respect to specific States and Territories;

Subcontract means this agreement between Downer and the Subcontractor constituted by the Subcontract Documents;

Subcontract Details means the document described as such which is attached to these General Conditions of Subcontract;



Subcontract Documents has the meaning identified in the Instrument of Agreement which forms part of this Subcontract;

Subcontract Sum means:

- (a) where there is a lump sum specified in Item 7, that lump sum including any provisional sums but excluding any additions or deductions which may be required to be made under the Subcontract; or
- (b) where there are applicable rates included in this Subcontract, the sum ascertained by multiplying those rates by the quantity of Work properly performed in accordance with this Subcontract; or
- (c) where there are both applicable rates and a lump sum(s), the aggregate of the sums referred to in subclauses (a) and (b),

as adjusted under this Subcontract;

Subcontractor's Design Obligations means each of the obligations of the Subcontractor pursuant to clause 5;

Subcontractor's Representative means the person identified as such in Item 8 of the Subcontract Details or a nominated replacement whose appointment has been approved by Downer;

Superintendent means the person stated in Item 6 and is the Superintendent or the Principal's representative or other person from time to time appointed in writing by the Principal to be the Superintendent or the Principal's Representative under the Head Contract and notified as such in writing to the Subcontractor by Downer and, so far as concerns the functions exercisable under the Head Contract by a Superintendent's representative or the Principal's representative delegate, includes each of those persons;

Tax means any present or future tax, royalty, levy, impost, deduction, assessment, charge, excise, fee, withholding or duty of any nature imposed, assessed, charged, levied or collected by any government agency or other body authorised by Legal Requirements;

Tax Invoice has the meaning given to that expression under the GST Act;

Variation means:

- (a) additional work;
- (b) a change in the character or quality of the Work;
- (c) an increase or decrease in the scope of the Work (including the omission of any part of the Work); or
- (d) a change to the levels, lines, positions or dimensions of any part of the Work;

Variation Notice has the meaning in clause 14.1(a);

Verification Statement has the same meaning as in the PPSA; and

Work means the work described generally in the Subcontract and more particularly identified in Item 9 and all work and activities that are necessary or incidental to that work including, where applicable, the performance of the Subcontractor's Design Obligations.

1.2 Interpretation

- (a) Reference to:
 - (i) one gender includes the others;
 - (ii) the singular includes the plural and the plural includes the singular;
 - (iii) a person includes a body corporate;
 - (iv) a Party includes the Party's executors, administrators, successors and permitted assigns;
 - (v) a thing includes the whole and each part of it separately;
 - (vi) a statute, regulation, code or other law or a provision of any of them includes:
 - (A) any amendment or replacement of it; and
 - (B) another regulation or other statutory instrument made under it, or made under it as amended or replaced; and
 - (vii) dollars means Australian dollars unless otherwise stated.
- (b) Words such as "includes", "including" and "for example" are not words of limitation and are to be construed as though followed by the words "without limitation".
- (c) Where a word or expression is given a particular meaning, other parts of speech and grammatical forms of that word or expression have a corresponding meaning.
- (d) Headings and any table of contents or index are for convenience only and do not form part of this Subcontract or affect its interpretation.
- (e) A provision of this Subcontract must not be construed to the disadvantage of a Party merely because that Party was responsible for the preparation of the Subcontract or the inclusion of the provision in this Subcontract.
- (f) Any terms referred to in this Subcontract that are also defined terms in the Head Contract, have the same meaning in this Subcontract as the meaning given to them in the Head Contract, unless the context otherwise requires.
- (g) Unless this Subcontract expressly provides otherwise, the Subcontractor must perform all of its obligations under this Subcontract at its own cost and expense.



- (h) If an act must be done on a specified day which is not a Business Day, it must be done instead on the next Business Day.
- (i) Unless otherwise provided, prices are in the currency in Item 13 and payments shall be made at the place in Item 14.

1.3 Parties

- (a) If a Party consists of more than 1 person, this Subcontract binds each of them separately and any 2 or more of them jointly.
- (b) An obligation, representation or warranty in favour of more than 1 person is for the benefit of them separately and jointly.

1.4 State and Territory Specific Conditions

(a) To the extent that any Work is performed in New South Wales, the conditions set out in Schedule 5 apply.

1.5 Commonwealth Building Code

If Item 44 states that Schedule 13 applies, the Subcontractor must at all times comply with the provisions set out in Schedule 13 (otherwise, Schedule 13 will not apply to this Subcontract).

2 The Work

2.1 Performance of the Work

- (a) The Subcontractor must carry out and complete the Work in a good, proper and workmanlike manner to the satisfaction of Downer and in accordance with the highest standards of the respective trades using industry best practices and otherwise in accordance with the requirements of this Subcontract.
- (b) Downer may, at any time, and without prejudice to any other right available to Downer, reject any work or materials which do not comply with this Subcontract. The Subcontractor must rectify or replace any rejected work or materials at its own cost in accordance with the Directions of Downer (including any time period directed by Downer), failing which Downer may rectify or replace such work or materials or have such work or materials rectified or replaced by others, the costs of which will be a debt due from the Subcontractor to Downer.

(c) The Subcontractor must comply with:

- (i) all Directions of Downer;
- (ii) Downer's requirements in relation to occupational health, safety and the environment as set out in the Subcontract and as directed by Downer from time to time; and
- (iii) all Legal Requirements applicable to the Subcontract or the Work.

2.2 The Head Contract

- (a) The Subcontractor must do all things necessary to enable performance by Downer of the Head Contract Requirements and so as to ensure that Downer is not, by act or omission, in breach of any Head Contract Requirements.
- (b) The Subcontractor acknowledges and agrees that:
 - (i) it obtains no rights or benefits under the Head Contract; and
 - (ii) the Work to be performed by the Subcontractor for the Subcontract Sum includes anything reasonably required of the Subcontractor by Downer to enable Downer to comply with the Head Contract Requirements.
- (c) Without limiting the Subcontractor's obligations under clauses 2.2(a) and 2.2(b), the Subcontractor must co-operate and co-ordinate performance of the Work with Downer and others carrying out work on or about the Site so as to enable Downer to complete its work under the Head Contract in accordance with the Head Contract Requirements.
- (d) The Subcontractor acknowledges and agrees that the Subcontract Sum includes an allowance to fully compensate the Subcontractor for all obligations, risks and contingencies which are associated with the Subcontractor's compliance with this clause 2.2 and the requirements pursuant to this clause 2.2 shall not constitute a Qualifying Cause of Delay (or an act, default or omission by Downer or Downer's Representative) for the purposes of clause 21.1.

2.3 Quantities

Quantities in a Schedule of Rates are estimated quantities and are not guaranteed by Downer. No limits of accuracy shall apply. The Subcontractor shall have no Claim by reason of the actual quantity of an item or section required to carry out the Work being greater or less than the quantity shown in the Schedule of Rates.

2.4 Legal Requirements

In the performance of the Work, the Subcontractor must:

- (a) comply with its obligations and reasonably foreseeable potential obligations under the OHS Rules and Downer's occupational health and safety policies and procedures as amended from time to time;
- (b) do all that is required to ensure the health and safety of workers and others;
- (c) conform with, and ensure that the Work conforms with, all applicable industry requirements, best practices and Standards;
- (d) ensure all Work, materials, tools, equipment and personal protective equipment is compliant with the relevant Australian Standards;



- Subcontract Long Form
- (e) ensure it does not breach the Fair Work Act 2009 (Cth) or other relevant industrial legislation, awards or enterprise agreements;
- (f) obtain and keep in full force and effect all Approvals necessary for the lawful performance, supply and use of the Work; and
- (g) provide to Downer, upon request, any data and information that is or may be required by Downer, the Principal or any third party to comply with the *National Greenhouse and Energy Reporting Act 2007* (Cth) to the extent that such data and information relates to the Work or this Subcontract.

3 Commencement

3.1 Access to Site

- (a) Subject to clause 3.2, not later than the date stated in Item 10, Downer must give the Subcontractor reasonable access to the Site to enable the Subcontractor to commence carrying out the Work. Any delay in giving the Subcontractor access to the Site is not a breach of Subcontract but may entitle the Subcontractor to claim an Extension of Time under and subject to clause 21.
- (b) Unless Downer's Representative directs otherwise, the Subcontractor must only access the Site during the hours and on the days provided for in accordance with Item 15.
- (c) Notwithstanding this clause 3, if the Subcontractor has not complied with clauses 3.1(e)(i), 8, 9.2 and 9.3, the Subcontractor has no entitlement to (and Downer may refuse to give the Subcontractor) access to the Site until the Subcontractor complies with the requirements of those clauses.
- (d) Except to the extent otherwise expressly stated in this Subcontract, the Subcontractor acknowledges and agrees that it is solely responsible for and has made sufficient provision for any constraints on access to and from the Site and all cranage, scaffolding, haulage and handling that may be required for the performance of the Work.
- (e) The Subcontractor must:
 - (i) provide to Downer, evidence of its safety management system that will be implemented to manage the Work pursuant to this Subcontract;
 - (ii) ensure that its workers (and all of its Secondary Subcontractors' workers) are inducted to the Site prior to the workers commencing work at the Site; and
 - (iii) ensure that its workers (and all of its Secondary Subcontractors' workers) possess the appropriate licence, qualification and competency for the work being undertaken.

3.2 Other works on the Site

- (a) The Subcontractor acknowledges and agrees that it is not entitled to exclusive possession of the Site and that Downer and others will be carrying out work on or about the Site at the same time as the Subcontractor is carrying out the Work.
- (b) The Subcontractor must co-ordinate its Work with the work and activities being carried out by others on the Site and has no entitlement to make any Claim against Downer in any way relating to the carrying out of work by others.
- (c) Downer is not obliged to give the Subcontractor access to the Site under this clause 3 which is greater than Downer's rights under the Head Contract.

4 Subcontractor Warranties and Acknowledgements

4.1 General Warranties

The Subcontractor represents and warrants, in addition to and without limiting any other warranty given by the Subcontractor under this Subcontract:

- that it has thoroughly examined all the Subcontract Documents, the Project Information and all other information or documentation made available to it by Downer before entering into this Subcontract, and obtained all other information necessary to carry out and complete the Work;
- (b) that it has examined all information obtainable by the making of reasonable enquiries in relation to the Work;
- (c) that it is and will at all times be suitably qualified and experienced;
- (d) that it has entered into this Subcontract without relying on any representation by Downer, the Principal or any person purporting to represent Downer or the Principal except to the extent that such representation forms part of and is expressly stated in this Subcontract;
- (e) that it has thoroughly inspected the Site and its adjacent surroundings, including any prior work, existing structures or materials and physical conditions (whether naturally occurring or in consequence of human activity) on, in, over or under the Site and its surroundings;
- (f) that it will carry out and complete the Work so that, when complete, it is free from Defects and is fit for the Intended Purpose and is capable of remaining fit for the Intended Purpose (if maintained in accordance with good industry practice);
- (g) that all materials supplied by it will be suitable for the purpose for which they are used and that, unless otherwise stated in this Subcontract, those materials will be new;
- (h) that the Work will be completed within the time stipulated in this Subcontract;



- that the Work will comply with all the requirements of or to be inferred from, this Subcontract including, the Legal Requirements, Australian Standards and the requirements of all authorities having jurisdiction over the Work and will meet or exceed the Project Objectives;
- (j) that it has determined the nature and extent of the Work and assessed the amount of temporary works, materials, labour, plant and equipment necessary to complete the Work in accordance with its obligations under this Subcontract and made all necessary allowances in the Subcontract Sum, including allowance for the supply of all items not expressly mentioned in this Subcontract but which are necessary for the satisfactory completion of the Work;
- (k) that it has considered its obligations under this Subcontract and that both the Subcontract Sum and Date for Practical Completion are reasonable and each contain all necessary allowances taking into account the risk, responsibilities and costs allocated to the Subcontractor, whether expressly or otherwise;
- (I) that it has made proper allowance for all matters which might impact on its ability to complete the Work or to complete the Work within any particular time, cost or quality constraints subject to the express provisions of this Subcontract;
- (m) that it has obtained, or will be able to obtain, all necessary consents, permits or authorisations (other than those which Downer is required to obtain in accordance with this Subcontract) necessary for it to carry out the Work in accordance with the requirements of this Subcontract;
- (n) that all registrations, permits, licences, qualifications and other requirements of its trade are in full force and effect at all times;
- (o) that it is a GST registered entity;
- (p) that it shall comply with all Legal Requirements applicable to the Work and the performance of the Work; and
- (q) that is will carry out and complete the Work so that, when complete, each asset or item to which a Design Life applies will be free from Defects and fit for the purposes for which it is intended (without any major maintenance or refurbishment works) for its Design Life.

The Subcontractor's warranties remain unaffected notwithstanding:

- (r) that design work (including preliminary design) has been carried out by or on behalf of Downer and included in Downer's Project Objectives;
- (s) that the Subcontractor has entered into an assignment of any prior contract between Downer and a consultant of Downer;
- (t) any receipt or review of, or comment or Direction on, the Design Documents or any aspect of the Work by Downer; or
- (u) any Variation.

4.2 Deeds of Warranty

- (a) Upon written direction from Downer, and as a precondition to Practical Completion, the Subcontractor must provide executed deeds of warranty for the direct benefit of Downer and the Principal:
 - (i) in the form required by any express provision of this Subcontract (including any Schedule to this Subcontract); or
 - (ii) if there is no such express provision, in a form reasonably required by Downer and the Principal.
- (b) The Subcontractor shall, and shall ensure that it is able to, assign to Downer and/ or the Principal (as required by Downer), the benefit of all other warranties obtained by the Subcontractor from any of its subcontractors or suppliers.

4.3 Deliverables

The Subcontractor must (and warrants that it will) ensure that all Deliverables:

- (a) comply in all respects with this Subcontract;
- (b) are fit for the purposes for which they are intended (or any purpose which may be reasonably inferred from the Subcontract or the Project Information);
- (c) comply with all applicable Legal Requirements and Australian Standards;
- (d) do not infringe any Intellectual Property Rights of any person;
- (e) comply in all respects with the Head Contract Requirements; and
- (f) satisfy or exceed the Project Objectives.

4.4 Taxes and Employees Benefits

- (a) The Subcontractor acknowledges that it has sole liability in relation to:
 - (i) wages, salaries, allowances, incentive payments, bonuses, sick leave, long service leave, annual leave, personal leave, termination or redundancy payments and any other employment related liabilities; and
 - (ii) all group tax, payroll tax, PAYE, superannuation, workers compensation and other taxes, levies, deductions, charges, penalties, duties or withholdings,

in respect of the Subcontractor's personnel.

(b) The Subcontractor further acknowledges that neither the Subcontractor nor any of the Subcontractor's personnel have, pursuant to this Subcontract or otherwise, any entitlement from Downer in relation to any form of employment benefit.



The Subcontractor will not communicate or otherwise represent to its personnel that any of the Subcontractor's personnel have any entitlement from Downer in relation to any form of employment related benefit.

- (c) The Subcontractor indemnifies Downer from and against any liability for the Indemnified Taxes, together with any other amount determined by Downer to be reasonably necessary to compensate Downer for an income tax liability, or reduction in income tax losses available to be carried forward or available income tax credits or rebates, to ensure that the after tax position of Downer is the same (or substantially the same) as it would have been had Downer never been liable for any Indemnified Taxes.
- (d) If Downer is, becomes or reasonably forms the view that it may be or become, liable for the payment of any Indemnified Taxes, or Downer is required under a Legal Requirement in respect of Tax to withhold or deduct any amount from any payment due to the Subcontractor (Withholding Amount), Downer may deduct or withhold the amount of its liability or prospective liability for the Indemnified Taxes or Withholding Amount from any amount due by Downer to the Subcontractor, whether under this Subcontract or otherwise.
- (e) In this clause, Indemnified Taxes means any taxes, excluding GST, arising out of or in relation to this Subcontract or the performance of or payment for the Work or any other transaction contemplated by this Subcontract including Pay As You Go, withholding tax, superannuation guarantee charge, fringe benefits tax, workers' compensation insurance premiums and payroll tax, together with all costs, interest or penalties payable by reference to those taxes.

5 Design

Except to the extent that Item 17 excludes the responsibility of the Subcontractor for design and without limiting any other obligation of the Subcontractor under this Subcontract, the Parties acknowledge and agree that:

- the Subcontractor must prepare the Design Documents including by correcting and completing any incorrect or incomplete Design Documents existing as at the date of this Subcontract and otherwise carry out and complete the design of the Work in compliance with this Subcontract;
- (b) the Subcontractor must submit its proposed Design Documents to Downer for review and comment at the times specified in the Subcontract or, if no time is specified, then by the earlier of:
 - (i) the date that enables Downer to comply with, any design review process contained in the Head Contract Requirements; or
 - (ii) 21 days prior to the Subcontractor's proposed commencement of construction (including procurement, manufacture and fabrication of any part of the Work the subject of the Design Documents);
- (c) Downer may (but is not obliged to):
 - (i) review any Design Documents prepared and submitted by the Subcontractor; and
 - (ii) consult with and take into account any views or requirements of the Principal in connection with the Design Documents; and
- (d) within the period prescribed by this Subcontract (or if no period is specified, within 21 days of their receipt), Downer may reject or require amendments to the Design Documents if, in its opinion, the Design Documents do not comply with the requirements of this Subcontract or the Principal;
- (e) if Downer issues any Direction in connection with Design Documents pursuant to clause 5(d), the Subcontractor must submit amended Design Documents to Downer in which case, the process in clauses 5(b), 5(c) and 5(d) shall apply to the amended Design Documents;
- (f) the Subcontractor must not commence construction of the part of the Work to which any Design Documents which it has submitted to Downer applies, unless Downer has had the period prescribed by clause 5(b) to review the Design Documents and has not rejected or required amendments to the Design Documents;
- (g) no preliminary design issued by or on behalf of Downer and no review of, comments upon, rejection of, failure to review or comment upon or reject, any Design Documents prepared by the Subcontractor or any other Direction by Downer shall:
 - (i) cause Downer to assume or owe any duty of care to the Subcontractor in respect of errors or omissions in the Design Documents or the Subcontractor's compliance with this Subcontract;
 - (ii) relieve the Subcontractor from, or alter or affect, the Subcontractor's warranties, liabilities or responsibilities whether under the Subcontract or otherwise according to law; or
 - (iii) prejudice Downer's rights against the Subcontractor whether under the Subcontract or otherwise according to law;
- (h) without limiting any other warranty of the Subcontractor under the Subcontract, the Subcontractor warrants to Downer that the Subcontractor:
 - (i) at all times shall be suitably qualified and experienced, and shall exercise due skill, care and diligence in the carrying out and completion of the Subcontractor's design responsibilities under this Subcontract;
 - (ii) has examined the Subcontract and any preliminary design therein is suitable, appropriate and adequate for the Intended Purpose;
 - (iii) understands that any preliminary design may be incomplete and may require further work before it can be used by a competent contractor to carry out the Work to a stage of Practical Completion and wholly accepts liability



for the adequacy of all Design Documents whether prepared by or on behalf of the Principal, Downer or the Subcontractor;

- (iv) understands that the process referred to in this clause 5 will require the iterative submission and review of Design Documents and the carrying out of design development by the Subcontractor, in respect of which process the Subcontractor has allowed a sufficient amount in the Subcontract Sum and sufficient period of time in calculating the Date for Practical Completion;
- (v) in carrying out the Subcontractor's design obligations, shall ensure that all the Design Documents:
 - (A) have been subjected to coordination, resolution of any error, omission, ambiguity, conflict, lack of clarity or deficiency in the design;
 - (B) do not depart from the layout, purposes, design intent, Standards, style, appearance and dimensions shown in or reasonably inferred from this Subcontract without the express written Approval of Downer:
 - (C) comply with the Legal Requirements and the requirements of this Subcontract; and
 - (D) are consistent with and meet the requirements of the Project Objectives; and
- (i) shall carry out and complete the Work in accordance with the Design Documents prepared by the Subcontractor in accordance with this clause 5 so that the Work, when completed, shall:
 - (i) be fit for the Intended Purpose;
 - (ii) be free from design errors and Defects;
 - (iii) be compliant with the Head Contract Requirements;
 - (iv) meet or exceed the Project Objectives; and
 - (v) be compliant with any further purposes or requirements set out in Schedule 2.

6 Subcontract Documents

6.1 Discrepancies

- (a) The several documents forming this Subcontract shall be taken as mutually explanatory of one another. Should the Subcontractor encounter any discrepancies, contradictions, omissions, ambiguity, errors, faults or inconsistencies in or between the Subcontract Documents the Subcontractor must promptly notify Downer's Representative in writing.
- (b) The Subcontractor must comply with any Direction of Downer's Representative as to the interpretation to be adopted in resolving the discrepancy, contradiction, omission, ambiguity, error, fault or inconsistency and shall have no Claim in connection therewith.
- (c) To the extent that any discrepancies, contradictions, omissions, ambiguity, errors, faults or inconsistencies exist in or between the Subcontract Documents, the Subcontractor shall comply with the highest quality or standard specified or perform the more onerous obligation

6.2 Evidence of Subcontract

The Subcontractor is not entitled to payment under or in connection with this Subcontract and Downer is not obliged to make any payment to the Subcontractor until this Subcontract is executed by the Subcontractor and an original executed copy returned to Downer.

6.3 Supply of documents by the Subcontractor

The Subcontractor must, at least 14 Business Days before and as a precondition to Practical Completion, give Downer all warranties, guarantees, operating manuals, maintenance manuals and "as built" drawings applicable to the Work in accordance with this Subcontract or the Head Contract Requirements.

6.4 Supply of documents by Downer

- (a) Unless this Subcontract expressly provides otherwise, Project Information of any nature provided by or on behalf of Downer to the Subcontractor at any time (other than the Subcontract Documents) is furnished to the Subcontractor solely for its convenience only and are not guaranteed to be complete, accurate, consistent or fit for any purpose (including the Intended Purpose). Downer has no liability whatsoever to the Subcontractor, whether in tort (including negligence), contract, statute or otherwise (except to the extent that such liability cannot be excluded) concerning or in any way connected with any interpretations, deductions, inferences drawn or conclusions made by the Subcontractor in relation to such information or documents or any errors, omissions, representations or misrepresentations contained in the same.
- (b) The Subcontractor warrants that it has:
 - examined carefully and acquired actual knowledge of the content of the Project Information and the Subcontract Documents and any other information made available by or on behalf of Downer to the Subcontractor;
 - (ii) examined all information obtainable by the making of reasonable enquiries in relation to the Work;
 - (iii) satisfied itself that the Subcontract Sum covers the cost of complying with all of its obligations under this Subcontract; and
 - (iv) checked and considered the Design Documents and any document from which the drawings are derived and satisfied itself that they are suitable for the Intended Purpose.



7 Administration and Personnel

7.1 Downer's Representative

Downer's Representative:

- (a) has authority to exercise and discharge any of Downer's powers and duties under this Subcontract unless and until Downer notifies otherwise; and
- (b) may from time to time and at any time by notice in writing to the Subcontractor appoint delegates to exercise any functions of Downer's Representative.

7.2 Compliance with Directions

- (a) The Subcontractor must:
 - (i) comply with any Direction given by Downer or Downer's Representative (or any authorised delegates); and
 - (ii) communicate with Downer's Representative in relation to any matters within Downer's Representative's authority.
- (b) If the Subcontractor is dissatisfied with or disputes any Direction of Downer or Downer's Representative (or any authorised delegates), without limiting any other obligation of the Subcontractor under this Subcontract including with respect to the giving of notices, the Subcontractor shall within five Business Days after the Direction is given, notify Downer in writing identifying the Direction and giving particulars of the Subcontractor's dissatisfaction or dispute. If the Subcontractor fails to do so, the Subcontractor shall have no Claim arising out of or in connection with the Direction.

7.3 Subcontractor's Representative

The Subcontractor must ensure that:

- (a) the Subcontractor's Representative is present on Site whenever Work is being undertaken and in any event during normal working hours;
- (b) the Subcontractor's Representative has the full authority of the Subcontractor to receive instructions from and notices given by Downer's Representative in respect of all matters relating to this Subcontract or the Work;
- (c) the Subcontractor's Representative attends all Site meetings as requested by Downer's Representative;
- (d) subject to events beyond the Subcontractor's control, the key personnel specified in Item 28 are engaged in the execution of the Work and, if it becomes necessary for the Subcontractor to change any of the key personnel, the Subcontractor shall provide to Downer with detailed curricula vitae of at least two persons with training, qualifications, expertise and experience which is at least comparable to that of the personnel proposed to be replaced as proposed replacements for Approval by Downer. The Subcontractor shall not change the key personnel without the written consent of Downer; and
- (e) the Subcontractor's Representative is replaced by an alternative Subcontractor's Representative upon receipt by the Subcontractor of a written notice by Downer's Representative requesting the replacement under clause 15.3 of this Subcontract.

7.4 Subcontractor's Responsibilities

- (a) Downer, Downer's Representative and any delegates do not owe or assume any duty in Subcontract or otherwise:
 - to advise the Subcontractor, to supervise or control the Subcontractor's operations, methods of working or temporary works, to detect, prevent or remedy the Subcontractor's defaults or to ensure the proper performance of any of the Subcontractor's obligations or to exercise any authority or discretion for the benefit of the Subcontractor; and
 - (ii) in relation to any Approval, monitoring, inspection, review or attendance carried out or in relation to any information, permission, comment or recommendation to the Subcontractor.
- (b) Any Approval, monitoring, inspection, review, or any attendance at any test or the giving of any information or permission or the making of any comment or recommendation by Downer or Downer's Representatives shall not constitute waiver of any breach or acceptance of any work, materials or goods, or in any way affect the Subcontractor's obligations and sole responsibility to ensure that the Work is in accordance with this Subcontract.

7.5 Engagement of Illegal Workers prohibited

- (a) The Subcontractor must ensure that each person engaged by the Subcontractor would not, in doing the work for which they are engaged, be an Illegal Worker.
- (b) The Subcontractor must remove, or cause to be removed, any Illegal Worker from any involvement in carrying out the Work.
- (c) For the avoidance of doubt, compliance with the Subcontractor's obligations under this clause will not form the basis of, and will not give rise to any entitlement for the Subcontractor to make, any Claim.
- (d) When requested in writing, the Subcontractor will provide evidence within 14 days that it has taken all reasonable steps to ensure that it has complied with, and is complying with, its obligations under this clause.
- (e) In this clause:
 - (i) **Illegal Worker** means a person who is not a lawful citizen of the country in which the Work is being substantially performed and is not lawfully entitled, under a visa or otherwise, to perform the Work they are



performing, including an Unlawful Non-Citizen who is working without a visa or a Non-Citizen who is performing work in breach of a Visa Work Condition;

- (ii) Non-Citizen has the same meaning as under the *Migration Act* 1958;
- (iii) Unlawful Non-Citizen has the same meaning as under the Migration Act 1958; and
- (iv) **Visa Work Condition** means a condition (as set out in Schedule 8 of the *Migration Regulations* 1994) attached to a visa restricting the work that the Non-Citizen may do in Australia.

8 Security

8.1 Bank Guarantees

- (a) within seven days after the date of this Subcontract, the Subcontractor must provide to Downer two Bank Guarantees each for the amount stated in Item 19 as security for the performance of the Subcontractor's obligations under the Subcontract; and
- (b) the Subcontractor has no entitlement to payment under or in connection with this Subcontract and Downer is not obliged to make any payment to the Subcontractor until the Bank Guarantees are so provided.

8.2 Retention Monies

- (a) If Item 18 provides that retention monies are to be deducted in lieu of the provision of Bank Guarantees then Downer is entitled to retain 10% of each progress payment until the amount retained equals the percentage of the Subcontract Sum set out in Item 20 and such retention monies shall be security for the performance of the Subcontractor's obligations under this Subcontract.
- (b) Downer does not hold retention monies on trust for the Subcontractor and is not required to act in a fiduciary capacity with respect to retention monies held.
- (c) The right to any interest accruing on retention monies vests in Downer.

8.3 Recourse to security

- (a) Downer may have recourse to security and may convert into money any security that does not consist of money where Downer reasonably considers that monies are or will become due and payable from the Subcontractor to Downer, where Downer has a right of set off under this Subcontract or otherwise where Downer has an express right under this Subcontract.
- (b) Where, with the prior written consent of Downer, the Subcontractor:
 - (i) has provided security by way of an approved unconditional undertaking;
 - (ii) the unconditional undertaking contains an expiry date; and
 - (iii) on the date which is three calendar months before the expiry date the Subcontractor is not yet entitled to the release of the security,

the Subcontractor shall provide a replacement undertaking with an identical undertaking except that the date of expiry shall be one year later than the expiry date of the previous undertaking.

(c) The replacement undertaking must be received by Downer not less than two calendar months before the expiry date of the original undertaking. If a replacement undertaking is not received by Downer by the time specified, Downer shall be entitled without notice to the Subcontractor to have recourse to the undertaking and convert it to money and the Subcontractor undertakes that it will not take any steps whether by itself or through any other person, to prevent Downer in any way from so converting the security.

8.4 Reduction of security

Subject to Downer's rights under this Subcontract (including clauses 8.7 and 22.8), provided that the Subcontractor has given Downer an executed Deed of Release in the form set out in Schedule 3, and subject to the exercise of any right of recourse that Downer may have to security, Downer must reduce by the percentage stated in Item 21 of the amount then held by Downer as a Bank Guarantee or as retention monies on the later of 42 days after the Date of Practical Completion for the whole of the Work and the date on which all Defects identified at Practical Completion have been rectified.

8.5 Release of security

Subject to clause 8.7 and Downer's right to exercise a right of recourse that Downer may have to security, Downer will release the balance of the amount then held as a Bank Guarantee or as retention monies under clause 8.2 on the later of 42 days after:

- (a) the date on which the Subcontractor gives Downer an executed Deed of Final Release in the form set out in Schedule 3A;
- (b) the issue of the Final Certificate under clause 22.4; and
- (c) the date on which all Defects identified during the Defects Liability Period have been rectified.

8.6 Parent company guarantee

- (a) In this clause 8.6, the terms "corporation" and "subsidiary" have the meanings defined in the *Corporations Act 2001* (Cth).
- (b) If the Subcontractor is a corporation that is related to or is a subsidiary of another corporation as defined in the *Corporations Act 2001* (Cth), the Subcontractor must, if requested by Downer, give Downer within 14 days of that



request, a deed of guarantee and indemnity in a form acceptable to Downer and duly executed by the Subcontractor and the other corporation for the performance of the obligations and the discharge of the liabilities of the Subcontractor under this Subcontract.

(c) If a deed of guarantee and indemnity is requested by Downer, the provision of such deed by the Subcontractor is a precondition to any entitlement to payment in connection with this Subcontract.

8.7 Effect of claims

- (a) Despite any other provision of this Subcontract, where, at the time for the return of any security to the Subcontractor by Downer, Downer has claims against the Subcontractor that have not been finally resolved, Downer may retain such portion of the security held as Downer considers reasonably appropriate up to the limit of the value of those claims.
- (b) Promptly upon the final and binding resolution of claims referred to in clause 8.7(a) and satisfaction of any entitlement to payment resulting therefrom, and subject to the other terms of this Subcontract, Downer shall return to the Subcontractor the balance of any security then held.

9 Indemnity, Liability and Insurance

9.1 Indemnity

- (a) The Subcontractor is liable for and indemnifies and shall keep indemnified Downer (to the maximum extent permitted by law) against:
 - (i) all cost, loss, damage and expense (including legal fees on an indemnity basis) suffered by Downer and any of its employees or agents;
 - (ii) loss of or damage to Downer's or the Principal's property including existing property in or upon which the Work is being carried out;
 - (iii) claims in respect of personal injury or death or loss of, or damage to, any other property, arising out of or as a consequence of the carrying out of the Work;
 - (iv) any breach by the Subcontractor of the OHS Rules or any penalty or enforceable undertaking imposed for breach of any Legal Requirements; and
 - (v) all liabilities incurred by Downer as a consequence of any liability Downer has or may have to the Principal or another third party in relation to, arising out of or in connection with the Head Contract, the work under the Head Contract or work under a separate subcontract,

arising directly or indirectly as a result of or in connection with the performance of the Subcontractor's obligations under this Subcontract, any breach of this Subcontract by or any negligence of the Subcontractor, its employees, Secondary Subcontractors or agents. However, the Subcontractor's liability to indemnify Downer, its employees or agents is reduced proportionally to the extent that the act or omission of Downer, its employees or agents caused or contributed to the cost, loss, damage, expense or liability.

(b) The Subcontractor's liability under clause 9.1(a) is in addition to its liability under clause 23.3 to the extent that payments made under clause 23.3 are not sufficient to or do not compensate Downer for its actual cost, loss, damage and expense suffered and liabilities incurred under clause 9.1(a).

9.2 Insurance required by Subcontractor

- (a) The Subcontractor must, as a precondition to any entitlement to payment in connection with this Subcontract, provide to Downer certificates of currency in respect of and have in place the insurance policies stated in Item 22, Item 23, Item 24, Item 25 and Item 26 in the amounts and for the periods stated in those items and upon terms and with an insurer approved by Downer.
- (b) The Subcontractor must ensure that its Secondary Subcontractors are similarly insured or covered by the insurance required under this clause 9.2 for the relevant work to be performed by those Secondary Subcontractors.
- (c) Without limiting the rest of this clause 9.2, all policies must require the insurer to notify Downer in writing at the same time it gives a notice of cancellation or any other notice concerning the policy to the Subcontractor.
- (d) If the Subcontractor is required to have in place a public liability insurance policy under clause 9.2(a), such policy must:
 - (i) note the interest of Downer;
 - (ii) provide that Downer is protected by a "Principals" indemnity extension covering Downer's vicarious liability for the acts or omissions of other "Named Insureds" under such policy; and
 - (iii) include a cross liability clause in which the insurer agrees that the policy applies as if a separate policy was issued to Downer and each "Named Insured" (with the exception of limits of liability).
- (e) If the Subcontractor is required to have in place a contract works insurance policy under clause 9.2(a), such policy must:
 - (i) identify Downer as a named insured;
 - (ii) provide that Downer is protected by a "Principals" indemnity extension covering Downer's vicarious liability for the acts or omissions of other "Named Insureds" under such policy; and
 - (iii) include a cross liability clause in which the insurer agrees that the policy applies as if a separate policy was issued to Downer and each "Named Insured" (with the exception of limits of liability).



- (f) Before commencing any work and whenever requested by Downer's Representative, the Subcontractor must promptly provide to Downer's Representative copies of insurance policies required by this clause 9.2 together with certificates of currency.
- (g) If the Subcontractor is required to have in place a professional indemnity policy of insurance pursuant to clause 9.2(a), it must ensure that such policy extends coverage to contractual liabilities assumed by the Subcontractor.

9.3 Insurance of the Subcontractor's Plant and Equipment

- (a) Before commencing work the Subcontractor shall effect and maintain for the duration of the Subcontract an insurance policy covering loss or damage to:
 - (i) any construction plant, for their full replacement value at the time loss or damage occurs; and
 - (ii) valuable documents (including drawings, drafts, reports, calculations and data) relating to or prepared for the purposes of the Work.
- (b) The insurance shall name Downer as an additional insured and shall include a cross liability clause which contains a waiver of subrogation rights against Downer.

9.4 Insurance required by Downer

- (a) Downer will be responsible for causing the insurances set out in Item 27 to be taken out.
- (b) Downer must promptly when requested by the Subcontractor provide to the Subcontractor copies of certificates of currency in respect of insurance policies required by this clause 9.3.
- (c) The Subcontractor must satisfy itself that the insurance to be taken out by Downer under this clause 9.3 is satisfactory for its stated purpose and effect any other or additional insurance which a reasonable and competent subcontractor would effect.
- (d) The Subcontractor must comply with the terms of the insurance policies to be taken out by Downer under this clause 9.3 and is responsible for all excesses payable on any insurance claim under such insurance unless the relevant claim does not relate in any way to the Work.

9.5 Failure to provide evidence of insurance

If the Subcontractor fails to provide to Downer copies of insurance policies together with certificates of currency in accordance with the requirements of this Subcontract, Downer may (without being obliged to do so) effect and maintain such insurance and the cost incurred is a debt due by the Subcontractor to Downer.

9.6 Notice of claims or likely claims

The Subcontractor must as soon as practicable inform Downer's Representative in writing of any occurrence which it ought reasonably expect may give rise to a claim under an insurance policy required by this Subcontract. The Subcontractor must give all information and assistance requested by Downer's Representative in respect of any such claim or possible claim.

9.7 Effect of insurances

The effecting or failure to effect insurance by either the Subcontractor or Downer does not in any way limit or reduce any of the Subcontractor's obligations or liabilities under this Subcontract or at law.

9.8 Limitation of Liability

- (a) Subject to clause 9.8(b), and except to the extent that liability cannot be limited or excluded, the total aggregate liability of the Subcontractor to Downer under this Subcontract is limited to the amount set out in Item 45 of the Subcontract Details.
- (b) Clause 9.8(a) does not apply to:
 - (i) the Subcontractor's obligation and liability to carry out and complete the Work in accordance with the Subcontract;
 - (ii) the Subcontractor's liability as a consequence of, or to rectify, a Defect;
 - (iii) reduce or otherwise affect the Subcontractor's liability to pay liquidated damages under this Subcontract or any other damages for delay;
 - (iv) the Subcontractor's liability to indemnify Downer pursuant to clauses 4.4, 9.1(a)(i), 9.1(a)(ii), 9.1(a)(iii), 9.1(a)(iii), 9.1(a)(iv), 15.2(c) and 16;
 - (v) the Subcontractor's liability in relation to any Claim made by a third party (including the Principal) against Downer or the Subcontractor;
 - (vi) the Subcontractor's liability for breach of clauses 32.3, 34 or 35;
 - (vii) the Subcontractor's liability in respect of fraud, criminal conduct, or any intentional or reckless act or omission of the Subcontractor having had regard to, or with conscious or reckless indifference to, the foreseeable harmful consequences arising from that act or omission;
 - (viii) the Subcontractor abandoning all or a substantial part of its obligations under this Subcontract;
 - (ix) any event or Claim for which the Subcontractor is required to have insurance in accordance with this Subcontract; or



- Subcontract Long Form
- (x) any liability in respect of which the Subcontractor is indemnified under a policy of insurance required to be effected pursuant to the requirements of this Subcontract or in respect of which the Subcontractor would have been indemnified by a policy of insurance required to be effected pursuant to the requirements of this Subcontract if the Subcontractor had:
 - (A) diligently pursued a claim under that policy of insurance;
 - (B) complied with the terms and conditions of that policy of insurance; or
 - (C) complied with its insurance obligations under this Subcontract.

9.9 Consequential Loss

- (a) Subject to clause 9.9(b), neither Party will be liable to the other Party for any Consequential Loss arising out of or in connection with this Subcontract.
- (b) Clause 9.9(a) does not apply to the Subcontractor's liability in respect of:
 - (i) liquidated damages under this Subcontract or any other damages for delay;
 - (ii) the Subcontractor's liability as a consequence of, or to rectify, a Defect;
 - (iii) the Subcontractor's liability to indemnify Downer pursuant to clauses 4.4, 9.1(a)(i), 9.1(a)(ii), 9.1(a)(iii), 9.1(a)(iii), 9.1(a)(iv), 15.2(c) and 16;
 - (iv) the Subcontractor's liability for breach of clauses 32.3, 34 or 35;
 - (v) the Subcontractor's liability in respect of fraud, criminal conduct, or any intentional or reckless act or omission of the Subcontractor having had regard to, or with conscious or reckless indifference to, the foreseeable harmful consequences arising from that act or omission;
 - (vi) the Subcontractor abandoning all or a substantial part of its obligations under this Subcontract;
 - (vii) any event or Claim for which the Subcontractor is required to have insurance in accordance with this Subcontract; or
 - (viii) any liability in respect of which the Subcontractor is indemnified under a policy of insurance required to be effected pursuant to the requirements of this Subcontract or in respect of which the Subcontractor would have been indemnified by a policy of insurance required to be effected pursuant to the requirements of this Subcontract if the Subcontractor had:
 - (A) diligently pursued a claim under that policy of insurance;
 - (B) complied with the terms and conditions of that policy of insurance; or
 - (C) complied with its insurance obligations under this Subcontract.

10 Assignment and Subcontracting

10.1 Assignment

- (a) The Subcontractor must not assign this Subcontract or any right, benefit or interest under this Subcontract without the prior written consent of Downer. If such consent is given, it may be given in whole, in part or subject to whatever conditions Downer requires.
- (b) Downer may assign or novate this Subcontract or any right, benefit or interest under this Subcontract and the Subcontractor must promptly, upon request by Downer, execute a Deed of Novation in the form of Schedule 14 such deed being between Downer, the Subcontractor and Downer's nominee.

10.2 Subcontracting

- (a) The Subcontractor shall not without Downer's prior written Approval (which shall not be unreasonably withheld):
 - (i) subcontract or allow a Secondary Subcontractor to subcontract any Work described in Item 39; or
 - (ii) allow a Secondary Subcontractor to assign a secondary subcontract or any payment or any other right, benefit or interest thereunder.
- (b) Downer may impose any conditions it considers appropriate when giving its Approval under clause 10.2(a).
- (c) The Subcontractor must ensure that Secondary Subcontractors are paid in accordance with the terms of their subcontracts. If a Secondary Subcontractor has become entitled to suspend work under a subcontract (whether under this Subcontract, applicable law (including statute) or otherwise) because of a failure by the Subcontractor to pay moneys to the Secondary Subcontractor, the Subcontractor irrevocably agrees that Downer or the Principal may pay to the Secondary Subcontractor the amount owing to or claimed by the Secondary Subcontractor in connection with that work, and any amount so paid by Downer or the Principal will be a debt due and immediately payable by the Subcontractor to Downer.
- (d) The Subcontractor must ensure that its Secondary Subcontractors comply with all relevant requirements of this Subcontract.
- (e) The Subcontractor is fully responsible for performing the Work and for ensuring compliance with the requirements of this Subcontract and will not be relieved of that responsibility because of any:
 - (i) involvement by Downer in the performance of the Subcontractor's obligations under this Subcontract; or
 - (ii) subcontracting of the whole or part of its obligations under this Subcontract.



- (f) The Subcontractor must give to Downer and the Principal access to (or copies of, upon request) any proposed or executed subcontract (regardless of whether the Subcontractor or the Principal is a party to that subcontract) and all plans, specifications and drawings relating to that subcontract.
- (g) The Subcontractor must:
 - (i) as a condition precedent to the achievement of Practical Completion provide to Downer warranties in favour of Downer and the Principal in a form reasonably required by Downer; and
 - (ii) ensure that Downer and the Principal have the benefit of all warranties given by all Secondary Subcontractors in relation to Work performed by them and any materials provided by them which are used in the provision of or form part of the Work.
- (h) Without limiting the foregoing, the Subcontractor must include in each subcontract with a Secondary Subcontractor:
 - (i) details of the Subcontractor's obligations in connection with the Subcontract which are to be carried out by the Secondary Subcontractor;
 - (ii) consent to a novation to Downer or its nominee at the Direction of Downer and in this regard:
 - (A) the Subcontractor must, at the Direction of Downer, execute such documents as Downer may reasonably require to give effect to such novation and procure that the Secondary Subcontractor do likewise; and
 - (B) Downer may at any time make payments and may deduct, withhold or set-off any amounts to be paid under such novated contracts from amounts otherwise payable to the Subcontractor; and
 - (iii) when possible, a right of termination for convenience.
- (i) Downer may require at any time that it, its nominee or the Principal may conduct probity or criminal investigations to report on the character, integrity or honesty of the Subcontractor, its officers and employees or any other Relevant Person. The Subcontractor must do all things necessary to enable the investigation to be conducted. The Subcontractor must give Downer notice immediately upon becoming aware that a Probity Event has occurred.

10.3 Intention to suspend

- (a) The Subcontractor must promptly give to Downer's Representative a copy of any notice of intention to suspend work that the Subcontractor receives from any of its Secondary Subcontractors under the Security of Payment Act or otherwise if that work forms part of the Work.
- (b) If Downer receives a copy of a notice of intention to suspend work or a Secondary Subcontractor otherwise suspends or threatens to suspend work, Downer may, in its absolute discretion, pay the Secondary Subcontractor the whole or any part of the money that it states that it is owed by the Subcontractor for its work and the amount of the payment made by Downer is a debt due from the Subcontractor to Downer.
- (c) Payment by Downer of any amount under clause 10.3(b) does not relieve the Subcontractor of any of its obligations or liabilities under this Subcontract.
- (d) The Subcontractor indemnifies Downer against any liability, damage, loss, cost or expense (including legal costs on a full indemnity basis) incurred by Downer arising from:
 - (i) a suspension by any of its Secondary Subcontractors under the Security of Payment Act or pursuant to a right under the relevant subcontract, if the relevant work forms part of the Work; and
 - (ii) any failure of the Subcontractor to notify Downer under clause 10.3(a);
- (e) The Subcontractor's liability under clause 10.3 is in addition to the Subcontractor's liability under clause 23.3 to the extent that payment made under that clause is not sufficient to or does not compensate Downer for the damage, loss, cost and expense referred to in clause 10.3.

11 Legal Requirements

11.1 Compliance

- (a) The Subcontractor shall satisfy all Legal Requirements except those in Item 40 or directed by Downer to be satisfied by or on behalf of Downer.
- (b) The Subcontractor, upon finding that a Legal Requirement is at variance with the Subcontract or the Project Objectives, shall promptly give Downer written notice thereof.

11.2 Change in Legal Requirements

- Subject to clause 22.9, if a Legal Requirement:
 - necessitates a change:
 - (i) to the Work; or
 - (ii) in a fee or charge or payment of a new fee or charge;
- (b) comes into effect after the date of execution of the Subcontract but could not reasonably then have been anticipated by a competent and diligent subcontractor performing work similar to that of the Subcontractor; and
- (c) causes the Subcontractor to incur more or less cost than otherwise would have been incurred,

DG-LG-TP020

(a)



the difference shall be assessed by Downer and added or deducted from the Subcontract Sum which shall constitute the Subcontractor's sole remedy in respect of a change in Legal Requirements.

12 Site Conditions

12.1 Notification and risk

- (a) No information and data made available or provided by or on behalf of Downer to the Subcontractor in relation to the Site, or its surrounds, shall form part of the Subcontract. Downer does not warrant, guarantee or make any representation with respect to the completeness, accuracy or adequacy of such information or data. Such information and data is furnished only for the convenience of the Subcontractor and the Subcontractor warrants that it has made and shall rely upon its own enquiries, investigations and assessments. The use of or reliance on any of the information and data is solely at the Subcontractor's own risk. Downer shall not be liable to the Subcontractor whether in contract or otherwise in connection with any fact, matter or thing arising out of or in any way connected with the information or data made available or provided to the Subcontractor as to the Site or subsurface conditions.
- (b) If the Subcontractor becomes aware of any physical condition on, over or under the Site or its adjacent surroundings that may result in the Subcontractor being delayed in completing the Work, the Subcontractor must immediately notify Downer's Representative in writing.
- (c) After it receives a written notification under clause 12.1(b) Downer's Representative may, in its absolute discretion, issue a Direction pertaining to the condition and the Subcontractor must comply with the Direction.
- (d) The Subcontractor wholly assumes the risk associated with, and has no entitlement to make a Claim in relation to, the Site and its surroundings, including:
 - (i) any delay to or prolongation of the performance of the Work; and
 - (ii) any cost, loss or expense caused by or arising out of any conditions on, in, over or under the Site or its surroundings (whether naturally occurring or in consequence of human activity), including any structures, materials, physical conditions or any contamination.
- (e) The Subcontractor warrants that it has taken into account in agreeing the Subcontract Sum and the Date for Practical Completion all risks associated with the Site as set out in this clause 12.1. The Subcontractor has no entitlement to make any Claim against Downer in any way relating to the risks associated with the Site or its surroundings, including the risks identified in this clause 12.1.

12.2 Archaeological or other finds

Any things of value or archaeological or special interest found on or under the Site are, as between the parties, the property of Downer. If such an item is found, the Subcontractor must immediately notify Downer's Representative in writing and must comply with all Directions of Downer's Representative pertaining to the item.

13 Construction

13.1 Subcontractor's obligations

- (a) The Subcontractor must diligently and continuously perform its obligations under this Subcontract and carry out the construction of the Work in accordance with this Subcontract.
- (b) In addition to any other rights of Downer under this Subcontract or at law, Downer may perform or have others perform any obligation of the Subcontractor under this Subcontract which the Subcontractor has failed to perform despite notice in writing from Downer requiring such performance. Downer may recover the costs and expenses of it or others performing the obligation as a debt due and immediately payable to Downer by the Subcontractor.

13.2 Setting out

The Subcontractor must set out the Work in accordance with this Subcontract. The Subcontractor must, if it considers information is necessary to enable it to set out the Work, promptly notify Downer's Representative in writing. If the Subcontractor discovers an error in the position, level, dimensions or alignment in any part of the Work, the Subcontractor must immediately notify Downer's Representative in writing and unless otherwise directed by Downer's Representative, the Subcontractor must rectify the error at its own risk, including cost and time risk and has no Claim in connection therewith.

13.3 Construction method

- (a) The Subcontractor must, within 10 Business Days of the date of this Subcontract, provide a complete and competently prepared construction method statement for the Work including particulars of the mode and place of manufacture, the source of supply, performance capabilities and any other information in respect of any materials, plant or equipment to be supplied by the Subcontractor or used in connection with the Work.
- (b) The Subcontractor must not bring onto the Site any plant or equipment to which it does not have title unless the supply or hire agreement for the plant or equipment contains a provision that:
 - (i) requires the supplier or hirer (as the case may be), to immediately notify Downer of any failure of the Subcontractor to pay any monies in accordance with the supply or hire agreement; and
 - (ii) gives Downer the option (but does not require it) to remedy that default within a period of an additional seven days.
- (c) If requested by Downer, the Subcontractor must provide Downer's Representative with copies of all supply or hire agreements for all plant or equipment that it brings onto the Site.



13.4 Quality

- (a) The Subcontractor warrants to Downer that it will use:
 - (i) materials which are new, suitable, undamaged, free from Defects and which strictly comply with the Australian Standards and the requirements of this Subcontract; and
 - (ii) all due care and skill and proper workmanship expected of an expert contractor carrying out work and services similar to the Work.
- (b) The Subcontractor must do all things necessary to comply with any quality assurance system notified by Downer's Representative or must, if requested by Downer's Representative, implement its own quality assurance system approved by Downer's Representative.
- (c) The Subcontractor acknowledges and agrees that any quality assurance system implemented by it may require performance of the following:
 - (i) inspection and checklisting of work on completion;
 - (ii) identification and rectification of Defects;
 - (iii) provision of records on request;
 - (iv) reporting of non-conformance;
 - (v) provision of samples and prototypes; and
 - (vi) provision of access to the Subcontractor's systems and records by Downer's Representative and any persons authorised by Downer's Representative for the purpose of inspection and audit.

13.5 Protection of work and materials

- (a) The Subcontractor is, until Practical Completion, responsible for and must protect from damage or loss the Work and other things and materials brought on to the Site by or for the Subcontractor. If any damage or loss occurs, the Subcontractor must at its own cost promptly make good the damage or loss and fully and sufficiently reinstate and replace the things, damages or loss.
- (b) If the Subcontractor fails to make good the damage or loss after Downer's Representative has given the Subcontractor notice that it intends to have that work carried out by others if the Subcontractor does not carry out the work within the period specified by Downer's Representative, on expiry of that period Downer's Representative may have that work carried out by others and any cost incurred is a debt due and immediately payable from the Subcontractor to Downer.
- (c) Despite any other provision of this Subcontract, the Subcontractor accepts as full payment for any reinstatement or replacement of the Work that is the subject of an insurance claim, the amount of insurance proceeds recovered by Downer or the Subcontractor in respect of that reinstatement or replacement.
- (d) In respect of any materials supplied by Downer to the Subcontractor for incorporation in the Work, the Subcontractor shall examine and satisfy itself and be deemed to have examined and satisfied itself that each item is free from Defects and fit for the Intended Purpose, at the time that each is made available to the Subcontractor.
- (e) Risk in any Downer-issued items shall pass to the Subcontractor upon them being made available to the Subcontractor. The Subcontractor shall keep safe and maintain all such items in good order and condition. All Downer-issued items shall remain the property of Downer and any surplus shall be returned to Downer, disposed of, or otherwise dealt with as directed by Downer. Waste of Downer-issued items as a result of bad workmanship, negligence or any other default of the Subcontractor shall be made good at the Subcontractor's cost.

13.6 Urgent protection

If urgent action is necessary to protect the Work, other property or people and the Subcontractor fails to take the action, Downer may take necessary action to protect the Work. If the action taken by Downer was, in the opinion of Downer's Representative, action which the Subcontractor should have taken at the Subcontractor's cost, the cost incurred by Downer is a debt due and immediately payable from the Subcontractor to Downer.

13.7 Testing

- (a) At any time before the issue of the Final Certificate, Downer's Representative may direct that any part of the work or materials comprising the Work be tested. If the Direction requires the Subcontractor to perform the testing, Downer's Representative may observe and must be promptly provided with the results of any test performed.
- (b) The reasonable and actual costs of and incidental to testing are to be added to the Subcontract Sum unless such testing:
 - (i) reveals work or materials not in accordance with this Subcontract;
 - (ii) is consequent upon a failure of the Subcontractor to comply with this Subcontract; or
 - (iii) was required to be performed by the Subcontractor or has otherwise been included in the Subcontract Sum as part of the work to be undertaken by the Subcontractor under any other provision of this Subcontract.
- (c) Costs in respect of this clause 13.7 that are not to be borne by Downer shall be borne by the Subcontractor and, in the case of costs incurred by Downer of or incidental to such testing, certified by Downer as moneys due and immediately payable from the Subcontractor to Downer.



13.8 Defects

- (a) If Downer discovers any Defect, Downer may direct the Subcontractor to do any one or more of the following (including times for commencement and completion):
 - (i) remove material from the Site;
 - (ii) demolish the Work; or
 - (iii) reconstruct, replace or correct the Work.
- (b) The Subcontractor must comply with the Direction at its own cost. If the Subcontractor fails to comply with Downer's Direction, Downer may perform the relevant work or arrange for a third party to perform the relevant work, the cost of which will be a debt due and immediately payable from the Subcontractor to Downer (or the reasonably estimated cost of such work where the cost has not been incurred).
- (c) Instead of a Direction under clause 13.8(a), Downer or the Principal may elect to accept the Defect and reduce the Subcontract Sum by an amount equal to the decrease in value to the Work (including increased future operation and maintenance costs, loss of income, loss of value or reduction in asset life) as a result of the Defect.
- (d) Downer may give a Direction under this clause at any time prior to the expiry of the Defects Liability Period.

14 Variations

14.1 Variations

- (a) Downer's Representative may direct the performance of a Variation by notice in writing to the Subcontractor, such notice being expressly identified as a 'variation notice' (Variation Notice). The Subcontractor must execute any Variation directed by Downer's Representative in a Variation Notice.
- (b) If:
 - (i) Downer's Representative issues a Direction which is not a Variation Notice, but requires or may cause the Subcontractor to carry out work that is a Variation; or
 - (ii) the Subcontractor is otherwise required to carry out any Work that constitutes a Variation (without having received a Variation Notice),

the Subcontractor must, before it commences carrying out such Work and in any event no later than five days after receipt of the relevant Direction or upon becoming aware of the requirement to carry out Work that constitutes a Variation (as applicable), provide to Downer a written claim identifying the Variation and setting out an estimate of the cost, delay and any other impact of the Variation, including any proposed adjustment to the Subcontract Sum.

- (c) To the extent permitted by law, the Subcontractor will have no Claim in respect of any Work that constitutes a Variation unless:
 - (i) it has received a Variation Notice from Downer which complies with clause 14.1(a) in respect of that Work; and
 - (ii) to the extent clause 14.1(b) applies, the Subcontractor has complied strictly with clause 14.1(b) in respect of that Work.
- (d) A Direction under clause 14.1(a) may involve the omission of any part or parts of the Work and the Subcontractor acknowledges and agrees that Downer may itself, or engage others to, carry out that part of parts so omitted at any time. The Subcontractor further acknowledges that any one or more omissions will not constitute a basis to allege that Downer has repudiated the Subcontract notwithstanding the extent or timing of the omission.
- (e) Where Downer omits Work, the Subcontractor will not be entitled to any compensation in respect of that Work (including for loss of profit or any costs incurred by reason of the omission). Downer has right to deduct the amount for profit and overhead by applying % as per item 35 to the value of omitted Work.

14.2 Quotation for Variations

- (a) If Downer's Representative requests the Subcontractor to provide a quotation for a proposed Variation the Subcontractor must provide a detailed quotation for the work, supported by measurements and other evidence of cost, accompanied by details of any Extension of Time the Subcontractor seeks, within five days of the request by Downer's Representative.
- (b) In response to any quotation provided by the Subcontractor to Downer's Representative under clause 14.2(a) Downer's Representative may:
 - (i) require the Subcontractor to execute the Variation as quoted under the terms and condition of the Subcontract;
 - (ii) decline to proceed with the Variation; or
 - (iii) reject the quotation and require the Subcontractor to carry out the Variation, in which case the Variation must be valued by Downer's Representative in accordance with clause 14.3 and any Extension of Time must be assessed by Downer's Representative in accordance with clause 21.

14.3 Valuation of Variations

- (a) Subject to this clause 14.3 and the terms of this Subcontract, Downer shall ensure that the value of any Variation is added to or deducted from the Subcontract Sum (as applicable). If the Parties do not agree the value of a Variation, Downer's Representative will determine a reasonable value for the Variation and in doing so may have regard to:
 - (i) applicable rates and prices included in this Subcontract; and



- Subcontract Long Form
- (ii) any increase or decrease in the costs that have been or will be incurred by the Subcontractor as a direct result of the Variation.
- (b) Despite clause 14.3(a), if a Direction to carry out a Variation under this Subcontract is the result of a Direction to Downer under the Head Contract, without limiting any other provision of the Subcontract and to the extent permitted by law, the Subcontractor is not entitled to be paid for that Variation any amount which is greater than the amount to which Downer is entitled to be paid for that Variation under the Head Contract.
- (c) Where a Variation relates to a variation under the Head Contract and the Variation has been valued under the Head Contract otherwise than by agreement between Downer and the Principal, the Subcontractor shall not be allowed any greater value for the Variation than the relevant value which has been determined or assessed under the Head Contract.
- (d) The Subcontractor shall not be entitled to any payment for a Variation unless it has performed the work the subject of the Variation and until a specific price for the Variation has been finally determined by agreement in writing between the Parties, pursuant to the terms of this Subcontract or pursuant to a dispute resolution process prescribed by this Subcontract.

15 Conduct On and in the Vicinity of the Site

15.1 Protection of people and property

- (a) In the performance of the Work the Subcontractor must take all measures and provide all things reasonably necessary to protect the environment, people and property.
- (b) Without limiting the generality of the foregoing, the Subcontractor must:
 - (i) take all necessary action, to the satisfaction of Downer, to minimise vibration, shock and noise arising from construction activities for the Work;
 - (ii) ensure that all construction facilities erected on the Site by the Subcontractor are designed and operated to minimise any nuisance arising from dust caused by construction activities;
 - (iii) take all proper precautions to minimise the impact of discharge of water into waterways on and in the vicinity of the Work and the Site;
 - (iv) take all precautions necessary to prevent the discharge into waterways of any oils or similar materials or of any foaming or non-biodegradable detergents and the Subcontractor acknowledges and agrees that all plant and equipment maintenance shall be carried out on a paved area, the drainage from which shall be provided with approved soil separation traps before discharge into any waterway. The Subcontractor shall be solely responsible for regular removal of deleterious matter from such traps and its disposal by approved methods; and
 - (v) ensure that the whole of the Subcontract Works and all operations related to them are carried out in a manner which will minimise inconvenience and nuisance to occupants of adjacent buildings, the public, Downer and to other subcontractors and workers.

15.2 Access to other Properties

- (a) The Subcontractor acknowledges that it has been made aware of, and will comply with, any agreement made between the Principal and/or Downer and the owners of the land adjacent to and proximate to the Site and all matters included therein (including but not limited to restrictions on hours of work).
- (b) Except for permissions and arrangements that Downer informs the Subcontractor have already been obtained or made, the Subcontractor must, at its own cost, and expense:
 - (i) obtain any necessary or appropriate permission to work upon, up to, in, over, under or make use of any adjoining or neighbouring site or property; and
 - (ii) make all arrangements for any access to work upon, up to, in, over, under or to make use of any adjoining or neighbouring site or property,

which the nature of the Work requires or which it may otherwise require for any purpose of the Subcontract or the Work.

(c) The Subcontractor accepts liability for and agrees to indemnify and keep indemnified and hold harmless Downer and the Principal in respect of any cost, expense, loss or damage arising out of or in connection with the Work being carried out upon, up to, in, over, under or by making use of any adjoining, adjacent or surrounding sites or properties or contrary to the terms of any agreement referred to in clause 15.2(a).

15.3 Removal of persons from Site

Downer's Representative may direct the Subcontractor to remove from the Site any person whom Downer's Representative considers to be disruptive, incompetent, negligent or guilty of misconduct. The written Approval of Downer's Representative must be obtained by the Subcontractor before the Subcontractor subsequently employs the person on Site or has the person involved in activities in any way connected with the Work.



16 Intellectual Property Rights

16.1 No Infringement of Intellectual Property Rights

The Subcontractor warrants that it has all Intellectual Property Rights necessary to carry out and complete the Work in accordance with this Subcontract and indemnifies Downer against any Claim as a consequence of any claim by a third party that it has a right to any Intellectual Property Right in the Work or any Deliverables.

16.2 Intellectual Property Rights granted to Downer

- (a) Any Intellectual Property Rights that are created in the course of the performance of the Work, including all Deliverables and any Design Documents created by or on behalf of the Subcontractor, shall vest in Downer immediately upon creation.
- (b) In relation to any Intellectual Property Rights held by the Subcontractor that do not vest in Downer pursuant to clause 16.2(a) (but which relate in any way to the Work or the Deliverables), the Subcontractor grants to Downer a perpetual, irrevocable, transferable, worldwide, royalty-free licence of all such Intellectual Property Rights for Downer to use, consume and otherwise enjoy the full benefit of the Work and the Deliverables, comply with all of its obligations under the Head Contract (including the right to sub-licence and to transfer relevant Intellectual Property Rights to the Principal or other third parties) and achieve the Project Objectives.
- (c) Downer grants to the Subcontractor a royalty-free, non-transferable licence to use the Intellectual Property Rights that vest in Downer pursuant to clause 16.2(a) solely for the purpose of allowing the Subcontractor to comply with its obligations under this Subcontract.

16.3 Moral Rights

The Subcontractor must ensure that, and warrants that, it has obtained from all authors and holders of the Moral Rights in the Deliverables and the Work, consent to the following specific acts or omissions by Downer and the Principal and their successors, assignees and sub-licensees:

- (a) reproducing, publishing, adapting or communicating the Deliverables and the Subcontractor's other documents to the public without attributing their authorship or otherwise identifying the author of the relevant Deliverables and other documents; and
- (b) subjecting the Deliverables and the Subcontractor's other documents to derogatory treatment, including material distortion, mutilation or material alteration or the doing of anything else to the Deliverables and Subcontractor's other documents, including adapting, reproducing, publishing, communicating to the public, adding, deleting, editing or modifying the text, format or structure of the Deliverables and the Subcontractor's other documents, in such a way as may prejudice the honour and reputation of the author.

17 Reports and Approvals

17.1 Reports and Records

Downer's Representative may at any time direct the Subcontractor to submit a report or provide records to Downer's Representative containing such information as is reasonably requested by Downer's Representative for the purpose of monitoring the Subcontractor's compliance with this Subcontract or auditing the state of the Subcontractor's finances but nothing in this clause shall oblige the Subcontractor to provide any document that is the subject of legal professional privilege. The Direction may specify that compliance with the Direction is a precondition to the entitlement of the Subcontractor to issue a progress claim or further progress claim or further progress claim, then it is hereby agreed to constitute such a precondition.

17.2 Approvals

Except for those Approvals listed in Item 29, the Subcontractor must obtain (and pay all charges and costs associated with those Approvals) and comply with all Approvals required for the performance and completion of the Work, and must ensure that all such Approvals remain in full force and effect at all times. The Subcontractor must promptly provide to Downer's Representative copies of all Approvals obtained by the Subcontractor.

18 Cleaning Up

- (a) The Subcontractor must keep the Site and the Work clean and tidy and must regularly remove rubbish from the Site and at the times directed to do so by Downer's Representative.
- (b) Prior to Practical Completion (and as a precondition to Practical Completion), the Subcontractor must remove any temporary works, plant and equipment unless directed otherwise by Downer's Representative.

19 Defects Liability Period

19.1 Rectification

- (a) Without limiting any other obligations of the Subcontractor under this Subcontract or at law, the Subcontractor must promptly rectify any Defect that is found to exist in the Work at the Date of Practical Completion or at any time during the Defects Liability Period.
- (b) The Subcontractor must, when directed by Downer's Representative to do so, rectify any Defect in the Work at its sole risk and expense. The Direction may, without limitation, require the Subcontractor to remove material from the Site, demolish work, reconstruct, replace or correct the material or Work. Downer's Representative may direct the times



within which the Subcontractor must commence and complete rectification of a Defect. The Subcontractor must notify Downer's Representative when rectification of a Defect has been completed.

19.2 Further Defects Liability Period

Where a Direction is given under clause 19.1, a separate Defects Liability Period in respect of the rectified Work will commence on the date that the rectification is completed.

19.3 Defects Rectified by Others

If the Subcontractor fails to rectify any Defect in accordance with clause 19.1 or in accordance with a Direction given under clause 19.1, Downer may rectify the Defect itself or have the Defect rectified by others (including the Principal), and Downer may:

- (a) certify and recover all actual or anticipated costs of so doing as a debt due and immediately payable from the Subcontractor to Downer provided that Downer accounts to the Subcontractor for any amount by which the anticipated costs exceed the actual costs; or
- (b) accept the Defect and recover its assessment of any consequent reduction in value of the Work or claim upon Downer by the Principal as a debt due from the Subcontractor to Downer.

20 Time

20.1 Practical Completion

The Subcontractor must carry out the Work with due expedition and without delay and so as to achieve Practical Completion by the Date for Practical Completion.

20.2 Subcontractor's program

- (a) The Subcontractor must supply to Downer's Representative at least seven days before the commencement of any work, a program for the performance of the Work compliant with clause 20.3 and Downer may, from time to time, direct the Subcontractor to give to Downer an updated program within the time and in the form directed by Downer, which program must:
 - (i) conform with the programming requirements of Downer including those in clause 20.3;
 - (ii) be consistent with any Head Contract Program, as provided from time to time by Downer to the Subcontractor; and
 - (iii) be approved by Downer.
- (b) The Subcontractor shall not, without reasonable cause, depart from a program approved by Downer.
- (c) An approved program may be used by Downer in its absolute discretion to monitor the progress of the Work by the Subcontractor and assess claims for Extensions of Time but no program, approved program or Head Contract Program shall form part of the Subcontract and any departure from or amendment of a program, approved program or Head Contract Program shall not entitle the Subcontractor to any Claim, including a Claim for an Extension of Time. The Subcontractor's entitlement to an Extension of Time shall only arise in accordance with clause 21.
- (d) Without limiting any other obligation of the Subcontractor under this Subcontract, the Subcontractor must:
 - (i) not, without reasonable cause, depart from the current Head Contract Program insofar as it identifies or is dependent upon the Work; and
 - (ii) immediately notify Downer in writing if its performance of the Work will depart from that identified in the Head Contract Program or delay the performance of activities identified in the Head Contract Program current at the time of departure, which are dependent upon performance of the Work.
- (e) The Subcontractor shall not be entitled to any Claim arising from its obligations pursuant to this clause 20.2

20.3 Contents of the program

Each program provided by the Subcontractor under clause 20.2 must include:

- (a) the date of commencement and the Date for Practical Completion;
- (b) the sequence and timing of each component of the Work, including a critical path network analysis in the form of a time scaled bar chart;
- (c) the dates when the Subcontractor is required to provide any information or materials in connection with the Work; and
- (d) all other information reasonably required by Downer's Representative,
- and must be provided to Downer in its native format with all logic links exposed and capable of being interrogated.

20.4 Suspension

- (a) Downer's Representative may at any time and for any reason suspend the whole or any part of the Work by written notice to the Subcontractor. If Downer's Representative does so, the Subcontractor must not recommence work on the whole or on the relevant part of the Work until Downer's Representative directs the Subcontractor to do so in writing.
- (b) If Downer Directs the Subcontractor to suspend the Work or any part of the Work, then at the time of issuing such Direction or at any subsequent time, Downer may also instruct the Subcontractor to:
 - (i) reduce the resources, including staff, allocated to the performance of the Work; and/or



- (ii) demobilise all resources from the performance of the Work,
- within the time nominated by Downer (provided that such time is not less than two days after the Direction is issued).
- (c) The Subcontractor must resume the performance of the suspended Work as soon as practicable after being Directed by Downer and in any event not later than five days after receiving a written instruction to do so from Downer.
- (d) The Subcontract Sum will be adjusted by Downer to include the reasonable costs actually incurred by the Subcontractor directly as a result of the suspension, except where the suspension is occasioned by an act or omission of the Subcontractor, in which case the Subcontractor will not be entitled to any adjustment of the Subcontract Sum or any Extension of Time to the Date for Practical Completion in connection with the suspension. The adjustment of the Subcontractor is entitled pursuant to this clause 20.4(d) and any Extension of Time to which the Subcontractor is entitled pursuant to clause 21 shall be the Subcontractor's sole remedy in connection with any suspension of the Work pursuant to this clause 20.4.

20.5 Milestones

If any milestone and corresponding milestone date are referred to in this Subcontract or any program approved by Downer pursuant to clause 20.2, the Subcontractor must bring that portion of the Work which comprises the milestone to the stage of completion by the relevant milestone date specified.

20.6 Corrective action

- (a) Without limiting any other right of Downer or obligation of the Subcontractor under this Subcontract, the Subcontractor agrees that:
 - (i) if at any time the progress of Work has fallen behind that shown in a program approved by Downer or is otherwise not in accordance with this Subcontract, the Subcontractor shall at its own cost take the necessary corrective action to ensure that progress is maintained in accordance with this Subcontract. Subject to permissible working hours, such corrective action may include the working of overtime and additional shifts, the application of more resources to carry out Work and the adjustment and rescheduling of activities. Downer may from time to time direct the Subcontractor to provide details of the corrective action it plans to take under this clause 20.6 and the Subcontractor must provide such details in writing within five Business Days of the Direction; and
 - (ii) if the Subcontractor fails to take corrective action in accordance with clause 20.6, Downer may direct the Subcontractor as to the corrective action it is to take and the Subcontractor shall comply with such Direction at its own cost and risk.
- (b) The Subcontractor shall have no Claim in connection with, or as a consequence of, complying with its obligations under this clause 20.6.

20.7 Proposal to accelerate

Downer may at any time prior to the Date for Practical Completion by written notice request the Subcontractor to provide a proposal to accelerate the performance of the Work so as to expedite the achievement of Practical Completion. Within three days of such a request, the Subcontractor shall provide a written proposal to Downer which contains the following details:

- (a) the measures which the Subcontractor considers necessary to accelerate the performance of the Work so as to expedite the achievement of Practical Completion; and
- (b) the additional payment required by the Subcontractor to achieve the acceleration of the performance of the Work so as to expedite the achievement of Practical Completion.

Notwithstanding that, if Downer finds the Subcontractor's acceleration proposal to be unacceptable, whether in terms of the measures proposed or the additional payment required or otherwise, Downer may nevertheless give the Subcontractor a Direction to accelerate which expressly states that it is an acceleration Direction given under this clause and which contains the following:

- (i) the general measures which Downer requires the Subcontractor to take to accelerate the performance of the Work so as to expedite the achievement of Practical Completion;
- (ii) the time by which the Subcontractor shall commence to implement the acceleration Direction; and
- (iii) the reasonable revised (earlier) Date for Practical Completion.
- (c) The Subcontractor shall comply with the acceleration Direction and Downer shall assess and certify the additional costs payable to the Subcontractor reasonably and necessarily arising from compliance with the acceleration Direction as an amount payable by Downer to the Subcontractor, which amount shall constitute the Subcontractor's sole entitlement to payment in connection with the acceleration Direction and which amount shall not be payable unless the acceleration Direction is implemented by the Subcontractor to the reasonable satisfaction of Downer.
- (d) For the avoidance of doubt, a Direction by Downer to the Subcontractor to accelerate or take any corrective action or other measures to catch up on progressing the Work as a result of any delay in the Work for which the Subcontractor is not entitled to an Extension of Time for any reason, does not constitute an acceleration Direction pursuant to this clause 20.7.



21 Delay

21.1 Notice

- (a) If the Subcontractor:
 - (i) is or will be delayed in reaching Practical Completion by the Date for Practical Completion by a Qualifying Cause of Delay:
 - (ii) takes all reasonable steps to prevent, overcome and mitigate the effects of the delay (including by reconfiguring the critical path of the Work to accommodate, minimise or overcome the delay);
 - (iii) gives Downer within five days of the date of the earliest to occur of:
 - (A) the commencement of the cause of the delay;
 - (B) the Subcontractor becoming aware that the Subcontractor is or will be delayed; or
 - (C) the date that the Subcontractor should reasonably have been aware that the Subcontractor is or will be delayed,

(Notice Trigger Date)

written notice that it intends to make a claim for an Extension of Time to the Date for Practical Completion pursuant to clause 21.1(a)(iv), setting out a brief description of the facts upon which the claim may be based and the current estimate of the delay or potential delay based on the information reasonably available to the Subcontractor at that stage;

- (iv) gives Downer within 10 days of the Notice Trigger Date, a detailed written claim for an Extension of Time which:
 - (A) evidences the cause, effect and extent of the delay and the number of days extension claimed together with the basis of such claim;
 - (B) identifies with a program analysis the critical activities delayed on the Subcontractor's program;
 - (C) demonstrates the Subcontractor's compliance with clause 21.1(a)(ii); and
 - (D) is warranted as being true and correct to the best of the Subcontractor's knowledge and belief; and
- (v) in the case of an ongoing delay that continues beyond the date on which the claim is submitted pursuant to clause 21.1(a)(iv), an updated written claim for an Extension of Time every five days after the submission of the claim pursuant to clause 21.1(a)(iv) until the delay has ceased,

then, subject to clauses 21.1(b) and 21.2, the Subcontractor is entitled to such Extension of Time to the Date for Practical Completion as Downer (acting reasonably) determines but only to the extent that:

- (vi) the Qualifying Cause of Delay has caused delays to the critical path of the Work; and
- (vii) the Qualifying Cause of Delay is not caused or contributed to by, or connected with, any act or omission of the Subcontractor, a Secondary Subcontractor or their respective agents, personnel and representatives.
- (b) If more than one event causes a delay and the cause of at least one of those events is not a Qualifying Cause of Delay, then to the extent that the events of delay or the effects of those events of delay are concurrent, the Subcontractor is not entitled to an Extension of Time.
- (c) If at the time the Subcontractor is required to give a notice under clause 21.1(a), the duration or impact of the delay is not ascertainable then the Subcontractor must in the notice state what details are not yet known and must give a further notice or notices advising those details promptly once they are known.

21.2 Failure to give notice

Strict compliance by the Subcontractor with clause 21.1 is a pre-condition to any entitlement to an Extension of Time. The Subcontractor is not entitled to make or maintain any Claim for an Extension of Time in connection with a delay (and irrevocably waives any entitlement to make or maintain any such Claim) if the Subcontractor has not complied strictly with clause 21.1 in connection with the delay.

21.3 Response by Downer's Representative

- (a) If the Subcontractor is entitled to an Extension of Time pursuant to clause 21.1, Downer must, within 28 days (if the Qualifying Cause of Delay is not the subject, in whole or in part, of an extension of time claim by Downer under the Head Contract) or 45 days (if the Qualifying Cause of Delay is the subject, in whole or in part, of an extension of time claim by Downer under the Head Contract) after receiving a claim by the Subcontractor made in accordance with clause 21.1 (or where the delay is ongoing, after the Subcontractor has issued the final updated claim pursuant to clause 21.1(a)(v)), issue in writing to the Subcontractor its assessment of any Extension of Time to which Downer considers the Subcontractor is entitled.
- (b) A delay by Downer or the failure of Downer to grant a reasonable Extension of Time or to grant an Extension of Time within the relevant period referred to in this clause 21.3 shall not cause the Date for Practical Completion to be set at large but nothing in this clause shall prejudice any right of the Subcontractor to damages.

21.4 Extension of Time claim and accelerations

(a) If the Subcontractor gives a claim under clause 21.1, irrespective of whether the Subcontractor is entitled to any Extension of Time, Downer may direct the Subcontractor to accelerate the Work by taking those measures which are necessary to overcome or minimise the extent and effects of some or all of the delay, including if required, to reach



Practical Completion by the Date for Practical Completion. If Downer gives an acceleration Direction that only applies to part of the delay for which the Subcontractor is entitled to an Extension of Time, the Subcontractor's entitlement to any Extension of Time shall be reduced to the like extent.

(b) If Downer gives the Subcontractor an acceleration Direction the Subcontractor shall accelerate the Work to overcome or minimise the extent and effect of the delay, including if required, to reach Practical Completion by the Date for Practical Completion. If the Subcontractor would, but for the Direction, have been entitled to an Extension of Time, the Subcontractor shall be entitled to be paid the extra costs reasonably and necessarily incurred by it and directly attributable to accelerating the Work as assessed and certified by Downer's Representative.

21.5 Downer may extend

At any time, Downer may, under this clause, grant an Extension of Time to the Subcontractor for the benefit of Downer regardless of whether or not the Subcontractor has made a claim for Extension of Time. Downer is not obliged to exercise the right under this clause 21.5 for the benefit of the Subcontractor and the exercise of the right under this clause 21.5 shall not entitle the Subcontractor to make any Claim.

21.6 Delay Costs

- (a) For every day the subject of an Extension of Time for a Compensable Cause and for which the Subcontractor gives Downer a claim for Delay Costs strictly in accordance with clause 29, the Subcontractor shall be entitled to recover such additional costs in respect of the Subcontractor's personnel, Secondary Subcontractors and construction plant directly engaged either on-Site or off-Site in the performance of the Work (excluding profit, mark-up or off-Site overheads) which are reasonably, necessarily and actually incurred directly as a result of the delay and which are substantiated to Downer in writing, provided that the Subcontractor will not be entitled to any amount exceeding the amount stated in Item 31.
- (b) The amount of Delay Costs payable pursuant to this clause is the agreed damages which will be payable by Downer in these circumstances and will be a limit upon Downer's liability to the Subcontractor for any delay, disruption or prolongation which arises out of or in connection with this Subcontract, howsoever caused, except in respect of a suspension Direction issued by Downer pursuant to clause 20.4 or arising pursuant to a right under clause 27.9(a), in which case the Subcontractor's sole entitlement shall be its entitlement pursuant to clause 20.4(d) or 27.9(b), as the case may be.
- (c) The Subcontractor must take all reasonable steps to reduce, and where possible eliminate, the costs referred to in this clause 21.6
- (d) Compliance by the Subcontractor with this clause 21.6 and clause 29 is a pre-condition to the Subcontractor's entitlement to the payment of any amount in connection with any delay. If the Subcontractor fails to comply with this clause 21.6 in respect of any delay, the Subcontractor shall have no Claim in connection with the delay.

22 Payment

22.1 Progress Claims

- (a) The Subcontractor must submit progress claims to Downer at the times stated in Item 32, which date shall be a 'reference date' for the purposes of the Security of Payment Act.
- (b) The Subcontractor shall have no entitlement to, and will not, submit a payment claim, except in accordance with this clause 22 and at the times set out in Item 32.
- (c) An early progress claim will be deemed to have been made on the date for making that claim stated in Item 32.
- (d) A progress claim for payment must, as a condition precedent to its validity:
 - (i) identify all Work carried out by the Subcontractor in the performance of the Subcontract up to the date of the progress claim, with all corresponding amounts then claimed in respect of the Subcontract Sum;
 - (ii) include the Subcontractor's valuation of Work executed (including, where there are separable portions, the Work performed within each such separable portion);
 - (iii) include the amount and particulars of any adjustments to the Subcontract Sum;
 - (iv) include the total amount previously certified pursuant to subclause 22.2;
 - (v) include the total amount previously paid or deemed to have been paid to the Subcontractor;
 - (vi) include the amount then claimed by the Subcontractor;
 - (vii) include the Subcontractor's estimated cost to complete the Works;
 - (viii) be accompanied by a warranty in the form attached as Schedule 15 duly executed by the Subcontractor;
 - (ix) be accompanied by certificates of currency in respect of each policy of insurance required to be held by the Subcontractor pursuant to this Subcontract; and
 - (x) be accompanied by any other documents requested by the Subcontract or reasonably required by Downer.

22.2 Certificates

(a) Downer must, within 10 Business Days after receiving a progress claim made in accordance with clause 22.1, assess the claim and issue to the Subcontractor a progress certificate evidencing Downer's opinion, subject always to clause 22.8, of the moneys due from Downer to the Subcontractor pursuant to the progress claim (if any) or from the Subcontractor to Downer (as the case may be) and reasons for any difference (Progress Certificate).



- (b) If the Subcontractor does not make a Progress Claim in accordance with clause 21.1, Downer may nevertheless issue a progress certificate.
- (c) Upon issue of a Progress Certificate the Subcontractor must within, two Business Days, issue a corresponding Tax Invoice to Downer for the value identified in the Progress Certificate.
- (d) Downer must, within the time stated in Item 41, pay the Subcontractor the amount due under the Progress Certificate less any set off Downer is entitled to make.
- (e) If the Progress Certificate shows an amount due from the Subcontractor to Downer or Downer's setting off results in an amount due from the Subcontractor to Downer, the Subcontractor must pay such amount within five Business Days after receiving the Progress Certificate.
- (f) Downer may, in any subsequent Progress Certificate, amend an earlier Progress Certificate.

22.3 Unfixed plant and materials

- (a) Downer will not be liable to pay for unfixed plant and materials unless they are listed in Item 33 and the Subcontractor:
 - (i) provides the additional security in Item 42;
 - (ii) satisfies Downer that the subject plant and materials have been paid for, properly stored and protected, and labelled the property of Downer; and
 - (iii) satisfied Downer that the subject plant and materials have been insured and such insurance notes Downer's interests.
- (b) Upon payment to the Subcontractor and the release of any additional security in clause 22.3(a)(i), the subject plant and materials will be the unencumbered property of Downer.

22.4 Final Payment Claim and certificate

- (a) Within 20 Business Days of the last to occur of the expiry of all Defects Liability Periods or the rectification by the Subcontractor of all Defects in accordance with clause 19.1, the Subcontractor must give Downer a written final payment claim endorsed 'Final Payment Claim' being a progress claim together with all other claims whatsoever in connection with the subject matter of the Subcontract to the extent not already barred (Final Payment Claim).
- (b) Within the earlier of 10 Business Days after the receipt of the Final Payment Claim or, where no Final Payment Claim is made by the Subcontractor, 10 Business Days after the last date for submitting the Final Payment Claim pursuant to clause 22.4(a), Downer must issue to the Subcontractor a Final Certificate evidencing the moneys finally due and payable between the Subcontractor and Downer on any account whatsoever in connection with the subject matter of the Subcontract.
- (c) The Subcontractor must, as a condition precedent to the release of the balance of security pursuant to clause 8.5 and receiving any amount certified as being payable in accordance with clause 22.4(d), provide to Downer an executed Deed of Final Release in the form set out at Schedule 3A setting out the moneys finally due and payable between the Subcontractor and Downer, as certified in the Final Certificate.
- (d) Those moneys certified by Downer as due and payable must be paid:
 - (i) by the Subcontractor (if the Final Certificate shows an amount payable by the Subcontractor) within 10 Business Days after the Final Certificate is issued; or
 - (ii) by Downer (if the Final Certificate shows an amount payable by Downer) by the later of:
 - (A) 10 Business Days after the Final Certificate is issued; and
 - (B) five Business Days after the Subcontractor provides to Downer the executed Deed of Final Release strictly in accordance with this Subcontract.

22.5 Interest

The Subcontractor is liable to pay to Downer interest at the rate stated in Item 34 on any amounts that the Subcontractor fails to pay to Downer by the date on which such amount becomes due and payable under this Subcontract.

22.6 Effect of payment

Any payment made by Downer to the Subcontractor is on account only and is not evidence of the value of the Work or that the Work has been satisfactorily completed.

22.7 Provisional sums

- (a) The Subcontract Sum includes the provisional sums (**Provisional Sum Allowance**), if any, stated in Part B of the Subcontract Details.
- (b) No part of the Provisional Sum Allowance is itself payable by Downer but where at the Direction of Downer the work or item to which the Provisional Sum Allowance relates is performed or supplied by the Subcontractor, the provisions of clause 22.7(c) to (f) shall apply.
- (c) Unless otherwise specified in this Subcontract, the Provisional Sum Allowance includes the costs associated with the supply, delivery, storage and installation of goods and materials, together with any on or off site work. The Provisional Sum Allowance includes all taxes (but excluding GST) as applicable and includes the Subcontractor's allowances for attendance and profit for the work covered by or associated with the scope of the work to which the Provisional Sum Allowance relates.



- (d) It is the Subcontractor's responsibility to advise Downer in sufficient time of the date when any items to which a Provisional Sum Allowance applies are required on Site to ensure that the requisite design documentation, tendering, order, manufacture and delivery times will comply with the approved program and not cause a delay to the performance of the Work.
- (e) Downer's Representative shall adjust the Provisional Sum Allowance as follows:
 - (i) where a part or the whole of the work or item to which the Provisional Sum Allowance relates is performed or supplied by or on behalf of the Subcontractor at the Direction of Downer, the actual value of the work or item shall be valued by Downer's Representative and, subject to clause 22.7(f) the difference added to or deducted from the Subcontract Sum; or
 - (ii) if Downer does not issue a Direction to the Subcontractor to perform work the subject of a Provisional Sum Allowance, the Subcontract Sum shall be reduced by an amount equal to that Provisional Sum Allowance.
- (f) If a percentage amount is stated in Item 35, then the adjustment to the Subcontract Sum pursuant to clause 22.7(e)(i) must include an increase at the percentage stated calculated upon any amount by which the actual value of the item or work the subject of a Provisional Sum Allowance as valued by Downer's Representative exceeds the amount of a relevant Provisional Sum Allowance.

22.8 Set off

Without prejudice to any other right available to Downer under this Subcontract or at law, Downer may, at any time, deduct or set-off from either or both of any money payable or to become payable by Downer to the Subcontractor under this Subcontract and/or any security provided by the Subcontractor under this Subcontract:

- (a) any money due, or reasonably claimed to be due or to become due, from the Subcontractor to Downer whether in connection with this Subcontract or otherwise, including:
- (b) any amount payable or allowable in favour of Downer by way of liquidated damages;
- (c) any amount which the Subcontractor owes to Downer (whether or not the amount is expressed to be a debt due from the Subcontractor to Downer or is an amount in respect of which the Subcontractor indemnifies Downer); and
- (d) any other loss, cost, expense or damage incurred by Downer in respect of which the Subcontractor is or may be liable to Downer (including under this Subcontract, any other agreement or on any other basis whatsoever).

22.9 Subcontract Sum

The Subcontract Sum, including any rates set out in this Subcontract (including the Schedule of Rates), will not be subject to adjustment for rise and fall, exchange rate variations or any changes to general or market specific economic conditions.

22.10 Direct payments

The Subcontractor must ensure that its subcontractors are paid in accordance with the terms of their subcontracts. If Downer reasonably forms the view that a subcontractor engaged by the Subcontractor:

- (a) has not been paid an amount due to it under its subcontract; and/ or
- (b) has become entitled to suspend work under a subcontract (whether under statute, contract or otherwise) because of a failure by the Subcontractor to pay moneys to the subcontractor,

Downer or the Principal may pay directly to the subcontractor the amount claimed by the subcontractor, and any amount so paid by Downer or the Principal will be a debt due and payable by the Subcontractor to Downer.

23 Practical Completion

23.1 Notice

- (a) The Subcontractor must notify Downer's Representative in writing when it considers it has achieved Practical Completion.
- (b) The achievement of Practical Completion requires, in addition to any other requirement of this Subcontract, compliance with the following:
 - (i) that the Work (including equipment, plant services and installation) has been demonstrated and tested to the satisfaction of Downer's Representative:
 - (A) to perform as required by this Subcontract both under normal conditions and under emergency conditions; and
 - (B) to have been tested, commissioned and be in a continually usable condition; and
 - (ii) the Subcontractor has provided to Downer's Representative:
 - (A) an executed Deed of Release in the form set out in Schedule 3; and
 - (B) all warranties, guarantees, manuals and drawings required under this Subcontract or reasonably requested by Downer's Representative, in a format acceptable to Downer's Representative, and any other warranties which are available from suppliers and manufacturers for the equipment, plant or materials used in or provided for the Work; and
 - (iii) the Subcontractor has:
 - (A) handed over all necessary information required by Downer's Representative for the operation and maintenance of the Work;



- Subcontract Long Form
- (B) removed all rubbish, plant and surplus material from the Site, other than plant and equipment required for the carrying out of the Subcontractor's obligations in the Defects Liability Period; and
- (C) procured all certificates and Approvals from all necessary authorities to the extent the Subcontractor is required by this Subcontract to procure them.

23.2 Practical Completion

When Downer's Representative is of the opinion that the Work has achieved Practical Completion and that the Subcontractor has complied with all other relevant obligations, Downer's Representative must certify Practical Completion by issuing a certificate to that effect to the Subcontractor, identifying the date on which Practical Completion was achieved, which date may be a date other than that on which the certificate of Practical Completion is issued.

23.3 Liquidated damages

- (a) If Practical Completion is not achieved by the Date for Practical Completion, the amount of liquidated damages at the rate set out in Item 36 shall accrue as a debt due and immediately payable by the Subcontractor to Downer for every day after the Date for Practical Completion until and including the earlier of:
 - (i) the Date of Practical Completion; or
 - (ii) the date that this Subcontract is terminated or the Work is taken out of the Subcontractor's hands.
- (b) The liability of the Subcontractor under this clause 23.3 is not and is not deemed to be, inclusive of nor does it in any way limit or reduce, any amount for which the Subcontractor is liable under any indemnity under this Subcontract.
- (c) If liquidated damages are found to be void, voidable or unenforceable on any basis so that Downer is not entitled to claim liquidated damages for the Subcontractor's failure to reach Practical Completion by the Date for Practical Completion, Downer is entitled to claim general law damages if the Subcontractor fails to reach Practical Completion by the Date for Practical Completion.
- (d) If an Extension of Time is directed after the Subcontractor has paid or Downer has set-off liquidated damages, Downer shall forthwith repay or allow to the Subcontractor an amount equal to such of those liquidated damages as represent the days the subject of the Extension of Time.
- (e) The Parties acknowledge and agree that the amount(s) for liquidated damages payable under this Subcontract are a genuine pre-estimate of Downer's damages if the Work does not reach Practical Completion by the Date for Practical Completion.
- (f) A failure by Downer at any time to demand payment or to deduct, withhold or set-off the liquidated damages does not amount to a waiver of, or otherwise affect, Downer's rights and entitlements.

23.4 Separable portions

- (a) At any time and from time to time, separable portions may be directed by Downer's Representative, including if any part of the Work has reached a stage equivalent to Practical Completion but others have not.
- (b) The definitions of Practical Completion, Defects Liability Period, Date for Practical Completion and Date of Practical Completion and clauses 8, 19, 20 and 21 apply separately to each separable portion.
- (c) Thereafter, references to the Work mean so much of the Work as is comprised in the relevant separable portion.
- (d) The amount of the liquidated damages applicable to a separable portion are such proportion of the amount applicable to the whole of the Work as the value of the separable portion bears to the Subcontract Sum.
- (e) Where separable portions have been directed and without limiting any other provision of this Subcontract with respect to Downer's rights in respect of security, security provided by the Subcontractor shall not be released until the circumstances for the release prescribed by this Subcontract have been satisfied in respect of the Work the subject of the last separable portion to reach Practical Completion.

24 Industrial relations

24.1 Compliance

- (a) The Subcontractor must comply, and must ensure that all of its workforce, Secondary Subcontractors and agents comply, with all Legal Requirements in respect of industrial and workplace matters, including:
 - (i) all state and federal legislation and legally enforceable codes of practice which apply to the Work or the Site; and
 - (ii) all applicable legally enforceable agreements, awards and workplace agreements.
- (b) The Subcontractor must make available upon reasonable notice whatever documents and records Downer's Representative requests to see concerning compliance with this clause.

24.2 Industrial disputes

- (a) The Subcontractor must do everything possible to avoid and minimise the consequences of industrial disputes of any kind.
- (b) The Subcontractor is responsible for and assumes all risks of and incidental to all industrial actions, actions, bans, limitations and disputes (whether lawful or unlawful) in relation to industrial relations or employment issues both on and off Site with its workforce and those of its Secondary Subcontractors and agents.



25 Work Health and Safety

Without limiting any other obligation of the Subcontractor under this Subcontract, the Subcontractor must comply with the OHS Rules.

26 Environment

26.1 Compliance

The Subcontractor must comply with all Legal Requirements in respect of environmental matters and the protection or preservation of the environment including all state and federal legislation and codes of practice which apply to the Work or the Site.

26.2 Hazardous substances and materials

If the Subcontractor intends to bring onto the Site any material or substance which may be hazardous to health and safety, the Subcontractor must, before doing so, give information to Downer's Representative in respect of such material or substance. The information must include plans for the safe handling, storage and use of the material or substance and precautions to be taken.

26.3 Preventative measures and contamination

The Subcontractor must do everything possible to protect and preserve the environment from harm or damage arising from or in connection with the carrying out of the Work and is responsible for all such harm or damage, including any contamination, to the extent caused or contributed to by the Subcontractor or the Work.

26.4 Environmental Reporting

The Subcontractor must provide to Downer, upon request, any data and information that is or may be required by Downer, the Principal or any third party to comply with the *National Greenhouse and Energy Reporting Act 2007* (Cth) to the extent that such data and information relates to the Work or this Subcontract.

27 Default and Termination

27.1 Notice of Subcontractor Default

If in the opinion of Downer, the Subcontractor commits a breach of this Subcontract then, without limiting any other right it may have, Downer may by notice in writing serve upon the Subcontractor a notice entitled "Notice of Subcontractor Default". Upon giving a Notice of Subcontractor Default, Downer may suspend payments to the Subcontractor until the breach is remedied.

27.2 Contents of Notice of Subcontractor Default

A Notice of Subcontractor Default given under clause 27.1 must:

- (a) state that it is given under clause 27.1;
- (b) identify and particularise the breach complained of; and
- (c) specify a time which is at least seven days from the date the Notice of Subcontractor Default is given, within which the Subcontractor must either remedy the breach or show cause to Downer's satisfaction why Downer ought not exercise a right under clause 27.3.

27.3 Failure by Subcontractor to remedy or show cause

- (a) If the Subcontractor fails either to remedy the breach or to show cause to Downer's satisfaction why Downer ought not exercise its rights under this clause 27.3, Downer may by notice in writing with immediate effect:
 - (i) take out of the hands of the Subcontractor the whole or any part of the Work remaining to be completed, engage others to, or itself, carry out any part or the whole of the remaining Work and suspend payment until an amount (if any) becomes due and payable to the Subcontractor pursuant to clause 27.6(b); or
 - (ii) terminate this Subcontract.
- (b) The exercise of a right under clause 27.3(a) will be effective immediately and will not affect any other rights available to Downer.

27.4 Breaches

- For the purposes of clause 27.1, a breach by the Subcontractor includes:
- (a) suspension of the Work;
- (b) failure to proceed with due expedition and without delay (regardless of whether or not the Date for Practical Completion has passed);
- (c) failure to use the materials or standards of workmanship required by this Subcontract;
- (d) failure to provide evidence of insurances required by this Subcontract;
- (e) failure to comply with any Direction of Downer's Representative issued under a provision of this Subcontract;
- (f) failure to properly protect any person or property;
- (g) failure to maintain any licence or Approval required of the Subcontractor for the performance of the Work;
- (h) failure to immediately confirm, upon request for confirmation by Downer's Representative, that the Subcontractor is able and willing to complete performance of this Subcontract in accordance with its obligations;



- Subcontract Long Form
- (i) failure to complete any milestone by any relevant milestone date as required by clause 20.5;
- (j) any act or omission by the Subcontractor that results or may result in Downer being in breach of the Head Contract Requirements; and
- (k) failure to rectify a Defect, error, omission or deficiency in the Work in accordance with this Subcontract.

27.5 Subcontractor unable or unwilling to complete

If the Subcontractor advises Downer that the Subcontractor is unable or unwilling to complete performance of this Subcontract, Downer may immediately (and without serving upon the Subcontractor a Notice of Subcontractor Default) exercise a right under clause 27.3.

27.6 Procedure upon termination or taking work out of hands

- (a) Despite any other provision of this Subcontract, if Downer terminates this Subcontract or takes any Work out of the Subcontractor's hands and engages others to carry out or itself carries out any part or the whole of the remaining Work (including by way of Variation), Downer may without payment of compensation to the Subcontractor:
 - take possession of all documents (including Design Documents), information and the like in the Subcontractor's possession which is connected with the Work and reasonably required by Downer to facilitate completion of the Work and the Subcontractor must immediately deliver up all such documents, information and the like to Downer;
 - (ii) take an assignment of the Subcontractor's rights and benefits under any Secondary Subcontracts including any warranties and guarantees. The Subcontractor must do all things necessary to effect such an assignment; and
 - (iii) take possession of such plant, equipment and other things on or about the Site as are owned by the Subcontractor and are reasonably required by Downer to facilitate completion of the Work. Downer must return any plant, equipment and other things which are surplus to the Subcontractor on completion of the relevant Work, subject to the Subcontractor satisfying the debt to Downer as determined under clause 27.6(c).
- (b) When that part of the Work taken out has been completed, Downer shall assess the cost thereby incurred and shall certify as moneys due and payable accordingly the difference between the cost (showing the calculations therefor) and the amount which would otherwise have been paid to the Subcontractor if the work had been completed by the Subcontractor.
- (c) If the Subcontractor is indebted to Downer, Downer may retain any Subcontractor's plant or other things taken under clause 27.6 until the debt is satisfied. If after reasonable notice the Subcontractor fails to pay the debt, Downer may sell the Subcontractor's plant or other things and apply the proceeds to the satisfaction of the debt and the costs of sale. Any excess shall be paid to the Subcontractor.

27.7 Termination by Subcontractor

- (a) If Downer fails to pay an undisputed amount that is due and payable to the Subcontractor under this Subcontract and such failure continues for a period of more than 28 days after the Subcontractor provides Downer with written notice thereof and identifying its rights under this clause 27.7, the Subcontractor may suspend performance of Work.
- (b) The Subcontractor must promptly recommence performance of Work upon remedy of the breach by Downer.
- (c) The Subcontractor may, by written notice to Downer terminate this Subcontract if, within 28 days of the date of commencement of suspension pursuant to clause 27.7(a), Downer has failed to remedy the breach.
- (d) Damages reasonably and necessarily incurred by the Subcontractor by reason of a suspension pursuant to clause 27.7(a) shall be assessed by Downer who shall certify the amount due and payable to the Subcontractor. This amount shall be the limit of the Subcontractor's entitlement arising from the suspension of the Work.
- (e) The Subcontractor acknowledges and agrees that this clause 27.7constitutes the Subcontractor's sole right to terminate this Subcontract as a consequence of Downer's breach (howsoever occurring).

27.8 Insolvency

- (a) Without prejudice to any other right either Party may have, Downer or the Subcontractor may terminate this Subcontract by notice in writing upon the date stated in the notice if the other Party is subject to an Insolvency Event.
- (b) Despite any other provision of this Subcontract, from the date Downer is entitled to terminate this Subcontract under clause 27.8(a):
 - (i) Downer is deemed to have become entitled to recourse to all retention monies and Bank Guarantees still held by Downer; and
 - (ii) the Subcontractor has no entitlement to (or to make any Claim in respect of) and Downer has no obligation to return to the Subcontractor any retention monies or Bank Guarantees still held by Downer.

27.9 Immediate Termination

Without prejudice to any other right Downer may have, Downer may terminate this Subcontract by notice in writing upon the date stated in the notice if:

- (a) there is any change in the legal or equitable ownership of the Subcontractor without Downer's prior written consent (which Downer may withhold in its absolute discretion);
- (b) the Subcontractor is in breach of clauses 34 or 35, or a Suspected Slavery occurs; or



- (c) the Subcontractor knowingly provides documents containing an untrue or misleading statement or information; or
- (d) the amount of liquidated damages paid or payable by the Subcontractor under this Subcontract reaches the limit on liquidated damages set out in this Agreement (or would exceed the limit on liquidated damages set out in this Subcontract in the absence of such limit).

27.10 Termination for convenience

- (a) Downer may at any time and for any reason (or for no reason and without any requirement to provide any reason), including for its convenience, terminate this Subcontract by issuing a notice of termination to the Subcontractor. When the Subcontractor receives a notice of termination from Downer under this clause, the Subcontractor must
 - (i) stop all Work to the extent required by the notice of termination;
 - (ii) take such action as necessary or as Downer directs for the transfer, protection and preservation of Downer property;
 - (iii) use its best endeavours to minimise the cost of termination of this Subcontract (as applicable) to Downer; and
 - (iv) provide to Downer a written claim for the amounts set out in clause 27.10(b), in compliance with clause 22.1, within 15 Business Days of the effective date of termination.
- (b) Where Downer terminates this Subcontract pursuant to clause 27.10(a), Downer must pay to the Subcontractor:
 - (i) the amount due for the Work that has been completed by the Subcontractor in accordance with this Subcontract prior to the date of termination;
 - (ii) the cost of materials reasonably ordered by the Subcontractor for the Work, which the Subcontractor is liable to accept, but only if the materials become the property of Downer upon payment;
 - (iii) the reasonable cost of removal of plant and equipment; and
 - (iv) all Bank Guarantees or retention monies to which Downer is not otherwise entitled.

Such payment will constitute the full and final compensation payable by Downer to the Subcontractor under or in connection with this Subcontract, the Subcontractor will have no Claim against Downer in relation to or in connection with such termination, and Downer will not be liable to the Subcontractor for any amounts in addition to those set out in this clause 27.10(b).

27.11 Termination of the Head Contract

- (a) Without limiting any other right available to Downer under this Subcontract or at law, if the Head Contract is terminated at any time for any reason, Downer may terminate this Subcontract by notice in writing to the Subcontractor.
- (b) If the Subcontractor terminates this Subcontract under clause 27.11(a), the Subcontractor's entitlements are limited to those set out in clause 27.10(b).

27.12 Effect of Termination by Downer

If the Subcontract is terminated by Downer pursuant to clause 27.3, 27.08, 27.9 or 27.11:

- (a) Downer is not required to make any further payment to the Subcontractor, and without limiting any other right of Downer conferred by this Subcontract, the rights and liabilities of the parties shall be the same as they would be at common law if the Subcontractor had wrongfully repudiated this Subcontract and Downer had elected to treat this Subcontract as at an end and recover damages;
- (b) Downer may at any time and from time to time estimate the damages to which it is entitled as a consequence of the (deemed) wrongful repudiation of this Subcontract by the Subcontractor and advise the Subcontractor of the amount of the estimated damages. Until the damages to which Downer is entitled are finally ascertained, that estimate shall be a debt due and immediately payable by the Subcontractor to Downer, and Downer is entitled to withhold, set-off or otherwise deduct the amount of that estimate; and
- (c) the Subcontractor must cease the performance of the Work and make the Site safe for employees and others and report any hazards or risks to Downer.

28 Dispute Resolution

28.1 Notice

- (a) If a dispute or difference arises between Downer and the Subcontractor out of or in connection with the Work or this Subcontract, either Party may give the other a written notice specifying the dispute or difference. The notice must specify in reasonable detail the nature of the dispute or difference and the notice must specify in reasonable detail the legal basis of any Claim made by the Party serving the notice.
- (b) Subject to clause 28.5, neither Party may commence proceedings (other than to recover an amount due and payable by the Subcontractor under this Subcontract, or for injunctive or other urgent relief) in respect of any dispute or difference unless a notice under clause 28.1(a) has been served and the procedure in clauses 28.2, 28.3 and 28.4 have been complied with.

28.2 Meeting

(a) If a dispute or difference notified under clause 28.1(a) has not been settled within 14 days of the date of that notice, either Party may, by written notice to the other, require that a person holding a position of senior management of each



of Downer and the Subcontractor meet and undertake genuine and good faith negotiations on a without prejudice basis with a view to resolving the dispute or difference.

- (b) If a meeting is required under this clause by either Party, then each Party must ensure attendance on its behalf by a person holding a position of senior management. Each Party must use its best endeavours to ensure that a meeting required under this clause takes place within 14 days of the receipt of a valid written notice requiring the meeting.
- (c) If the dispute or difference involves or may involve the Principal, at the option of Downer, the Principal may participate in any meeting held under this clause 28.2 (and the Subcontractor hereby irrevocably consents to such participation).

28.3 Mediation

- (a) If the dispute or difference is not resolved within 28 days of the giving of notice under clause 28.1, the Parties must refer the dispute or difference to mediation in accordance with clause 28.3(b).
- (b) If a dispute or difference is referred to mediation as referred to under clause 28.3(a), the Parties agree that:
 - a mediator is to be appointed by agreement between the parties or failing such agreement within 14 days of the referral to mediation, is to be appointed by the Chairman of the relevant Chapter of the Resolution Institute in the State or Territory stated in Item 11 or the Chairman's nominee;
 - (ii) each Party must bear its own costs of the mediation save that the Parties must share equally the mediator's fees, fees for mediation rooms and costs of shared equipment, facilities and services of the mediation;
 - (iii) the Parties must agree the venue for the mediation and if they cannot agree, the mediator appointed must nominate the venue;
 - (iv) each Party may be legally represented in the mediation if they so wish;
 - (v) complete confidentiality must be preserved in respect of the mediation and any documents and information used at or in relation to the mediation; and
 - (vi) mediation proceedings including any documents and information used at or in relation to the mediation must not be used as evidence in any legal proceedings and the Parties agree not to compel the mediator to give evidence as to any matter in relation to the mediation in any legal proceedings.

28.4 Resolution not involving Head Contract

- (a) Subject to clauses 28.5 and 28.6, if the dispute has not been resolved within 14 days after the Parties have attended mediation in accordance with clause 28.3, (or such other period as agreed by the parties), either Party may refer the dispute to the dispute resolution forum identified in Item 43.
- (b) Subject to clause 28.4(c), neither Downer nor the Subcontractor may refer the dispute to the forum identified in Item 43 unless they have first complied with clauses 28.1 to 28.3 in relation to the dispute or difference.
- (c) Clause 28.4(b) does not prevent either Party from instituting proceedings to seek injunctive or other urgent relief in respect of a Dispute or difference arising under this Subcontract.
- (d) In the event that the forum for resolution of the dispute identified in the Subcontract Details is arbitration, the arbitrator's decision or majority decision of arbitrators (as applicable) shall be final and binding on the Parties.

28.5 Consistent Resolution

- (a) Where a dispute arises between Downer and the Principal under the Head Contract (including by way of arbitration or expert determination) which Downer considers concerns matters which are relevant to the Subcontractor's rights and obligations under this Subcontract, Downer may at any time prior to the final resolution of that dispute, elect to have Downer's and the Subcontractor's rights and obligations determined in that dispute simultaneously, and if so:
 - (i) the Subcontractor must, at the expense of the Subcontractor give Downer all necessary assistance and cooperation with respect to the dispute; and
 - (ii) Downer must ensure that any claims of the Subcontractor in respect of the Principal are put to the dispute resolution procedures referred to in the Head Contract.
- (b) The Subcontractor agrees that, in respect of a dispute to which this clause 28.5 applies, clauses 28.3 and 28.4 shall cease to apply to the subject matter of that dispute and it will be bound by any determination in the dispute resolution procedures under the Head Contract that affects the Subcontractor's rights and obligations as though that determination had been made under the dispute resolution procedures in this Subcontract.

28.6 Consolidation

If Downer and the Principal are parties to litigation, arbitration or an expert determination in connection with the Head Contract (Head Contract Dispute Process), Downer may direct that:

- (a) any dispute that arises between Downer and the Subcontractor (whether such dispute arises before or after the commencement of the Head Contract Dispute Process) be referred to litigation, arbitration or expert determination (as applicable); and
- (b) such litigation, arbitration or expert determination (as applicable) between Downer and the Subcontractor will be consolidated with the Head Contract Dispute Process,

in which case, clauses 28.3 and 28.4 shall cease to apply to the subject matter of that dispute and the Subcontractor irrevocably agrees to the referral of the relevant dispute to litigation, arbitration or expert determination (as applicable) and



agrees (and irrevocably waives any entitlement to object) to such consolidation of litigation, arbitral proceedings or expert determination processes (as applicable).

29 Claims

29.1 Making of Claims

Except for Claims for an Extension of Time under clause 21.1 or payment under clause 22, or a Claim which another provision of this Subcontract expressly sets out the time, method and process whereby the Subcontractor may submit the Claim, the Subcontractor must give Downer the notices required by clause 29.2 if it wishes to make a Claim against Downer in respect of any Direction, act, omission or any other fact, matter or thing (including a breach of this Subcontract by Downer) under, arising out of or in any way in connection with the Work or this Subcontract.

29.2 Prescribed Notice

The notices referred to in clause 29.1 are:

- (a) a notice within 10 Business Days after the commencement of the first occurrence of the Direction, act, omission or any other fact, matter or thing upon which the Claim is based, expressly specifying that the Subcontractor proposes to make a Claim and the Direction, act, omission or any other fact, matter or thing upon which the Claim is based; and
- (b) a written Claim within 10 Business Days after the date on which the notice was required to be given to Downer pursuant to clause 29.2(a), which must include:
 - (i) detailed particulars concerning the Direction, act, omission or other fact, matter or thing upon which the Claim is based;
 - (ii) the legal basis for the Claim, including the terms of this Subcontract upon which the Claim is based;
 - (iii) the facts and evidence relied upon in support of the Claim in sufficient detail to permit verification; and
 - (iv) details of the amount claimed and how it has been calculated.

29.3 Continuing Events

If the Direction, act, omission or other fact, matter or thing upon which the Claim under clause 29.2 is based or the consequences of the Direction, act, omission or other fact, matter or thing are continuing, the Subcontractor must continue to give the information required by clause 29.2(b) every 20 Business Days after the written Claim under clause 29.2(b) was required to be given to Downer, until after the Direction, act, omission or any other fact, matter or thing upon which the Claim is based, has, or the consequences thereof have, ceased.

29.4 Condition Precedent

It is a condition precedent to the Subcontractor's entitlement to make a Claim that the Subcontractor has fully complied with the requirements of clauses 29.1, 29.2 and 29.3.

If the Subcontractor fails to comply with clause 29.1, 29.2 or 29.3, Downer will not be liable upon any Claim by the Subcontractor and the Subcontractor will be absolutely barred from making any Claim against Downer, arising out of, or in any way in connection with, the relevant Direction, act, omission or other fact, matter or thing (as the case may be) to which clause 29.1 applies.

30 Goods and Services Tax

30.1 Exclusive of GST

Unless otherwise expressly stated, prices or other sums payable or consideration to be provided under or in accordance with this Subcontract are exclusive of GST.

30.2 Payment of GST

If a Party makes a taxable supply under or in connection with this Subcontract, the other Party must pay to the supplier at the same time, and in addition to the GST-exclusive consideration, an amount equal to the GST payable on that supply.

30.3 Tax Invoice

The supplier must, as a precondition to the payment of GST, give the other Party a tax invoice by the end of the month in which the supply is made.

30.4 Adjustments

If an adjustment event arises in connection with a supply made under this Subcontract, the supplier must give the other Party an adjustment note in accordance with the GST law.

30.5 Reimbursements

If this Subcontract requires one Party to pay for, reimburse or contribute to any expense, loss or outgoing suffered or incurred by the other Party, the amount required to be paid, reimbursed or contributed by the first Party will be reduced by the amount on input tax credits (if any) to which the other Party is entitled in respect of the reimbursable expense.

30.6 Defined terms

In this clause 30:

(a) words and expressions which have a defined meaning in the *A New Tax System (Goods and Services Tax) Act* 1999 (Cth) (**GST Act**) have the same meaning as in the GST Act; or



- Subcontract Long Form
- (b) if that GST Act does not exist for any reason, means any Act imposing or relating to the imposition or administration of a goods and services tax in Australia and any regulation made under that Act.

31 Security of Payment

31.1 Application

The provisions set out in the State and Territory Specific Provisions with respect to the Security of Payment Act shall apply in accordance with clause 1.4 of this Subcontract.

31.2 Downer's Representative's role

Without limiting Downer's right to issue a payment schedule under the Security of Payment Act, the Subcontractor acknowledges and agrees that in issuing payment schedules under the Security of Payment Act, Downer's Representative does so (and is authorised by Downer to do so) as agent of Downer.

31.3 Adjudication

If the Subcontractor applies for adjudication under the Security of Payment Act, the authorised nominating authority in respect of such an adjudication application is one of the bodies stated in Item 37.

32 General

32.1 Notices

- (a) A notice or other communication connected with this Subcontract (Notice) has no legal effect unless it is in writing.
- (b) Subject to clause 32.1(c), in addition to any other method of service provided by law, the Notice must be:
 - (i) sent by prepaid post to the address for service of the addressee set out in the Subcontract Details or subsequently notified;
 - (ii) delivered at the address for service of the addressee set out in the Subcontract Details or subsequently notified; or
 - (iii) sent by email to the email address of the addressee set out in the Subcontract Details.
- (c) A Notice given by the Subcontractor under clause 9 or clause 21 or under the Security of Payment Act must not be sent by email. A Notice given by the Subcontractor under clause 27 or clause 28 must be sent by registered mail or delivered (not by email) to Downer's address set out in Item 38.
- (d) A notice is taken as given by the sender and received by the intended recipient:
 - (i) if sent by post, three Business Days after posting;
 - (ii) if sent by email:
 - (A) when the sender receives an automated message confirming delivery; or
 - (B) four hours after the time sent (as recorded on the device from which the sender sent the email) unless the sender receives an automated message that the delivery failed,

whichever happens first; or

- (iii) if otherwise delivered before 5pm on a Business Day at the place of delivery, upon delivery, and otherwise on the next Business Day at the place of delivery.
- (e) The Subcontractor, Downer and Downer's Representative must each notify the others in writing of any change of contact details set out in Item 38.

32.2 Governing law and jurisdiction

- (a) This Subcontract is governed by the law of the State or Territory set out in Item 11. Each Party irrevocably submits to the non-exclusive jurisdiction of the courts of that State or Territory and any courts hearing appeals from them.
- (b) A Party must not object to the jurisdiction of a court merely because the forum is inconvenient.
- (c) Where the Subcontractor is not incorporated within the jurisdiction of any of the States or Territories of the Commonwealth of Australia, the Subcontractor:
 - submits to the non-exclusive jurisdiction of the courts of the Commonwealth of Australia and the State or Territory stated in Item 11 and any courts which have jurisdiction to hear appeals from any courts of that State or Territory;
 - (ii) waives any objections on the ground of venue or forum non-convenience or any similar grounds;
 - (iii) consents to service of process (which term includes any communication, notices, including any notices under this Subcontract, demand, summons, writ, statement of claim, pleading, judgment, order, decree or document) by mail or in any other manner permitted by the relevant law; and
 - (iv) the Subcontractor must at all times maintain an agent for service of process in the State or Territory stated in Item 11. Any process shall be sufficiently served on the Subcontractor if delivered to the agent for service at that agent's address for the time being.
- (d) The Subcontractor hereby appoints the person named in Item 12 as its agent for service for the purpose of this clause 32.2. The Subcontractor shall not revoke the authority of any agent for service and if for any reason, the agent no longer serves as agent for the Subcontractor to receive service of process, the Subcontractor shall promptly advise



Downer and appoint another such agent approved by Downer in writing. If the Subcontractor does not immediately appoint another such agent, Downer may thereafter

32.3 Confidentiality

- (a) The Subcontractor must keep all aspects of this Subcontract and all matters arising from the Work confidential and must not disclose these details to any third party without the written Approval of Downer except to the extent required by law and to enable performance of this Subcontract.
- (b) Subject to clause 32.3(c), the Subcontractor must not, and must ensure that its officers, advisers, agents, consultants, sub-subcontractors and employees do not, without the prior written Approval of Downer, at any time, including after the termination or expiry of this Subcontract:
 - (i) disclose or give to any person any Confidential Information; or
 - (ii) without limitation to the above, disclose or give to any person any information of the kind described in section 275(1) of the PPSA.
- (c) Clause 32.3(b) does not apply to the extent that the Confidential Information is:
 - (i) lawfully in the public domain at the time that the Confidential Information was disclosed or given; or
 - (ii) required to be disclosed or given to comply with any applicable law, the rules of any securities or stock exchange or an order of a court or tribunal and Downer is given prior notice of the disclosure.
- (d) Where the Subcontractor discloses any Confidential Information pursuant to this clause 32.3, it:
 - (i) must ensure that the party to whom the Confidential Information is provided or disclosed to complies with the terms of this clause 32.3; and
 - (ii) will be responsible and liable for any breach of the terms of this clause 32.3 by such third party as if the Subcontractor committed the breach.

32.4 Entire agreement

- (a) This Subcontract:
 - (i) contains the entire agreement and understanding between the parties on everything connected with the subject matter of this Subcontract; and
 - (ii) supersedes any prior agreement or understanding on anything connected with that subject matter.
 - No other terms or conditions will be incorporated into this Subcontract unless strictly in accordance with clause 32.9.
- (c) Any terms and conditions proposed, published or sent by the Subcontractor to Downer or otherwise referred to in any document or material provided by the Subcontractor to Downer (including any terms and conditions published on any website or contained in any online ordering process, whether or not acknowledged by Downer):
 - (i) do not form part of (and are expressly excluded from) this Subcontract;
 - (ii) do not apply to or bind Downer; and
 - (iii) are, as between Downer and the Subcontractor, void and unenforceable,

irrespective of whether such terms and conditions were proposed, published or sent (or referred to in any document or material provided) by the Subcontractor before, during or after execution of this Subcontract.

32.5 Waiver

(b)

- (a) A party's failure or delay to exercise a power or right does not operate as a waiver of that power or right.
- (b) The exercise of a power or right does not preclude either its exercise in the future or the exercise of any other power or right.
- (c) A waiver is not effective unless it is in writing.
- (d) Waiver of a power or right is effective only in respect of the specific instance to which it relates and for the specific purpose for which it is given.

32.6 Severability

If a provision or part of a provision in this Subcontract is wholly or partly invalid or unenforceable, the provision or part must, to that extent, be treated as deleted from this Subcontract. This does not affect the validity or enforceability of the remaining provisions.

32.7 Attorneys

Each attorney who executes this Subcontract states that the attorney has no notice of the revocation of the power of attorney appointing that attorney.

32.8 Retrospectivity

- (a) This Subcontract applies to all Work performed by the Subcontractor for Downer and any preliminary works in relation to the subject matter of this Subcontract performed by the Subcontractor, including any preliminary work performed by the Subcontractor before the date of this Subcontract.
- (b) The Parties acknowledge and agree that all payments made by Downer to the Subcontractor before the date of this Subcontract have been paid on account of the liability of Downer to pay to the Subcontractor the Subcontract Sum.



32.9 Variation of Agreement

Any variation or amendment of this Subcontract must be in writing and signed by both Parties or by persons authorised to sign for them.

32.10 Counterparts

This Subcontract may be executed in a number of counterparts. It comprises all the counterparts, taken together.

32.11 Costs and outlays

- (a) Each Party must pay its own costs and outlays connected with the negotiation, preparation and execution of this Subcontract.
- (b) The Subcontractor must pay all stamp duty and other government imposts payable in connection with this Subcontract and all other documents and matters referred to in this Subcontract when due or earlier if requested in writing by Downer.

32.12 UN Convention on Contracts for the International Sale of Goods

The parties agree that the Convention on Contracts for the International Sale of Goods does not apply to this Subcontract.

32.13 Liability of Downer

This Subcontract codifies the Subcontractor's entitlement to payment or reimbursement of any cost, loss, expense or damage and the Subcontractor shall have no entitlement to payment or reimbursement of any cost, loss, expense or damage unless expressly so provided in this Subcontract.

To the fullest extent permitted by law, Downer and its directors, employees, consultants, other subcontractors and agents shall not be liable to the Subcontractor:

- (a) under or in connection with this Subcontract (including in respect of any breach of this Subcontract);
- (b) in tort for negligence or otherwise;
- (c) otherwise at law (including by statute, to the extent that it is possible to so exclude liability) and in equity, including for restitution for unjust enrichment; or
- (d) on any other basis whatsoever,

for any cost, loss, expense or damage which is not expressly provided for in this Subcontract and the Subcontractor irrevocably waives any entitlement to make (and irrevocably releases Downer from) a Claim for any such cost, loss, expense or damage.

32.14 Non-performance of obligations

If the Subcontractor fails to perform or comply with any of its obligations or agreements contained in this Subcontract, Downer or the Principal may perform or comply with (or procure performance of or compliance with) those obligations or agreements. Any costs incurred by Downer in connection with the rights referred to in this clause 32.14 will be a debt due and payable by the Subcontractor to Downer on demand.

32.15 Customs Duties

The Subcontract Sum includes all customs duties. The Subcontractor shall be responsible for payment of customs duties, provided that Downer shall provide such assistance and documentation as the Subcontractor may require to expeditiously pay such customs duties. In the event the customs duties are reduced then the Subcontractor shall reduce the Subcontract Sum by the same amount as any reduction in customs duties.

32.16 Inspection

The Subcontractor shall at all times permit Downer and the Principal, their respective employees, agents and consultants during working hours, to have access to any place where Work or any related or ancillary activities are being done in connection with the Work for the purpose of inspecting the same. Any such inspection will not relieve or affect the Subcontractor's obligation to execute Work which complies with this Subcontract.

32.17 Facilities for Downer's Inspector

If requested by Downer, the Subcontractor shall provide office facilities including desk and telephone, at the Subcontractor's or the Secondary Subcontractor's manufacturing plants for use by Downer and the Principal's representatives.

32.18 Media

The Subcontractor shall not disclose any information concerning the Project for distribution through any communications media without Downer's prior written Approval (which may be withheld in Downer's absolute discretion). The Subcontractor shall refer to Downer any enquiries from the media concerning the Work.

32.19 Trust

If the Subcontractor enters into this Subcontract as trustee of a trust (Trust), it warrants that:

- (a) it has power to enter into and perform its obligations under this Subcontract in its capacity as trustee of the Trust;
- (a) the Trust has been validly created and is in existence at the date of this Subcontract;
- (b) the Subcontractor has been validly appointed as trustee of the Trust and is the sole trustee of the Trust;
- (c) the Subcontractor has valid rights of indemnity against the assets of the Trust, which rights are available for satisfaction of all liabilities and other obligations incurred by it under this Subcontract; and



- Subcontract Long Form
- (d) the rights of the beneficiaries of the Trust relating to, and their interests in, the property of the Trust are subject to the prior rights and interests of the Subcontractor in the property of the Trust pursuant to its right of indemnity.

33 Personal Property Securities Act

The Subcontractor:

- (a) acknowledges and agrees that:
 - (i) this Subcontract constitutes a Security Agreement; and
 - (ii) this Subcontract creates a Security Interest of Downer in:
 - (A) all materials, equipment and other things intended for Work which are located onsite or offsite;
 - (B) all construction plant, temporary works and other things on-site or off-site as are used by the Subcontractor or any Secondary Subcontractors; and
 - (C) all Work documents,

(Collateral);

- (b) consents to Downer registering Downer's Security Interest in the Collateral;
- (c) must not purport to dispose of, grant any interest in, give any form of security over, or create a Security Interest or allow a Security Interest to subsist over, the Collateral;
- (d) must not register any Security Interest in respect of the Work or Collateral on the PPS Register;
- (e) must at its cost procure the removal from the PPS Register each Security Interest it has registered in respect of the Work or Collateral upon the expiry or termination of this Subcontract, and must provide Downer with certification of the removal of the Security Interests pursuant to section 157 of the PPSA;
- (f) undertakes to:
 - (i) promptly sign any further documents and provide any further information (such information to be complete, accurate and up-to date in all respects) which Downer may reasonably require to:
 - (A) register a Financing Statement or Financing Change Statement on the PPS Register in relation to a Security Interest in the Collateral;
 - (B) register any other document on the PPS Register which is necessary to perfect Downer's Security Interest in the Collateral; or
 - (C) correct any error in any such document;
 - (ii) not register, or permit to be registered by any third party, a Financing Statement or a Financing Change Statement in respect of the Collateral without the prior consent of Downer;
 - (iii) keep full and complete records of the Collateral; and
 - (iv) do anything which Downer reasonably requires for the purpose of ensuring that the Security Interest is enforceable and perfected and to enable Downer to exercise its rights in connection with the Security Interest;
- (g) agrees that, to the extent permitted by law, the following provisions of the PPSA do not apply to this Subcontract: (i) section 95; (ii) section 121(4); (iii) section 125; (iv) section 129; (v) section 130; (vi) section 132(3)(d); (vii) section 132(4); (viii) section 135; (ix) section 142; and (x) section 143;
- (h) unless otherwise agreed to by Downer in writing, the Subcontractor waives its right to receive a Verification Statement in accordance with section 157 of the PPSA; and
- (i) must give Downer written notice of any change to the Subcontractor's name, address or other details set out in this Subcontract within five Business Days after the date of such change.

34 Compliance with Anti-Bribery Laws

- (a) The Subcontractor will at all times comply with:
 - all Legal Requirements relating to anti-bribery, anti-corruption and anti-money laundering including the *Criminal Code Act 1995* (Cth), the *Foreign Corrupt Practices Act* of the United States of America, and the *Bribery Act* 2010 of the United Kingdom (and must not do anything, or omit to do anything, to cause Downer to be in breach of any such Legal Requirements); and
 - (ii) Downer's 'Standards of Business Conduct' and 'Anti Bribery and Corruption Policy' as published from time to time.
- (b) The Subcontractor warrants that neither it, nor any Relevant Person, has been convicted of any offence, and has not been the subject of any investigation or enforcement proceedings by any governmental, administrative or regulatory body regarding any offence or alleged offence, under any applicable laws, rules and regulation relating to anti-bribery, anti-corruption and anti-money laundering.
- (c) At any time before the expiry of three years from the completion or termination of this Subcontract, the Subcontractor must permit Downer, its nominee, or the Principal (in this clause 34, each the Auditor) to conduct an audit and investigation:
 - (i) to verify the Subcontractor's compliance with this clause 34 (irrespective of whether there has been a breach or suspected breach); and/or



- Subcontract Long Form
- (ii) in relation to a Probity Event (or suspected Probity Event).
- (d) As part of an audit or investigation under this clause 34, the Subcontractor must:
 - (i) make available to the Auditor (and allow the Auditor to make and retain copies of) any documents, records and other information in the power, possession or control of the Subcontractor; and
 - (ii) meet with the Auditor and make available the Subcontractor's personnel to meet with the Auditor and answer reasonable questions in relation to the subject matter of the audit.
- (e) The Subcontractor must give Downer notice immediately upon becoming aware of a Probity Event or any breach (or suspected breach) of this clause 34.

35 Modern Slavery

- (a) The Subcontractor must take (and must ensure that each of its Relevant Persons take) all reasonable steps to ensure that no modern slavery, human trafficking, servitude, forced labour, bonded labour, child labour, slavery, forced marriage or deceptive recruiting for labour or services (**Modern Slavery**) is present in the Subcontractor's, or its Relevant Persons', supply chains, or in any part of their businesses.
- (b) The Subcontractor warrants that neither it nor any of its Relevant Persons:
 - (i) has been convicted of any offence involving Modern Slavery or Modern Slavery-like practices; and
 - (ii) having made reasonable enquiries, has been or is, to the best of its knowledge, the subject of any investigation, inquiry or enforcement proceedings by any governmental, administrative or regulatory body regarding any offence of alleged offence of or in connection to any form of Modern Slavery.
- (c) The Subcontractor must implement due diligence procedures for its Relevant Persons to minimise the risk of Modern Slavery in its supply chains.
- (d) The Subcontractor must implement a system (to a standard that is consistent with good industry practices) for monitoring and evaluating the effectiveness of the Subcontractor's actions taken under clauses 35(a) and 35(c).
- (e) The Subcontractor must promptly notify Downer:
 - (i) as soon as it becomes aware of any actual or suspected Modern Slavery in its or any of its Relevant Persons' supply chain which is connected to this Subcontract (**Suspected Slavery**); and
 - (ii) its approach to address and remediate the Suspected Slavery.
- (f) The Subcontractor must, on request from Downer (from time to time), provide all assistance and information reasonably necessary for Downer to prepare a modern slavery statement and otherwise comply with its obligations at law and Legal Requirements.
- (g) The Subcontractor must maintain a complete set of records to trace the supply chain of all goods and services provided to Downer in connection with this Subcontract, including:
 - (i) the steps taken by the Subcontractor under clauses 35(a); and
 - (ii) the due diligence processes taken under clauses 35(c) and 35(d).
- (h) Downer will at any time have the right to inspect and to copy the whole or part of any record referred to in clause 35(g).
- (i) Upon receiving a request in writing from Downer for a copy of any record referred to in clause 35(g), the Subcontractor must promptly provide a copy of that record to Downer.
- (j) The Subcontractor must train all of its officers and employees on the risks of Modern Slavery and on Downer's policies and procedures in relation to Modern Slavery, including the principles set out in Downer's 'Standards of Business Conduct'
- (k) The Subcontractor must keep a record of all training completed by its officers and employees and shall make a copy of the training record available to Downer on request.

36 Proportionate Liability

- (a) For the purposes of this clause 36, a reference to the Proportionate Liability Act means:
 - (i) the Civil Law (Wrongs) Act 2002 (ACT) and the Building Act 2004 (ACT);
 - (ii) the Civil Liability Act 2002 (NSW);
 - (iii) the Proportionate Liability Act 2005 (NT) and the Building Act 1996 (NT);
 - (iv) the Civil Liability Act 2003 (Qld);
 - (v) the Law Reform (Contributory Negligence and Apportionment of Liability (Proportionate Liability)) Amendment Act 2005 (SA);
 - (vi) the Civil Liability Act 2002 amended by the Civil Liability Amendment (Proportionate Liability) Act 2005 (Tas) and the Building Act 2000 (Tas);
 - (vii) the Wrongs Act 1958 (Vic); and
 - (viii) the Civil Liability Act 2002 (WA).
- (b) To the maximum extent permitted by law, the operation of the Proportionate Liability Act is excluded in relation to all and any rights, obligations and liabilities under this Subcontract whether such rights, obligations or liabilities are sought



to be enforced as a breach of contract or claim in tort (including negligence), in equity, under statute or otherwise at law.

- (c) The Subcontractor further agrees that:
 - (i) in each contract with each Relevant Person into which it enters for the carrying out and completion of the whole or any part of the Subcontractor's obligations under this Subcontract, it will include provisions that, to the extent permitted by law, effectively exclude the operations of the Proportionate Liability Act in relation to all rights, obligations or liabilities under such contract whether such rights, obligations or liabilities are sought to be enforced as a breach of contract or in tort (including negligence), in equity, under statute or otherwise at law; and
 - (ii) it will require and ensure that each Relevant Person will include in any further contract that it enters into with others for the carrying out and completion of the whole or any part of the Subcontractor's obligations under this Subcontract, provisions that, to the maximum extent permitted by law, each such further contract will include provisions that effectively exclude the operation of the Proportionate Liability Act in relation to all rights, obligations or liabilities under such further contract whether such rights, obligations or liabilities are sought to be enforced as a breach of contract, in tort (including negligence), in equity, under statute or otherwise at law.
- (d) The Subcontractor indemnifies Downer against any Loss or Claim which Downer suffers or incurs in respect of a breach by the Supplier of clause 36(c).
- (e) This clause 36 will survive the expiry or termination of this Subcontract or part thereof




Subcontract Details

Part A

Part A			
Item 1	Downer's Representative	Clause 1.1	Andrew Gayed
Item 2	Date for Practical Completion	Clause 1.1	30 September 2021
Item 3	Head Contract	Clause 1.1	Transport Access Program (TAP) 3 Tranche 3 – Easy Access Station Upgrades Managing Contractor Framework Agreement: ISD-15-4742-16 – Wollstonecraft Station
Item 4	Site	Clause 1.1	Wollstonecraft Station as per Exhibit E Contract Specific Requirements
Item 5	Principal	Clause 1.1	Transport for New South Wales
Item 6	Superintendent	Clause 1.1	James Hill
Item 7	Subcontract Sum	Clause 1.1	\$1,676,399.15 (Refer to the Schedule 1 - Pricing Schedule)
Item 8	Subcontractor's Representative	Clause 1.1	Mal Helweh
Item 9	Work	Clause 1.1	The construction and completion of Building works and associated works as more particularly described or reasonably to be inferred from Schedule 1 – Scope of Works, Drawings and Specifications.
Item 10	Date for commencement	Clause 3	02 November 2020
Item 11	Governing law	Clause 1.1(a) Clause 32.2(a)	New South Wales
Item 12	Subcontractor's process agent (where Subcontractor not incorporated in Australia)	Clause 32.2(d)	
Item 13	Currency	Clause 1.2(i)	Australia Dollar
Item 14	Place for Payments	Clause 1.2(i)	(If nothing stated, then Downer's address.)
Item 15	Hours and days for access to the Site	Clause 3.1(b)	As per Exhibit E Contract Specific Requirements
Item 16	Subcontract Documents	Clause 1.1, clause 6	 Formal Instrument of Agreement; Special Conditions of Subcontract, if any, as listed in Part C of the Subcontract Details; General Conditions of Subcontract (including Schedules); and Drawings and Specifications as listed in the Scope of Works.
Item 17	What obligations of the Subcontractor with respect to design of the Work are excluded	Clause 5	All design excluded other than temporary works design by an AEO accredited Designer / Consultant
Item 18	Are retention monies to be deducted in lieu of provision of Bank Guarantees	Clause 8.2	Yes
Item 19	Bank Guarantees	Clause 8.1	5% of Subcontract Sum (in 2 x 2.5% each of the Subcontract Sum)
Item 20	Retention moneys to be deducted	Clause 8.2	5%
Item 21	Percentage by which security reduced	Clause 8.4	50%



Item 22	Public liability and products liability insurance to be taken out by Subcontractor	Clause 9.2	 Written on an occurrence basis with a limit of indemnity not less than \$20,000,000 for each and every occurrence, and in the case of product liability, no less than \$20,000,000 in the aggregate during any 12 month period of insurance, which covers the liability of the Subcontractor for bodily injury to any third party, third party property damage, and advertising liability. The insurance must be in force prior to the date of this Subcontract and be maintained until the expiry of the Defects Liability Period.
Item 23	Contract works insurance	Clause 9.2	For an amount not less than the total Subcontract Sum plus 20% covering all things referred to in clause 13.5 against loss or damage resulting from any cause until the Subcontractor ceases to be responsible for their care, including the Subcontractor's liability under clause 13.5 and things in storage off Site and in transit to the Site The insurance must be in force prior to the date of this Subcontract and
			be maintained until the expiry of the Defects Liability Period.
Item 24	Motor vehicle insurance	Clause 9.2	Covering all mechanically propelled vehicles that are registered, or capable of being registered, for road use and are at any time used in connection with this Subcontract including, as a minimum:
			(i) insurance that is compulsory under applicable laws governing the use of motor vehicles and liability for personal injury or death; and
			(ii) liability insurance for third party property damage with a sum insured of not less than \$20,000,000 per occurrence.
			The insurance must be in force prior to the date of this Subcontract and be maintained until the expiry of the Defects Liability Period.
Item 25	Workers compensation insurance to be taken out by Subcontractor	Clause 9.2	As required by law in the State or Territory in which the Work is being carried out.
Item 26	Professional indemnity Insurance to be taken out by	Clause 9.2	Not less than \$10,000,000 covering the Subcontractor's professional responsibilities to Downer.
	Subcontractor		The insurance must be in force prior to the date of this Subcontract and be maintained for 6 years after expiry of the Defects Liability Period.
Item 27	Work insurance to be taken out by Downer	Clause 9.4(a)	As required by Head Contract
Item 28	Key Personnel	Clause 7.3(d)	Mal Helweh
Item 29	Approvals not being obtained by the Subcontractor	Clause 17.2	
Item 30	Defects Liability Period	Clause 19	 Commencing at 4:00pm on the Date of Practical Completion and continuing until the later of: (i) the date which is 12 months after the date on which Downer notifies the Subcontractor that the Head Contract Works have achieved completion in accordance with the Head Contract.
Item 31	Delay Costs maximum amount per day	Clause 21.6(a)	\$0



Downer Relationships creating success

Subcontract – Long Form

Item 32	Date for submission of	Clause 22.1	Only as follows:
	progress claims		(i) from the commencement of the Work until the earlier of:
			(i) the date on which Downer gives the certificate of Practical Completion pursuant to clause 23.2;
			(ii) the date on which the Subcontract is terminated; and
			(iii) the date on which Work is taken out of the Subcontractor's hands in accordance with clause 27.3,
			once per month, claimable on the 20 th day of each month for Work performed and submit with the following:
			(i) Subcontractor's Statement;
			(ii) Contractor's Certificate of Construction Compliance;
			(iii) COC for Insurances;
			(iv) Aboriginal Participation Plan, Apprentice reporting and all other required report as per the Subcontractor Management Pack for Social Procurement and Sustainability ISCA;
			(v) QA documents; and
			(vi) Any other documents required under the Subcontract;
			(ii) after the date on which Downer gives the certificate of Practical Completion in accordance with clause 23.2:
			(i) once on and from the date of the certificate of Practical Completion; and
			(ii) once in accordance with clause 22.4(a);
			 (iii) A separate Progress Claim and a separate Invoice is to be submitted for each Project separately;
			 (iv) Invoice must be addressed to Downer EDI Works Pty Ltd with Downer's Purchase Order number; and
			(v) Invoice must be submitted to <u>supplier.invoiceonly@</u> <u>downergroup.com</u> , note that Downer accepts only one attachment per email at this email address so if needed then timesheet / dockets / substantiation etc to be attached with the invoice.
Item 33	Unfixed plant and materials for which progress claims may be made	Clause 22.3(a)	
Item 34	Interest rate on overdue payments	Clause 22.5	The rate of interest will be the rate from time to time prescribed for judgement debts under the Uniform Civil Procedure Rules 2005 (NSW). Interest will be compounded at six monthly intervals. This will be the party's sole entitlement to interest, including damages for loss of use of, or the cost of borrowing, money.
Item 35	Percentage amount for profit and overheads	Clause 14.3(a)(ii) Clause 22.7	10%
Item 36	Liquidated damages rate	Clause 23.3	\$5,990.00 per calendar day, capped at 10% Subcontract Sum
Item 37	Authorised nominating authorities	Clause 31.3	Resolution Institute (formerly known as LEADR & IAMA)
Item 38	Address and email for service of notices	Clause 32.1	Downer's details Address: Triniti Business Campus, 39 Delhi Road, North Ryde NSW 2113
			Email: Andrew.Gayed@downergroup.com



		Subcontractor's details	
		Address: 4/88 Violet Street, Revesby, NSW	2212
		Email: mal@maizegroup.com.au	
Secondary Subcontracting	Clause 10.2	Work by Subcontractor's consultants	Work by others
Legal Requirements (i) Those already accepted under the	Clause 11		
Clause 11.1			
Those excepted under the Subcontract	Clause 11.1		
Time for payment	Clause 22.2(d)	20 Business Days after receiving a progress with clause 22.1	s claim made in accordance
Subcontractor's security for unfixed plant and materials	Clause 22.3(a)		
Dispute resolution method	Clause 28.4	The dispute resolution method is: Arbitration	
		Where the dispute resolution method is arb	itration:
		The arbitration will be finally resolved under Arbitration Rules.	the Resolution Institute
		There will be one arbitrator, appointed in ac Resolution Institute Arbitration Rules. The a reasons for their award.	
		The seat of the arbitration will be Sydney , I proceedings (including all hearings) will take	e place in Sydney, NSW .
		The arbitration will be conducted in English.	
Commonwealth Building Code	Schedule 13 and clause 1.5	Does Schedule 13 apply? Yes ⊠ No □	
Limitation of Liability	Clause 9.8	200% of the Subcontract Sum (as adjusted Subcontract).	in accordance with this
	Legal Requirements (i) Those already accepted under the Head Contract Clause 11.1 Those excepted under the Subcontract Time for payment Subcontractor's security for unfixed plant and materials Dispute resolution method Commonwealth Building Code	Legal RequirementsClause 11(i) Those already accepted under the Head Contract Clause 11.1Clause 11Those excepted under the SubcontractClause 11.1Time for paymentClause 22.2(d)Subcontractor's security for unfixed plant and materialsClause 22.3(a)Dispute resolution methodClause 28.4Commonwealth Building CodeSchedule 13 and clause 1.5	Address: 4/88 Violet Street, Revesby, NSW Email: mal@maizegroup.com.au Secondary Subcontracting Clause 10.2 Work by Subcontractor's consultants (i) Those already accepted under the Head Contract Clause 11.1 Those excepted under the Subcontract Clause 11.1 Time for payment Clause 22.2(d) Subcontractor's security for unfixed plant and materials Clause 22.3(a) Dispute resolution method Clause 28.4 The dispute resolution method is: Arbitration The dispute resolution method is: Arbitration Where the dispute resolution method is arb The arbitration will be finally resolved under Arbitration Rules. Commonwealth Building Code Schedule 13 and clause 1.5 Limitation of Liability Clause 9.8



Part B

Provisional Sums

Clause 22.7

Not Applicable



Part C

Special Conditions

<u>SC1</u>

The Subcontractor and its employees are required to utilise the Downer near miss process and hotline for any near misses.

<u>SC2</u>

The Subcontractor understands that Downer is bound by a Framework Agreement for Transport Access Program – Easy Access Station upgrades Managing Contractor Contract (collectively the "Head Contracts") with Transport for New South Wales and that the Head Contracts contain provisions which require the Subcontractor to adhere to. The Subcontractor agrees that where the Head Contracts place an obligation on Downer's Subcontractor/s or for Downer to ensure that its Subcontractors comply with or do something or sign a schedule from the Head Contracts, then where such obligation exists, the Subcontractor must adhere to that obligation within the time period required by the Head Contracts. Where a time period is not stated, the Subcontractor must adhere to such obligation promptly and without delay. A copy of the Head Contracts is available for the review of the Subcontractor upon the Subcontractor's request in writing. Such obligations include (but are not limited to) the below conditions:

<u>SC3</u>

Any Subcontractor who has made an admission to the Independent Commission Against Corruption that it has engaged in; or in respect of whom the Independent Commission Against Corruption has made a finding that it has engaged in, corrupt conduct as defined in the Independent Commission Against Corruption Act 1988 (NSW); or any Subcontractor employing an employee in respect of whom paragraph above apply is a Prohibited Subcontractor and is not permitted to perform the work. Any Subcontractor who becomes a Prohibited Subcontractor may be terminated and in such circumstances will not be entitled to any claim against Downer or the Principal as a result of such termination.

<u>SC4</u>

Not Used

<u>SC5</u>

The Subcontractor must comply with Downer's Management Plan as listed below but not limited to require under the Works brief and TSR

Document Name
Project Contract Management Plan
Work Health and Safety Management Plan
Construction Environmental Management Plan (CEMP)
Construction and Site Management Plan
Quality Management Plan
Risk Management Plan
Community Liaison Management Plan
Heritage Management Plan
Design Management Plan



Value for Money Management Plan
Emergency Management Plan
Testing and Commissioning Management Plan
Subcontractor Management Pack

<u>SC6</u>

The Subcontractor must cooperate and coordinate as directed by Downer with Other Contractor and Interface Contractors. Other Contractor means any contractor, consultant, artist, tradesperson or other person engaged by the Principal or others to do work, other than Downer. Interface Contractors means an Other Contractor Sydney Trains/NSW Trains/NSW Trains subcontractors and as detailed in the Works Brief or otherwise identified by the Principal's Representative as an Interface Contractor that is carrying out, or that will carry out, Interface Work.

<u>SC7</u>

Head Contract Clause 2.2 - Compliance with Law

(g) Without limiting the Subcontractor's obligations under any other clause of this Subcontract, insofar as the Subcontractor, in carrying out the Subcontractor 's Activities, is:

- a person conducting a business or undertaking that designs plant, substances or structures to whom section 22 of the Work Health and Safety Act 2011 (NSW) applies;
- a person conducting a business or undertaking that manufactures plant, substances or structures to whom section 23 of the Work Health and Safety Act 2011 (NSW) applies;
- a person conducting a business or undertaking that imports plant, substances or structures to whom section 24 of the Work Health and Safety Act 2011 (NSW) applies;
- (iv) a person conducting a business or undertaking that supplies
- (v) plant, substances or structures to whom section 25 of the Work Health and Safety Act 2011 (NSW) applies; or
- (vi) a person conducting a business or undertaking that installs, constructs or commissions plant or structures to whom section 26 of the Work Health and Safety Act 2011 (NSW) applies, the Subcontractor must comply with the applicable obligations under the WHS Legislation.

(h) Without limiting the Subcontractor's obligations under any other clause of this Subcontract, the Subcontractor must:

- (i) ensure that, if any Law, including in the State or Territory in which the Works are situated or the Works are carried out (as the case may be), require that:
 - A. a person:

1) be authorised or licensed (in accordance with the WHS Legislation) to carry out any work at that workplace, that person is so authorised or licensed, and complies with



any conditions of such authorisation or licence; and/or

2) has prescribed qualifications or experience or, if not, is to be supervised by a person who has prescribed qualifications or experience (as defined in the WHS Legislation), that person has the required qualifications or experience or is so supervised; or

- B. a workplace, plant or substance (or design), or work (or class of work) be authorised or licensed, that workplace, plant or substance, or work is so authorised or licensed;
- (ii) not direct or allow a person to carry out or use plant or substance at a workplace unless the requirements of clause 2.2(h)(i) are met (including any requirement to be authorised, licensed, qualified or supervised); and
- (iii) if requested by the Downer's Representative, the Principal's Representative or required by the WHS Legislation, produce evidence of any approvals, authorisations, certificates, licences, prescribed qualifications or experience, or any other information relevant to work health and safety (as the case may be) to the satisfaction of the Principal's Representative before the Subcontractor (as the case may be) commences such work.

(j) The parties acknowledge and agree that (i) the Authority Approvals which are in existence as at the date of this Contract include those specified in Exhibit K.

<u>SC8</u>

Head Contract clause 2.4 - Services

Not Used

<u>SC9</u>

Site and Site Access

Refer to Exhibit E - Contract Specific Requirements for information on Site and Site Access. Where the Principal puts an obligation on Downer the same obligation applies to the Subcontractor

<u>SC10</u>

Head Contract Clause 14.5 - Principal's Common Rights After Take-Out or Termination If:

- (a) the Principal:
 - (i) exercises its rights under clause 14.3(a)(i) of the Head Contract; or
 - (ii) terminates the Contract under clauses 14.3(b), 14.4 or 14.9 of the Head Contract;
- (b) Downer repudiates the Contract and the Principal otherwise terminates this Contract; or
- (c) the Contract is frustrated under the Law,



then Downer will novate to the Principal or the Principal's nominee those Subcontracts between Downer and its Subcontractors that the Principal directs. The Subcontractor must participate in any novation required by the Principal.

<u>SC11</u>

The Subcontractor must supervise its workers and any subcontractor's activities and ensure that they are complying with all relevant Law, Authority Approvals and the TfNSW Standard Requirements in relation to the WHS management on the Site and Extra Land.

<u>SC12</u>

Head Contract Clause 4.7 - ASA Compliance

- (a) Without limiting or otherwise restricting clauses 4.7(c) and 4.7(d), if a Project Limited Authorisation has been granted, the Subcontractor must:
 - (i) ensure that the Project Limited Authorisation is held and maintained for so long as the Subcontractor's Activities are carried out;
 - provide to the ASA any document, information or other things reasonably required by the ASA under, out of or in connection with the Project Limited Authorisation within any time period required by the ASA (acting reasonably); and
 - (iii) comply (and must ensure that its subcontractors and all personnel for which the Subcontractor is responsible comply) with the conditions of the applicable Project Limited Authorisation.
- (b) Without limiting or otherwise restricting clauses 4.7(c) and 4.7(d), if the Subcontractor or its subcontractors have ASA Authorisation to carry out the Asset Lifecycle Services or obtain that ASA Authorisation prior to Completion, the Subcontractor must:
 - (i) ensure that ASA Authorisation to carry out the Asset Lifecycle Services is held and maintained for so long as the Subcontractor's Activities are carried out; and
 - (ii) on and from the date that ASA Authorisation was granted, comply (and must ensure that its subcontractors and all personnel for which the Subcontractor is responsible comply) with the conditions of the applicable ASA Authorisation.
- (c) The Contract must (and must ensure that its subcontractors and all personnel for which the Subcontractor is responsible):
 - (i) implement and comply with any ASA Requirements applicable to the Asset Lifecycle Services;
 - (ii) immediately notify the Principal's Representative in writing of any non-compliance with clauses 4.6 and 4.7;
 - (iii) cooperate fully with the ASA in the performance of the ASA's functions;
 - (iv) provide access to premises and resources as reasonably required by the ASA, including so that the ASA can effectively carry out its review, surveillance and audit



functions;

- (v) comply with the directions, instructions and requirements issued by the ASA;
- (vi) notify the ASA of any matter that could reasonably be expected to affect the exercise of the ASA's functions;
- (vii) provide the ASA with any information relating to its activities or any documents or other things reasonably required by the ASA in the exercise of its functions; and
- (viii) provide the Principal with such reasonable assistance as may be reasonably required by the Principal to enable the Principal to cooperate fully with the ASA and to implement and comply with ASA Requirements.
- (d) The Subcontractor acknowledges and agrees that it is not entitled to make (and neither the Principal nor the ASA will be liable upon) any Claim arising out of or in connection with the requirements to obtain, or any delays or failure by the ASA in grating the Subcontractor or its subcontractors, Project Limited Authorisation or ASA Authorisation or the obligation to comply with ASA Requirements with respect to Project Limited Authorisation or ASA Authorisation.

<u>SC13</u>

Head Contract Clause 5.7 - Ownership of Contract Documentation and Methods of Working

Where required by the Principal;

- (i) title to and Intellectual Property in or in relation to the Contract Documentation prepared by the Subcontractor will vest upon its creation for the purposes of this Contract in the Principal;
- to the fullest extent permitted by Law, the Subcontractor hereby assigns to the Principal all of its rights, titles, and interests in, and to, all Intellectual Property in or in relation to the Contract Documentation prepared by the Subcontractor, whenever created; and
- (iii) upon request by the Principal, the Subcontractor must do all things necessary to vest that title or that Intellectual Property in the Principal.

<u>SC14</u>

Head Contract Clause 5.8 - Delivery Up of Contract Documentation

If this Contract is frustrated or terminated the Subcontractor must:

- (a) immediately deliver the original and all sets and copies of all Contract Documentation (whether complete or not), including fully detailed electronic versions in unlocked native format (with all logic links intact and nothing hidden or protected), then in existence to Downer; and
- (b) provide such details, memoranda, explanations, documentation and other assistance as Downer requires in relation to the Contract Documentation.

<u>SC15</u>

If required by the Principal, Downer is required to provide the Principal's Representative with a copy of the executed subcontract agreement including the Works Brief or Design Documentation relevant to this agreement, in signing this Contract the Subcontractor agrees to this.



<u>SC16</u>

The Subcontractor must:

- (i) execute and submit to Downer within 3 days of this Subontract a Confidentiality Undertaking in the form in Appendix 1;
- (ii) ensure that all employees of the Subcontractor that have access to the information described in the Confidentiality Undertaking are aware of their obligations under the terms of the Confidentiality Undertaking; and
- (iii) ensure that each Subcontractor, including suppliers and Consultants, to the Subcontractor execute and submit a Confidentiality Undertaking to Downer.

<u>SC17</u>

Where a Subcontractor is to carry out design work or other professional services, unless not required by the Principal's Representative, the Subcontractor is required to execute a Deed in the form of Appendix 2 and provide this to Downer within 2 days of the signing of this Subcontract. For avoidance of doubt in Appendix 2 the Consultant means the Consultant or the Subcontractor whoever has executed this agreement.

<u>SC18</u>

Head Contract Clause 7.9 - Subcontractor Warranties

The Consultant agrees and acknowledges that Downer and its Subcontractor has an obligation to provide the warranty as described in this special condition and therefore the Consultant shall prepare Design and Design Documentation that comply with the requirements of this clause.

- (a) As a condition precedent to Completion of the Works or a Portion, the Subcontractor must procure and provide the Principal with the warranties described in Exhibit G or elsewhere in this Subcontract or the Contract:
 - (i) from the relevant Subcontractor undertaking or supplying the work or item the subject of the warranty;
 - (ii) in favour of, and directly enforceable by, the Principal and any other entity nominated by the Principal's Representative from time to time against the relevant Subcontractor; and
 - (iii) in a form set out in Appendix 3
 - (b) No warranty from a Subcontractor will be construed in any way to modify or limit any of the rights, powers or remedies of the Principal or Downer against the subcontractor whether under the subcontract or otherwise.
 - (c) If the Subcontractor is unable to or fails for any reason to provide any warranty from its Subcontractor required by this subcontract:
 - (i) the Subcontractor is deemed to have provided the Subcontractor warranty itself on like terms;
 - Downer will be entitled to elect to take an assignment of all the right, title and interest in the Subcontractor's rights against the Subcontractor's Subcontractor in relation to the Subcontractor's Activities; and
 - (iii) for the purpose of clause (c)(ii) of this Special Condition, the Subcontractor irrevocably appoints Downer as its lawful



attorney to execute any instrument necessary to give effect to the assignment.

No assignment under this clause will be construed in any way to modify or limit any of the rights, powers or remedies of against the Subcontractor whether under the subcontract or otherwise

<u>SC19</u>

Head Contract Clause 7.20 - Cleaning Up

In carrying out the work, the Subcontractor must:

- (a) keep the Site, Extra Land and the Works clean and tidy and free of refuse;
- (b) regularly remove rubbish, litter, graffiti and surplus material from the Site and Extra Land; and
- (c) as a condition precedent to Completion of the Works or a Portion, remove all rubbish, surplus materials, Construction Plant and Temporary Works from the Site and Extra Land or the part of the Site or Extra Land relevant to the Works or the Portion.

<u>SC20</u>

Head Contract Clause 7.21 - Safety

a)

- The Subcontractor must ensure that the Subcontractor's Activities are carried out:
 - (i) safely and in a manner that does not put the health and safety of persons at risk; and
 - (ii) in a manner that protects property.
- b) If Downer's Representative reasonably considers there is a risk to the health and safety of people or damage to property arising from the Subcontractor's Activities, Downer's Representative may direct the Subcontractor to change its manner of working or to cease working.
- c) The Subcontractor must:
 - (i) ensure that in carrying out the Subcontractor's Activities:
 - A. it complies with all Law, including the WHS Law, and other requirements of this Contract for work health, safety and rehabilitation management;
 - B. all Subcontractors comply with the requirements referred to in this special condition and their respective obligations under the WHS Legislation; and
 - C. it complies with its obligations under the WHS Legislation to consult, cooperate and coordinate activities with all other persons who have a work health and safety duty in relation to the same matter;
 - (ii) notify Downer's Representative immediately (and in the event within 12 hours of such matter arising) of all work health, safety and rehabilitation matters arising out of, or in any way in connection with, the Subcontractor's Activities, unless



otherwise directed by Downer;

- (iii) institute systems to obtain regular written assurances from all Subcontractors about their ongoing compliance with the WHS Legislation including the due diligence obligation contained therein;
- (iv) provide Downer's Representative with the written assurances obtained pursuant to clause (c)(iii) of this special condition, together with written assurance(s) from the Subcontractor about the Subcontractor's ongoing compliance with the WHS Legislation;
- (v) provide Downer's Representative with a written report at each meeting as directed, on all work health, safety and rehabilitation matters (including matters concerning or arising out of, or in any way in connection with, this special condition, or any other relevant matters as Downer's Representative may require from time to time, including a summary of the Subcontractor's compliance with the WHS Legislation;
- (vi) consult, cooperate and coordinate with all Other Contractors, Principal and Downer to ensure that all parties are able to comply with their respective obligations under the WHS Legislation;
- (vii) exercise a duty of the utmost good faith to Downer in carrying out the Works to enable Downer to discharge Downer's duties under the WHS Legislation;
- (viii) ensure that it does not do anything or fail to do anything that would cause Downer to be in breach of the WHS Legislation; and
- (ix) ensure its subcontracts include provisions equivalent to the obligations of this special condition.
- d) Without limiting clause 17.14 of the Head Contract Downer may take any action necessary to protect or to prevent or minimise risks to, the Works, the Environment, other property or the health or safety of people.
- e) If the action taken by Downer is action which the Subcontractor was required to take under this Contract but did not take, the amount of any penalty, fine, damage, expense, cost (including any reasonable legal fees), loss or liability that Downer suffers or incurs arising out of or in any way in connection with:
 - (i) taking the action contemplated in the clause (d) of this special condition; or
 - (ii) the Subcontractor's failure to take that action,

will, except to the extent prohibited by Law, be a debt due from the Subcontractor to Downer.

<u>SC21</u>

Except for the purpose of achieving Completion, the Subcontractor must not remove from the Site any:

(a) significant materials or major items of Construction Plant; or

(b) materials or Construction Plant specified in any written notice issued by Downer,

without the prior written approval of Downer, which approval will not be unreasonably withheld.



<u>SC22</u>

Head Contract clause 7.24 Rail Safety

- (a) In carrying out any part of the Subcontractor's Activities which require Accreditation as a Rail Infrastructure Manager, the Subcontractor:
 - (i) must comply with all conditions of the Principal's Accreditation as a Rail Infrastructure Manager and the Principal's Safety Management System;
 - (ii) must not do anything that may cause the Principal to breach its obligations under the Rail Safety National Law; and
 - (iii) must ensure that the Subcontractor's Subcontractors engaged in or in connection with the Subcontractor's Activities, comply with clauses (a)(i) and (a)(ii) of this special condition.
 - (b) In carrying out any part of the Subcontractor's Activities which require Accreditation as a Rolling Stock Operator, the Subcontractor must:
 - ensure that the Subcontractor, or one of the Subcontractor's Subcontractors, holds the necessary Accreditation for that part of the Subcontractor's Activities; and
 - (ii) comply with the conditions of that Accreditation.
 - (c) Without limiting or otherwise affecting any other provision under this Subcontract, the Subcontractor must, and must ensure that the Subcontractor's Subcontractors, comply with all obligations under the Rail Safety National Law including entering into interface agreements required by Part 3 of the Rail Safety National Law in respect of any part of the Subcontractor's Activities which require Accreditation as a Rolling Stock Operator.
 - (d) To the extent not prohibited by Law, the Subcontractor must indemnify the Principal and Downer against any damage, expense, loss or liability suffered or incurred by the Principal or Downer arising out of or in any way in connection with the Subcontractor's failure to comply with this special condition.

<u>SC23</u>

Head Contract Clause 9.7 Industrial Relations

- (a) The Subcontractor must in carrying out the Subcontractor's Activities:
 - (i) assume sole responsibility for and manage all aspects of industrial relations for the Subcontractor's Activities;
 - (ii) ensure all Subcontractors manage all aspects of the industrial relations with their employees appropriately;
 - (iii) ensure that the rates of pay and conditions of employment specified in all relevant industrial, enterprise and project based agreements and awards, and any relevant Law, for all



employees engaged in any capacity by any person in connection with the Subcontractor's Activities, are always observed in full;

- (iv) keep the Downer's Representative fully and promptly informed of industrial relations problems or issues that affect or are likely to affect the carrying out of the Subcontractor's Activities and Other Subcontractors' activities;
- (v) comply with all the requirements of the NSW Code and the NSW Guidelines;
- (vi) conduct its industrial relations affairs in accordance with the Workplace Relations Management Plan developed and submitted by the Subcontractor as part of the Contract Management Plan, in accordance with the TfNSW Standard Requirements;
- (vii) prepare, document and implement a project Workplace Relations Management Plan which must be based on the draft outline Industrial Relations Management Plan (if any) submitted with the Subcontractor's Tender;
- (viii) not commence any work on the Site or Extra Land until the Workplace Relations Management Plan has been submitted to the Downer's Representative and Downer's Representative has not rejected it;
- (ix) submit to the Downer's Representative, before beginning work on the Site or Extra Land, a statement detailing:
 - A. the location of time and wage records and other documents that are required to be kept to verify ongoing compliance with all employment and legal obligations;
 - B. the names of each award or enterprise agreement that is likely to cover the Subcontractor and its Subcontractors involved in the Subcontractor's Activities; and
 - C. the names of those responsible for coordinating industrial relations for the Subcontractor's Activities;
- (x) not do, or omit to do, anything that is, or is likely to be, prejudicial to the performance of the Subcontractor's Activities;
- (xi) before beginning work on the Site or Extra Land, submit a statement on the Subcontractor's letterhead and signed by an authorised person, attesting to the Subcontractor's compliance, in the preceding twelve months, with all employment and legal obligations, including:
 - A. payment of remuneration to employees;
 - B. annual leave provisions;
 - C. Long Service Leave Payment Scheme registration;
 - D. obligations to register workers under the Building and Construction Industry Long Service Payments Act



1986 (NSW);

- E. workers' compensation insurance, including self- insurance arrangements;
- F. superannuation fund membership and contributions; and
- G. over-award payments such as redundancy fund contributions; and
- (xii) continue to provide during the Subcontractor's Activities appropriate information to verify compliance with the awards, enterprise and workplace agreements and all other legal obligations relating to the employment of people for the Subcontractor's Activities.
- (b) If the Subcontractor engages an independent industry or employer association or other specialist organisation to audit and verify compliance with employment and legal obligations, a statement or declaration from that organisation may be submitted instead of the statement by the Subcontractor under the clause (a)(ix) of this special condition.
 - (c) The industrial relations requirements contained in this Contract, the NSW Code and the NSW Guidelines:
 - (i) are in addition to, but are not in substitution for, any requirements of Law; and
 - (ii) do not limit the powers of the Principal or the liabilities and responsibilities of the Subcontractor.

<u>SC24</u>

Head Contract clause 9.11 Financial Assessment

the Subcontractor acknowledges and agrees that:

- (a) the Principal may, during the term of the Contract, either itself, or through the engagement of private sector service providers, undertake ongoing financial assessments (Financial Assessment) of the Subcontractors;
- (b) the Financial Assessment may be undertaken at three monthly (or longer) intervals from the date of commencement of the Works; and

it must, if requested by the Principal's Representative or Downer's Representative, within 10 Business Days of receiving such request, provide any documents, information and evidence as is reasonably required by the Principal's Representative under, out of, or in connection with the Financial Assessment.

<u>SC25</u>

The Subcontractor cannot assign, transfer or novate any of its rights or liabilities under this Subcontract without the prior written consent of Downer and except on such terms and conditions as are determined in writing by Downer



<u>SC26</u>

Head Contract Clause 9.16 TfNSW's Statement of Business Ethics

- (a) The Subcontractor must at all times comply with TfNSW's Statement of Business Ethics, a copy of which is available at www.transport.nsw.gov.au.
- (b) The Subcontractor in signing this subcontract acknowledges that it has received, read, understood and will comply with TfNSW's Statement of Business Ethics.
- (c) Prior to the engagement of any subcontractor by the Subcontractor, the Subcontractor must obtain a written acknowledgement from such subcontractor that it has received, read, understood and will comply with TfNSW's Statement of Business Ethics.

<u>SC27</u>

Head Contract Clause 9.17 NSW Code of Practice

NSW Code and NSW Guidelines

In addition to terms defined in this document, terms used in this special condition have the same meaning as is attributed to them in the New South Wales Government's Implementation Guidelines to the NSW Code of Practice for Procurement: Building and Construction (**NSW Guidelines**) (as published by the NSW Treasury July 2013). The NSW Code and NSW Guidelines are available at www.industrialrelations.nsw.gov.au.

- **1.** Primary Obligation
 - (a) The Subcontractor must at all times comply with, and meet any obligations imposed by, the NSW Government's Code of Practice for Procurement (**NSW Code**) and NSW Guidelines.
 - (b) The Subcontractor must notify Downer of any possible non- compliance with the NSW Code and NSW Guidelines and of remedial action taken, within 24 hours of becoming aware of the possible non- compliance.
 - (c) Where the Subcontractor engages a Subcontractor, the Subcontractor must ensure that the Subcontract imposes on the Subcontractor equivalent obligations to those in this special condition, including that the Subcontractor must at all times comply with, and meet any obligations imposed by, the NSW Code and the NSW Guidelines.
 - (d) The Subcontractor must not appoint or engage another party in relation to the Works where that appointment or engagement would breach a sanction imposed on the other party in relation to the NSW Code or NSW Guidelines.
- **2.** Access and information
 - (a) The Subcontractor must maintain adequate records of compliance with the NSW Code and NSW Guidelines by it, its Subcontractors and related entities.
 - (b) The Subcontractor must allow, and take reasonable steps to facilitate, authorised personnel (including personnel of the CCU) to:
 - (i) enter and have access to sites and premises controlled by



the Subcontractor, including but not limited to the Site;

- (ii) inspect any work, material, machinery, appliance, article or facility;
- (iii) access information and documents;
- (iv) inspect and copy any record relevant to the Works;
- (v) have access to personnel; and
- (vi) interview any person,

as is necessary for the authorised personnel to monitor and investigate compliance with the NSW Code and NSW Guidelines, by the Subcontractor, its Subcontractors and related entities.

(c) The Subcontractor, and its related entities, must agree to, and comply with, a request from authorised personnel (including personnel of the CCU) for the production of specified documents by a certain date, whether in person, by post or electronic means.

3. Sanctions

- (a) The Subcontractor warrants that at the time of entering into this Contract, neither it, nor any of its related entities, are subject to a sanction in connection with the NSW Code or NSW Guidelines that would have precluded it from responding to a procurement process for work to which the NSW Code and NSW Guidelines apply.
- (b) If the Subcontractor does not comply with, or fails to meet any obligation imposed by, the NSW Code or NSW Guidelines, a sanction may be imposed against it in connection with the NSW Code or NSW Guidelines.
- (c) Where a sanction is imposed:
 - (i) it is without prejudice to any rights that would otherwise accrue to the parties; and
 - (ii) the State of NSW (through its agencies, Ministers and the CCU) is entitled to:
 - A. record and disclose details of non-compliance with the NSW Code or NSW Guidelines and the sanction; and
 - B. take them into account in the evaluation of future procurement processes and responses that may be submitted by the Subcontractor, or its related entities, in respect of work to which the NSW Code and NSW Guidelines apply.
- 4. Compliance
 - (a) The Subcontractor bears the cost of ensuring its compliance with the NSW Code and NSW Guidelines, including in respect of any positive steps it is obliged to take to meet its obligations under the NSW Guidelines. The Subcontractor is not entitled to make a claim for reimbursement or an extension of time from Downer, the Principal or the State of NSW for such costs.



- (b) Compliance with the NSW Code and NSW Guidelines does not relieve the Subcontractor from responsibility to perform the Subcontractor's Activities and any other obligation under the Subcontract or from liability for any Defect in the Works or from any other legal liability, whether or not arising from its compliance with the NSW Code and NSW Guidelines.
- (c) Where a change in the Contract or the Works is proposed, and that change may, or may be likely to, affect compliance with the NSW Code and NSW Guidelines, the Subcontractor must immediately notify Downer of the change, or likely change and specify:
 - (i) the circumstances of the proposed change;
 - (ii) the extent to which compliance with the NSW Code and NSW Guidelines will be, or is likely to be, affected by the change; and
 - (iii) what steps the Subcontractor proposes to take to mitigate any adverse impact of the change (including any amendments it proposes to a Workplace Relations Management Plan or Project Work Health and Safety Management Plan),

and Downer will direct the Subcontractor as to the course it must adopt within 15 Business Days of receiving notice

<u>SC28</u>

Head Contract clause 13.6 (f) and 13.6(c) Insurance Obligations

When the Subcontractor performs any professional services (including Design Work) forming part of the Contractor's Activities it must:

- A. maintains professional indemnity insurance which:
 - covers the subcontractor's liability in respect of breaches of professional duty (whether owed in contract or otherwise) by the subcontractor or its subcontractors in carrying out the work under the relevant Subcontract;
 - 2) covers the subcontractor for liability to the Principal or Downer for the relevant minimum amount listed below;

as detailed in Schedule 1 of the Head Contract

- 3) unless the subcontractor using its best endeavours is unable reasonably to procure such a term in the policy, includes at least one automatic reinstatement of the total limit of liability per annum after claims have been paid; and
- 4) remains in place at least until the expiration of a 7 year period from completion of the relevant Subcontract works or professional services; and
- B. be obliged under the relevant Subcontract to comply with below in relation to the insurance referred to ensure the professional indemnity insurance: covers claims for breach of professional duty (whether owed in contract or otherwise) by the Subcontractor or its subcontractors in carrying out the Subcontractor's Activities;



- A. does not do anything which prejudices any insurance;
- B. where required, rectifies anything which might prejudice any insurance;
- C. reinstates an insurance policy if it lapses;
- D. does not cancel, vary or allow an insurance policy to lapse without the prior written consent of the Principal's Representative;
- E. immediately notifies the Downer's Representative of any event that may result in an insurance policy lapsing or being cancelled, and replaces that insurance policy prior to it lapsing or being cancelled; and
- F. gives full, true and particular information to the insurer of all matters and things the non-disclosure of which might in any way prejudice or affect any such policy or the payment of all or any benefits under the insurance.

<u>SC29</u>

Head Contract clause 13.9 - Notice of Potential Claim

The Subcontractor must

(a) as soon as possible inform Downer in writing of any occurrence that may give rise to a claim under an insurance policy required by this Subcontract (except for the professional indemnity insurance policy);
 (b) keep the Downer informed of subsequent developments concerning the claim; and

ensure that its Subcontractors similarly inform their Subcontractor and Downer in respect of occurrences that may give rise to a claim

<u>SC30</u>

Head Contract clause 17.22 - Proportionate Liability

To the extent permitted by law, the Contract and this Subcontract excludes the Subcontractor from the application of Part 4 of the Civil Liability Act 2002 (NSW) in relation to all and any rights, obligations or liabilities of either party under or in any way in connection with each Subcontract whether such rights, obligations or liabilities are sought to be enforced by a claim in contract, tort or otherwise; and

The Subcontractor must include, in any further contract that it enters into with a third party for the carrying out of the work under this Subcontract, a term that (to the extent permitted by law) excludes the application of Part 4 of the Civil Liability Act 2002 (NSW) in relation to all and any rights, obligations or liabilities of either party under or in any way in connection with each further agreement whether such rights, obligations or liabilities are sought to be enforced by a claim in contract, tort or otherwise.

<u>SC31</u>

The Subcontractor must sign the Subcontractors Statement in the form of Appendix 4 along with any Payment Claim and when requested by Downer.



<u>SC32</u>

The Subcontractor and the Consultant must sign and provide to Downer the Form of Subcontractor Deed in the form of Appendix 5 upon execution of this Subcontract or Consultancy Agreement. For avoidance of doubt in Appendix 5 the Subcontractor means the Consultant or the Subcontractor whoever has executed this agreement.

<u>SC33</u>

The Subcontractor must sign and provide to Downer the Contractor's Certificate of Construction Compliance in the form of Appendix 6 monthly with the Subcontractor's Progress Claim, and when otherwise requested by Downer

<u>SC34</u>

The Subcontractor must sign and provide to Downer the Contractor's Certificate of Completion in the form of Appendix 7 upon Completion of the Works / Portion.

<u>SC35</u>

The Subcontractor must comply with Downer's Subcontractor Management Pack- refer to Attachment of the RFT.

<u>SC36</u>

The Subcontractor warrants that it has checked and conformed to the Design Documents, any changes required in Design Documents due to Subcontractor's negligence or error or any other reason will need to be approved by the Consultant/Designer engaged by Downer under the Head Contract. Downer will recover any costs incurred by the Consultant/Designer for changing Design Documents from the Subcontractor by using the rates provided in Appendix 8. The Subcontractor acknowledges and agrees that it will not make any claim against Downer and Downer is not liable to pay the Subcontractor such costs. For the clearance of doubt the changes in design includes as-built.

Design Documents means all design documentation including design standards, concrete mix designs, design reports, durability reports, construction descriptions, the drawings, shop drawings, digital records, business rules, system processes, computer software, specifications and other information, samples, models, prototypes, calculations, patterns, all other relevant data in electronic, computer readable and written or physical forms and the like required by the Subcontract and created (and including, where the context so requires, those to be created by the Subcontractor) for the construction of the Work and includes the Principal Design

<u>SC37</u>

The Subcontractor must execute Subcontractor Deed Poll in form of Appendix 9 and submit to Downer within 7 days of the date of the Subcontract.

<u>SC38</u>

The Subcontractor must comply with TfNSW Standard Requirement – refer to Attachment of the RFT.

<u>SC39</u>

The Subcontractor is responsible for Temporary Works and Temporary Works design. Temporary Works means any temporary works required to be carried out or provided by the Subcontractor for the purpose of the execution of the Subcontractor's Activities but not forming part of the Works.

<u>SC40</u>

The Subcontractor must comply with Sustainability Guideline Shortlist – refer to Attachment of the RFT



<u>SC41</u>

If required by Downer then employees and staff of the Subcontractor must undertake safety profiling by Downer's nominated supplier (Davidsons). The profiling is for psychometric assessment for the purpose of health and safety and will be required at Downer's discretion. Downer will arrange and pay for such assessments.

<u>SC42</u>

Clause 9.12 of the Head Contract - Employment of Aboriginal and Torres Strait Islander People

The Subcontractor must:

- (a) comply with the requirements of the NSW Government Policy on Aboriginal Participation in Construction (May 2015) Category 2;
- (b) within 35 days of the execution of this Contract, provide to the Principal an Aboriginal Participation Plan in accordance with the NSW Government Policy on Aboriginal Participation in Construction (May 2015) Category 2; and
- (c) provide, to the Principal, an Aboriginal Participation Re (c) port every 3 months in accordance with the format detailed in the NSW Government Policy on Aboriginal Participation in Construction (May 2015).

<u>SC43</u>

Clause 9.15 of the Head Contract - Training Management

- (a) Subject to the express provisions of the Head Contract, the Subcontractor must comply with the NSW Procurement Board direction PBD-2016-02 Construction Apprenticeships (PB-2016-02).
- (b) Training management requirements specified in the Head Contract and compliance with PBD-2016-02 may be in addition to, but are not in substitution for, any training obligations of the Subcontractor under statute, industrial award, enterprise or workplace agreement, or other workplace arrangements approved under Federal or NSW law.
- (c) at least 10 days before starting work on the Site, the Subcontractor must document and submit a Project Training Management Plan which complies with the PBD-2016-02.
- (d) The Subcontractor must systematically manage its training management processes in accordance with the systems plans, standards and codes specified in the Head Contract.
- (e) The Subcontractor must demonstrate to the Downer's Representative, wherever requested, that it has met and is meeting at all times its obligations under the clause 9.14 of Head Contract
- (f) The Subcontractor:
 - (i) Acknowledges that the target for the engagement of apprentices and trainees engaged by the Subcontractor to perform the Subcontractor's Activities is 20% (Training Target);
 - (ii) Must make reasonable endeavours to achieve the Training Target;
 - (iii) Provide written reports to the Downer's Representative quarterly, in a format set out below, and at such other times as may be requested by Downer's Representative, detailing the number of apprentices and trainees engaged by the Subcontractor in the Subcontractor's Activities against the Training Target; and



(iv) Provide Downer's Representative with all other assistance and information it requires in relation to the Subcontractor's performance against the Training Target in order for the Downer to comply with its reporting obligations at Law, including promptly making all relevant records available to the Downer's Representative after any written request by the Downer's Representative.

Report on training of apprentices and trainees

Requirement	Minimum targets (in terms of time worked)	Quantity achieved by Subcontractor for reporting period
Apprentice hours as a percentage of hours worked by qualified trades	20% of hours worked	[insert]%
Trainee hours as a percentage of hours worked by occupations with recognised traineeships:	20% of hours worked	[insert]%

<u>SC44</u>

Clause 9.15 of the Head Contract - National Greenhouse and Energy Reporting Act 2007 (Cth)

The Subcontractor acknowledges and agrees that:

- (a) if any of the Subcontractor's Activities, or the activities of any of the Subcontractor's personnel, in connection with the Subcontractor's Activities (the "Relevant Matters") constitute a "facility" within the meaning of the NGER Legislation, then, for the purposes of the NGER Legislation, the Subcontractor has operational control of that facility and will comply with any obligations arising in respect of the Downer's activities under the NGER Legislation;
- (b) if, despite the operation of clause (a) of this special condition, the Downer or Principal incurs, or (but for this clause) would incur, a liability under or in connection with the NGER Legislation as a result of or in connection with any of the Relevant Matters, and the NGER Legislation provides that such liability can be transferred by Downer, the Principal or the NSW Government or any of its agencies to the Subcontractor, the Subcontractor must, on the written request of Downer, do all things reasonably necessary to ensure the liability is transferred to the Subcontractor;
- (c) if Downer requests it, the Subcontractor must provide Greenhouse Data to Downer:
 - (i) to the extent that, in a manner and form that, and at times that, will enable Downer to comply with the NGER Legislation irrespective of whether the Principal or the Subcontractor or any other person has an obligation to comply with the NGER Legislation in connection with any Relevant Matters; and
 - (ii) otherwise as requested by Downer from time to time;



- (d) the Subcontractor must also provide to Downer all Greenhouse Data and other information which the Subcontractor provides to any other person under the NGER Legislation in connection with any Relevant Matters, at the same time as the Subcontractor provides that Greenhouse Data or other information to that other person;
- (e) the Subcontractor must:
 - (i) collect and record all such Greenhouse Data as may be required to enable reporting under the NGER Legislation or enable the Subcontractor to discharge its obligations under this special condition, and keep that Greenhouse Data for at least 7 years after the end of the year in which the Relevant Matters occur; and
 - (ii) permit any persons appointed or authorised by the Principal to examine, monitor, measure, copy, audit and/or verify the Greenhouse Data and co-operate with and provide all reasonable assistance to any such persons (including by doing such things as giving access to premises, plant and equipment, producing and giving access to documents and answering any relevant questions);
- (f) Downer may provide or otherwise disclose the Greenhouse Data and any other information which the Principal obtains under this special condition to any other person, and may otherwise use the Greenhouse Data and other information for any purpose as the Principal sees fit; and
- (g) nothing in this special condition is to be taken as meaning that the Principal or Downer has agreed to perform any statutory obligation that the Subcontractor may have regarding the provision of Greenhouse Data to any Authority.

<u>SC45</u>

If no time or other information provided regarding submission of program/schedule then the Subcontractor must submit program including all its Subcontract's Activities as directed by Downer's Representative.

<u>SC46</u>

Teambinder is the authorized document management system for the Project. The Subcontractor will be given user access (for a smsoall number of nominated personnel) to the Project on Downer Teambinder system for sending and receipt of contract correspondence and documentation. Notices, contract correspondence and documentation will not be acknowledged if sent via Microsoft Outlook or other electronic mail based system

<u>SC47</u>

For avoidance of the doubt the Contractor means Downer where it refers to the Contractor in this Special Conditions.

<u>SC48</u>

Design and Design Documentation - Head Contract clause 5

Not Used

<u>SC49</u>

If the Subcontractor's activities / Works include any work involving asbestos or asbestos decontamination, including stripping, encapsulation or removal, the Subcontractor or its specialist asbestos removal Subcontractor must before the Subcontractor commences, effect and have in place the asbestos liability insurance for \$20,000,000 for any one occurrence and in the aggregate, with insurers of the Required Rating and on terms satisfactory to Downer.



Appendix 1 – Form of Confidentiality Undertaking

(Clauses 1.1 and 17.11(c)(i) of Head Contract)

To: Downer EDI Works Pty Ltd

We <u>Maize Group</u> the engaged Subcontractor body, undertake to treat as confidential all information received/generated from Transport for NSW (ABN 18 804 239 602) (Principal) in respect of work performed by the Principal.

The Consultant/Supplier/Contractor/Subcontractor hereby undertakes:

- (a) To disclose information to its employees only on a need-to-know basis;
- (b) Not to disclose information to any other person without first obtaining the written consent of the Principal;
- (c) To ensure that its employees to whom information is disclosed will comply with (a) and (b) above.

This undertaking will not apply to information about the Principal which is in the public domain (except where the availability of the information in the public domain is due to any unauthorised disclosure by the Consultant/Supplier/Contractor/Subcontractor, its employees or agents) or which was already known to the Consultant/Supplier/Contractor/Subcontractor.

Any breach of this undertaking by the Consultant/Supplier/Contractor/Subcontractor's employee or agent will constitute a breach of this undertaking by the Consultant/Supplier/Contractor/Subcontractor and at the direction of the Principal the Consultant/Supplier/Contractor/Subcontractor must institute proceedings or do whatever the Principal regards as reasonable to prevent or contain the breach.

The Consultant/Supplier/Contractor/Subcontractor undertakes that on request from the Principal it will forthwith return to the Principal all originals and copies of the confidential information, however embodied, supplied by the Principal and destroy all documents containing or prepared using any confidential information however embodied.

The Consultant/Supplier/Contractor/Subcontractor also undertakes to declare to the Principal any conflict of interests that exists or arises during the course of its engagement which may impinge on the objectivity or probity of the work performed. Such declarations are to be made as soon as the conflict of interests issues arises.

This undertaking will remain in force until each part of the confidential information is released by the Principal into the public domain.

Dated:12/11/2020	
SIGNED for and on behalf of: Maize Group	
(Print Company Name)	
By: Mal Helweh (Print Name)	(Signature)
in the presence of:Adam Ibrahim	
(Print Name)	(Signature)



Appendix 2 – Consultant Deed of Covenant

(Clause 7	7.7(a)(iv) of Head Contract)		
This dee	d poll is made the	day of	20
То:	Transport for NSW (ABN 18 804 239 602) of Level 5, Tower A, Zenith Centre, 821 Pacif Highway, CHATSWOOD NSW 2067 (the "Principal")		
By:	[]	("Consultant")	
Recitals			
A.	The Principal has engaged [works for the Principal by a contrac	ot dated [] ("Contractor") to carry out certain] ("Contract").
В.	The Contractor has engaged the Consultant by agreement dated [("Subcontract") to carry out the professional services to be performed under Subcontract ("Professional Services") for the purposes of the performance of Contractor's obligations under the Contract as they relate those design services.		

C. Under the Contract, the Contractor is required to procure the Consultant to execute this deed poll in favour of the Principal.

Operative

1. Duty of Care

- (a) The Consultant:
 - (i) warrants to the Principal that:
 - A. in performing the Professional Services, it will exercise the standard of skill, care and diligence that would be expected of a consultant experienced in and expert in the provision of the type of professional services required by the Principal;
 - B. the Professional Services will be fit for the intended purposes disclosed in or reasonably able to be inferred from the Works Brief, which is an annexure to the Contract; and
 - C. the Professional Services do not and will not infringe any patent, registered design, trademark or name, copyright or other protected right;
 - (ii) acknowledges that:
 - A. in performing the Professional Services it will owe a duty of care to the Principal; and
 - B. it is aware that the Principal will be relying upon the skill and judgment of the Consultant in performing the Professional Services and the warranties given by the Consultant in this deed poll; and
 - (iii) must act in good faith and in the best interests of the Principal and promptly advise the Principal about any matter in which the Consultant has been instructed by the Contractor to provide the Professional Services in a manner which is, or may result in an outcome which is, not in accordance with the requirements of the Contract, including without



limitation:

- A. where the Contractor's instructions in relation to design are not consistent with the Contract or may result in the Works not being fit for their intended purpose; or
- B. where the Contractor's instructions require the Consultant to issue a certificate where the conditions for the issue of that certificate under the Contract have not been satisfied.
- (b) The Consultant must:
 - (i) fully cooperate with each other consultant and contractor engaged by the Principal ("Other Contractor");
 - (ii) carefully coordinate and integrate the Professional Services with the services and work carried out by each Other Contractor;
 - (iii) carry out the Professional Services so as to minimise any interfering with, disrupting or delaying, the services and work carried out by each Other Contractor;
 - (iv) without limitation, provide whatever advice, support and cooperation is reasonable to facilitate the due carrying out of the services and work being provided by each Other Contractor;
 - (v) ensure title to and intellectual property (including any patent, registered design, trademark or name, copyright or other protected right) in or in relation to the Professional Services will vest upon its creation for the purposes of the Contract in the Principal;
 - (vi) obtain an assignment to the Principal from any third party who owns any intellectual property right in the Professional Services;
 - (vii) if any intellectual property rights in or in relation to documents, designs and computer programs created for the purposes of the Contract is not capable of being vested in the Principal because the Consultant itself does not own, and is unable at a reasonable cost to obtain ownership of, those rights, provide to the Principal an irrevocable licence to use that Intellectual Property, by sub-licence from the Consultant or direct licence from a third party; and
 - (viii) ensure that the intellectual property created for the purposes of the Contract is not used, adapted or reproduced other than for the purposes of the Contract without the prior written approval of the Principal (which will not be unreasonably withheld, but may be given subject to terms and conditions).
- (c) The Consultant must indemnify the Principal from and against:
 - (i) any liability to or claim by any other person; and

(ii) all claims against, and costs, expenses, losses and damages, suffered or incurred by the Principal arising out of, or in any way in connection with:

- (iii) the Consultant's breach of a term of, or warranty under, this deed poll; or
- (iv) any actual or alleged infringement of any patent, registered design, trademark or name, copyright or other protected right.



2. Notices

(a) Any notices contemplated by, or arising out of or in any way in connection with, this deed poll must be in writing and delivered to the relevant address or sent to the facsimile number shown below (or to a party's new address or facsimile number which that party notifies to the others):

(i)	to the Principal:	c/o Level 5, Tower A
		Zenith Centre
		821 Pacific Highway
		CHATSWOOD NSW 2067
		Fax: (02) 9200 0290

- (ii) to the Consultant: [Insert details]
- (b) A notice sent by post will be taken to have been received at the time when, in due course of the post, it would have been delivered at the address to which it is sent.
- (c) A notice sent by facsimile will be taken to have been received on the next day after the day shown on the transmission slip showing the facsimile number of the party to whom it is addressed in accordance with clause 2.1, which is not a Saturday, Sunday or public holiday in New South Wales.
 - (d) If the Consultant is a foreign company (as defined in the *Corporations Act*), the Consultant must within 14 days of the date of this deed poll:
 - appoint a local process agent acceptable to the Principal as its agent to accept service of process under or in any way in connection with this deed poll; and
 - (ii) obtain the process agent's consent to the appointment. The appointment must be in a form acceptable to the Principal and may not be revoked without the Principal's consent.

3. Miscellaneous

- (a) This deed poll will be construed in accordance with the law of the State of New South Wales and the Consultant irrevocably submits to the jurisdiction of the Courts of that State.
- (b) This deed poll may not be revoked or otherwise modified without the prior written consent of the Principal.



...... [] by or in

Schedule	Sc	hed	u	le
----------	----	-----	---	----

)

[INSERT DESCRIPTION OF PROFESSIONAL SERVICES] as more particularly described in the Subcontract.

Executed as a deed poll.

Signed Sealed and Delivered

by the Consultant)

the presence of:) (Signature)

(Signature of Witness)

(Name of Witness in Full)



Appendix 3 – Form of Warranty

(Clause 7.9 of the Head Contract)

This Deed Poll is made the

day of

20

To: Transport Construction for NSW (ABN 18 804 239 602) of Level 5, Tower A, Zenith Centre, 821 Pacific Highway, CHATSWOOD NSW 2067 ("Principal")

[Add other beneficiaries as nominated by TfNSW] ("Beneficiary").

By: That person described in Item 1 of the Schedule ("Warrantor") which expression will include its successors and assigns)

Recitals

- A. The Warrantor has supplied the items described in Item 2 of the Schedule (**"Equipment"**) to the person described in **Item** 3 of the Schedule (**"Contractor"**) or the person described in Item 4 of the Schedule, a subcontractor of the Contractor (**"Subcontractor"**), for the works (**"Works"**) being carried out by the Contractor under the contract described in Item 5 of the Schedule (**"Contract"**) with the Principal.
- B. It is a requirement of the Contract that the Contractor procure the Warrantor to give the following warranties in favour of the Principal and the Beneficiary with respect to the Equipment.

Operative

1. Quality

The Warrantor:

- (a) warrants to the Principal and the Beneficiary that the Equipment will be to the quality and standard stipulated by the Contract and will be of merchantable quality and fit for the purpose for which it is required; and
- (b) gives the warranty more particularly set out in Item 6 of the Schedule with respect to the Equipment.

The above warranties are in addition to and do not derogate from any warranty implied by law in respect of the Equipment.

2. Replacement

The Warrantor warrants to the Principal and the Beneficiary that it will replace so much of the Equipment as within the period described in Item 7 of the Schedule:

- (a) is found to be of a lower quality or standard than that referred to in clause 1; or
- (b) shows deterioration of such extent that in the opinion of the Principal or the Beneficiary the Equipment ought to be made good or replaced in order to achieve fitness for the purpose for which it is required, whether on account of utility, performance, appearance or otherwise.

3. Warrantor to bear cost

The Warrantor covenants to the Principal and the Beneficiary that it will bear the cost of any work necessary to any part of the Works to enable the requirements of clause 2 to be carried out or to make good the Works afterwards.



4. Principal not liable

The Warrantor acknowledges to the Principal and the Beneficiary that nothing contained in this deed poll is intended to nor will render either the Principal or the Beneficiary in any way liable to the Warrantor in relation to any matters arising out of the Contract or otherwise.

5. This deed poll may not be revoked

This deed poll may not be revoked or otherwise modified without the prior written consent of the Principal and the Beneficiary.

6. Governing Law

This deed poll is governed by the laws of the State of New South Wales.

7. Jurisdiction

The Warrantor irrevocably submits to the non-exclusive jurisdiction of the Courts of New South Wales.

8. Enforcement of this deed poll

For the avoidance of doubt this deed poll is enforceable by any of the Principal or the Beneficiary.



Schedule

Item 1:	Name and Address of Warrantor
Item 2:	Equipment
Item 3:	(Recital A) Contractor (Recital A)
Item 4:	Subcontractor (Recital A)
Item 5:	Contract (Recital A)
Item 6: Clause 1(b))	Detailed Warranty of Warrantor

Item 7: Period of Years (Clause 2) [insert period] years from the expiry of the last "Defects Rectification Period" as defined in the General Conditions (including any extension under clause 8.6 of the General Conditions).

Executed as a deed poll.

Executed by [insert name of Warrantor] (ABN [insert ABN]) by or in the presence of:

Signature of Director

Signature of Secretary/other Director

Name of Director in full

Name of Secretary/other Director in full



Appendix 4 – Subcontractor's Statement

REGARDING WORKERS COMPENSATION, PAYROLL TAX AND REMUNERATION (Note 1 - see back of form)

For the purposes of this Statement a "subcontractor" is a person (or other legal entity) that has entered into a contract with a "principal contractor" to carry out work.

This Statement must be signed by a "subcontractor" (or by a person who is authorised, or held out as being authorised, to sign the statement by the subcontractor) referred to in any of s175B *Workers Compensation Act 1987*, Schedule 2 Part 5 *Payroll Tax Act 2007*, and s127 *Industrial Relations Act 1996* where the "subcontractor" has employed or engaged workers or subcontractors during the period of the contract to which the form applies under the relevant Act(s). The signed Statement is to be submitted to the relevant principal contractor.

SUBCONTRACTOR'S STATEMENT (Refer to the back of this form for Notes, period of Statement retention, and Offences under various Acts.

Subcontractor:	ABN:		
	(Business name)		
of			
	(Address of subcontractor)		
has entered into a contract with		ABN:	
	(Business name of principal contractor)		
	((Note 2)	
Contract number/identifier		(Note 3)	
This Statement applies for work	between:// and/	/ inclusive, (Note 4) subject	
of the payment claim dated:	// (Note 5)		

I, a Director or a person authorised by the Subcontractor on whose behalf this declaration is made, hereby declare that I am in a position to know the truth of the matters which are contained in this Subcontractor's Statement and declare the following to the best of my knowledge and belief:

- (a) The abovementioned Subcontractor has either employed or engaged workers or subcontractors during the above period of this contract. Tick [] if true and comply with (b) to (g) below, as applicable. If it is not the case that workers or subcontractors are involved or you are an exempt employer for workers compensation purposes tick [] and only complete (f) and (g) below. You must tick one box. (Note 6)
- (b) All workers compensation insurance premiums payable by the Subcontractor in respect of the work done under the contract have been paid. The Certificate of Currency for that insurance is attached and is dated/.....(Note 7)
- (c) All remuneration payable to relevant employees for work under the contract for the above period has been paid. (Note 8)
- (d) Where the Subcontractor is required to be registered as an employer under the *Payroll Tax Act 2007*, the Subcontractor has paid all payroll tax due in respect of employees who performed work under the contract, as required at the date of this Subcontractor's Statement. (Note 9)
- (e) Where the Subcontractor is also a principal contractor in connection with the work, the Subcontractor has in its capacity of principal contractor been given a written Subcontractor's Statement by its subcontractor(s) in connection with that work for the period stated above. (Note 10)



(f)	Signature	Full Name	
(g)	Position/Title		Date//

NOTE: Where required above, this Statement must be accompanied by the relevant Certificate of Currency to comply with section 175B of the Workers Compensation Act 1987.

Notes

- 1. This form is prepared for the purpose of section 175B of the *Workers Compensation Act 1987*, Schedule 2 Part 5 *Payroll Tax Act 2007* and section 127 of the *Industrial Relation Act 1996*. If this form is completed in accordance with these provisions, a principal contractor is relieved of liability for workers compensation premiums, payroll tax and remuneration payable by the subcontractor. A principal contractor can be generally defined to include any person who has entered into a contract for the carrying out of work by another person (or other legal entity called *the subcontractor*) and where employees of the subcontractor are engaged in carrying out the work which is in connection with the principal contractor's business.
- 2. For the purpose of this Subcontractor's Statement, a principal contractor is a person (or other legal entity), who has entered into a contract with another person (or other legal entity) referred to as the subcontractor, and employees/workers of that subcontractor will perform the work under contract. The work must be connected to the business undertaking of the principal contractor.
- 3. Provide the unique contract number, title, or other information that identifies the contract.
- 4. In order to meet the requirements of s127 *Industrial Relations Act 1996*, a statement in relation to remuneration must state the period to which the statement relates. For sequential Statements ensure that the dates provide continuous coverage.

Section 127(6) of the Industrial Relations Act 1996 defines remuneration 'as remuneration or other amounts payable to relevant employees by legislation, or under an industrial instrument, in connection with work done by the employees.'

Section 127(11) of the Industrial Relations Act 1996 states 'to avoid doubt, this section extends to a principal contractor who is the owner or occupier of a building for the carrying out of work in connection with the building so long as the building is owned or occupied by the principal contractor in connection with a business undertaking of the principal contractor.'

- 5. Provide the date of the most recent payment claim.
- 6. For Workers Compensation purposes an exempt employer is an employer who pays less than \$7500 annually, who does not employ an apprentice or trainee and is not a member of a group.
- 7. In completing the Subcontractor's Statement, a subcontractor declares that workers compensation insurance premiums payable up to and including the date(s) on the Statement have been paid, and all premiums owing during the term of the contract will be paid.
- 8. In completing the Subcontractor's Statement, a subcontractor declares that all remuneration payable to relevant employees for work under the contract has been paid.
- 9. In completing the Subcontractor's Statement, a subcontractor declares that all payroll tax payable relating to the work undertaken has been paid.
- 10. It is important to note that a business could be both a subcontractor and a principal contractor, if a business 'in turn' engages subcontractors to carry out the work. If your business engages a subcontractor you are to also obtain Subcontractor's Statements from your subcontractors.



Statement Retention

The principal contractor receiving a Subcontractor's Statement must keep a copy of the Statement for the periods stated in the respective legislation. This is currently up to seven years.

Offences in respect of a false Statement

In terms of s127(8) of the *Industrial Relations Act 1996*, a person who gives the principal contractor a written statement knowing it to be false is guilty of an offence if:

- (a) the person is the subcontractor;
- (b) the person is authorised by the subcontractor to give the statement on behalf of the subcontractor; or
- (c) the person holds out or represents that the person is authorised by the subcontractor to give the statement on behalf of the subcontractor.

In terms of s175B of the Workers Compensation Act and clause 18 of Schedule 2 of the Payroll Tax Act 2007 a person who gives the principal contractor a written statement knowing it to be false is guilty of an offence.

Further Information

For more information, visit the WorkCover website <u>www.workcover.nsw.gov.au</u>, Office of State Revenue website <u>www.osr.nsw.gov.au</u>, or Office of Industrial Relations, Department of Commerce website <u>www.commerce.nsw.gov.au</u>. Copies of the *Workers Compensation Act 1987, the Payroll Tax Act 2007* and the *Industrial Relations Act 1996* can be found at www.legislation.nsw.gov.au.



Appendix 5 – Form of Subcontractor Deed

(Clause 7.7(a)(v)of the Head Contract)

THIS DEED POLL is made on12th November, 20 20.... by Maize Group (ACN 169 460 379) of 4/88 Violet Street, Revesby, NSW 2212 (the "Subcontractor").

RECITALS:

- A. Transport for NSW (ABN 18 804 239 602) of Level 5, Tower A, Zenith Centre, 821 Pacific Highway, CHATSWOOD NSW 2067 (the "Principal") has entered into a contract with [] ("Contractor") for the construction of [] ("Works").
- B. The Subcontractor has an agreement (the **"Subcontract"**) with the Contractor for the execution and completion of the Building Works (the **"Subcontract Works"**) for the Works.
- C. It is a condition of the Subcontract that the Subcontractor executes this Deed Poll.

THIS DEED WITNESSES THAT THE SUBCONTRACTOR HEREBY COVENANTS, WARRANTS AND AGREES with and for the benefit of the persons named in the Schedule as follows:

- 1. It will comply with its obligations under the Subcontract and upon completion of the Works, the Subcontract Works will satisfy the requirements of the Subcontract.
- 2. The persons named in the Schedule may assign or charge the benefits and rights accrued under this Deed Poll.
- 3. The Subcontractor:
 - (a) must if required by a written notice by the Principal to sign a deed in the form of the attached Deed of Novation (Attachment 1) with such substitute contractor as the Principal may nominate; and
 - (b) for this purpose irrevocably appoints the Principal to be its attorney with full power and authority to complete the particulars in and sign the attached Deed of Novation.
- 4. This Deed Poll is governed by the laws of the State of New South Wales.
- 5. This Deed Poll may not be revoked or otherwise modified without the prior written consent of the Principal.
- 6. The Subcontractor's liability in respect of a breach of a particular obligation under this Deed Poll will be reduced to the extent to which the Subcontractor has already paid money to or performed work for the Contractor in respect of that breach.

PERSONS NAMED IN THE SCHEDULE TO THE DEED POLL

Transport for NSW (ABN 18 804 239 602)

[Insert relevant details e.g. Sydney Trains/NSW Trains]



EXECUTED AS A DEED POLL.

Executed by Maize Group (ACN 169 460 379) by or in the presence of:



Signature of Director

Mal Helweh

Name of Director in full

Signature of Secretary/other Director

Name of Secretary/other Director infull



Attachment 1 (to Appendix 5)

THIS DEED OF NOVATION is made on [parties:

] 20 [] between the following

- 1. [] ("Substitute Contractor")
- 2. [] ("Original Contractor")
- 3. [] ("Subcontractor").

RECITALS:

- A. By deed dated [] (the "Deed") between:
 - (i) **Transport for NSW (ABN 18 804 239 602)** of Level 5, Tower A, Zenith Centre, 821 Pacific Highway, CHATSWOOD NSW 2067 (the **"Principal"**); and
 - (ii) Original Contractor,

the Principal engaged the Original Contractor to undertake the Works (as defined in the Deed).

- B. The Original Contractor has entered into an agreement (**"Subcontract"**) with the Subcontractor for the execution and completion of the [] (**"Subcontract Works"**) as part of the Works.
- C. The Principal has terminated the Deed and has engaged Substitute Contractor to complete the Works.

D. The Principal and Substitute Contractor wish to effect a novation of the Subcontract. **THIS DEED WITNESSES** that in consideration, among other things, of the mutual promises contained in this deed, the parties agree:

- 1. Substitute Contractor must perform all of the obligations of the Original Contractor under the Subcontract which are not performed at the date of this deed. Substitute Contractor is bound by the Subcontract as if it had originally been named in the Subcontract in place of Original Contractor.
- 2. The Subcontractor must perform its obligations under, and be bound by, the Subcontract as if Substitute Contractor was originally named in the Subcontract in place of Original Contractor.
- 3. This deed is governed by the laws of New South Wales and the parties agree to submit to the non-exclusive jurisdiction of the courts of that state.

EXECUTED by the parties as a deed: [Insert appropriate execution clauses]



Appendix 6 – Contractor's Certificate of Construction Compliance

(Clauses 7.16(c) and 11.6(c)(ii) of the Head Contract)

CONTRACTOR'S CERTIFICATE OF CONSTRUCTION COMPLIANCE			
CONTRACTOR:			
WORK PACKAGE	DESCRIPTION		
(Attach schedule of	work packages if insufficient space)		
been completed to the extent indicated abo between the Principal and Downer EDI Wor	f the work packages or part thereof described above have ve in accordance with the requirements of the Contract ks Pty Ltd, and comply with the requirements of the ing minor construction non conformance and unresolved		
I further certify that the attached compliance of the work packages.	e records as required by the Contract reflect the true status		
NAME:	SIGNATURE: DATE: / /		
(Contractor's Representative)			
THIS SECTION MUST BE COMPLETED B SUBCONTRACTOR/DESIGNER	Y THE RELEVANT CONTRACTOR'S		
part thereof described above have been co the requirements of the Contract between the	f the work packages (one certificate per work package) or mpleted to the extent indicated above in accordance with ne Principal and Downer EDI Works Pty Ltd, and comply ect to the register of outstanding minor construction ttached.		
I further certify that the attached compliance of the work packages.	e records as required by the Contract reflect the true status		
NAME:			
SIGNATURE:	DATE:		
(Contractor's Subcontractor/			



Appendix 7 – Contractor's Certificate of Completion

(Definition of "Completion" in Clause 1.1 and Clause 12.3(c) of the Head Contract)

	CONTRACTOR'S CERTIFICATE OF COMPLETION
CON	ITRACTOR: Downer EDI Works Pty Ltd
Des	cription of Portion or Works:
acco Pty I	tify that the Completion of the above Portion/the Works has/have been achieved in ordance with the requirements of the Contract between the Principal and Downer EDI Works _td, complies with the requirements of the Contract, subject to the register of unresolved es attached.
l furt	her certify that:
(a)	All Variation Orders (including concessions) are listed in the attached compliance register.
(b)	All identified Defects (including any non-conformities but excluding Defects accepted as minor by the Principal) have been satisfactorily rectified and their documentation closed out.
(c)	All required documentation has been submitted.
(d)	All notices regarding system deficiencies have been satisfactorily closed out.
	her certify that the attached compliance records as required by the Contract reflect the true us of the Portion/the Works.
SICI	NATURE: SIGNATURE:
	(Contractor's Representative) (Contractor's Subcontractor/Designer)

Appendix 8 – Schedule of Rates for Design Fee

If rates are not inserted here then Downer to provide



Appendix 9 – Form of Subcontractor Deed Poll

(Clause 1.5 of Head Contract)

This deed poll ("Deed Poll") made the 12th day of November 2020

By: Maize Group (ACN 169 460 379) of 4/88 Violet Street, Revesby, NSW 2212 ("Subcontractor"),

in favour of: Downer EDI Works Pty Ltd (ABN 66 008 709 608) of Triniti Business Campus, 39 Delhi Road, North Ryde. NSW. 2113 ("Contractor").

RECITALS

A. Transport for NSW (**"TfNSW"**) of Level 5, Tower A Zenith Centre, 821 Pacific Highway, CHATSWOOD NSW 2067, is responsible for developing [Insert] (**"Program"**).

B. As part of the Program TfNSW is responsible for procuring the execution and completion of certain works for the [insert details of project] (the **"Works"**) on behalf of the Owner and the New South Wales Government, and has entered into a contract (**"Main Contract"**) with the Contractor to achieve this.

C. TfNSW is relying on Contractor to procure the Subcontractor to execute and complete the Works in accordance with the Main Contract.

D. The TfNSW will suffer loss if the Contractor does not procure the Subcontractor to execute and complete the Works in accordance with the Main Contract.

E. It is a condition of the Main Contract and this Subcontract that the Subcontractor executes this Deed Poll.

THIS DEED POLL WITNESSES THAT THE SUBCONTRACTOR HEREBY COVENANTS, WARRANTS AND AGREES with and for the benefit of the Contractor and TfNSW as follows:

- 1. It will comply with its obligations under the Subcontract, including with respect to achieving Completion of each Portion and the Works by the relevant Date for Completion.
- 2. Upon Completion of the Works, the Works will satisfy the requirements of the Main Contract.
- 3. In consideration of the Contractor making available to the Subcontractor Track Possessions the Subcontractor agrees that it must indemnify the Contractor against all costs, expenses, losses or damages suffered or incurred by the Contractor in respect of any delay to rail services or late return of Track Possessions arising out of or in connection with the Subcontractor's Activities.

The maximum liability which the Subcontractor will have to the Contractor pursuant to this clause for each event resulting in delay to rail services or for late return of a Track Possession will be determined on the basis of the maximum period by which any train was delayed by the event or late return of a Track Possession calculated by applying the following rates:


Period in which delay occurs	Rate per hour or part thereof
During peak hours	\$30,000
During all other hours	\$15,000

4. The aggregate of the Subcontractor's liability to the Contractor under this Deed Poll

(a) will not exceed the liability which the Subcontractor would have had under the Subcontract; and

(b) is subject to the same limitations of liability, and qualifications on such limitations of liability, as are specified in the Main Contract.





- 5. Any provision of this Deed Poll which seeks to limit or exclude a liability of the Subcontractor is to be construed as doing so only to the extent permitted by law.
- 6. The Contractor may assign or charge the benefits and rights accrued under this Deed Poll.
- 7. This Deed Poll is governed by the laws of the State of New South Wales.
- 8. This Deed Poll may not be revoked or otherwise modified without the prior written consent of the Contractor.
- 9. Where terms used in this Deed Poll are defined in the Main Contract, those terms have the meaning given to them in the Main Contract.

Executed as a deed poll.

Executed by **Maize Group ACN 169 460 379** by or in the presence of:



Signature of Director

Signature of Secretary/other Director

Mal Helweh

Name of Director in full

Name of Secretary/other Director in full



Appendix 10 – Final Subcontractor Handover Checklist

Project: Precincts and Infrastructure - TAP3-MC1	-T3&4	
Sub-Contractor: Maize Group		
Station: Wollstonecraft Station		
Date:		
THIS FORM IS TO BE COMPLETED BY THE DOWNER STATION PROJECT MANA		
DOCUMENT	CHECKED BY	Comments
Appendix A - WAE Drawing Register – By Downer		
Appendix B - WAE Drawings – By Downer		
Appendix C - Shop Drawings		
Appendix D - Asset Register		
Appendix E - Compliance Certificates		
Appendix F - Subcontractor O&M Manuals		
Appendix G - Cleaning Procedures		
Appendix H - Product Data Sheets		
Appendix I - Warranty Certificates (Warranties Schedule – Exhibit G)		
Appendix J - Red Line Mark-up		
Schedule 19 - Contractor's Certificate of Construction Compliance (Clauses 7.16(c) and 11.6(c)(ii))		
Schedule 21 - Contractor's Certificate of Completion		
(Definition of "Completion" in Clause 1.1 and Clause 12.3(c))		
Schedule 22 - Contractor's Certificate of Final Completion (Clause 12.8(d))		
DSS Submitted and closed out		
All relevant NCRs are Closed out		
Defects Identified		



(Attach Latest Defect Register)				
Quality Lots are clos	ed out			
Products NATA Tes	t Results provided			
ITPs &ITRs are clos	ed out			
Survey Data Provide	ed			
Calibration record P	rovided			
	COMPLETED &	& VERIFIED	BY	
Name	Company	position	Signature	Date
(Sub-Contractor)		Project Manager		
	Downer Group	Project Manager		



Exhibit G – LIST OF WARRANTIES REQUIRED FROM SUBCONTRACTORS

EXHIBIT G of the Head Contract

Item	Warranty Period	Scope of Warranty
Structural works		
Structural concrete columns,	25 years	Structural Integrity
floors, concrete shafts, walls		
and similar structural concrete		
items		
Roof Structural Elements	25 years	Structural Integrity
Structural Steel - all elements	25 years	Structural Integrity
Masonry - load and non lead	25 years	Structural Integrity
bearing columns, walls, shafts		
and similar masonry elements	•	
Architectural and Building we		
Ceilings/soffit linings including	Manufacturer's standard warranty	General integrity including agains
support structure - all types	period	corrosion, perforation and
		delamination of finish
Mombranes / Tenking /	Liquid mombranes 10 years	Porformanco of waterproofing
Membranes / Tanking / Waterproofing	Liquid membranes 10 years Sheet membranes 15 years	Performance of waterproofing function
waterproofing	Torch on membranes 15 years	Turrenom
Architectural grade steelwork	10 years	General integrity including agains
including screens, framing	To years	corrosion, perforation and
systems, custom balustrades,		delamination of finish
handrails, and fabricated		
metalwork such as access		
walkways		
Profiled metal roofing	25 years	General integrity including agains
including flashings, gutters	,	corrosion, perforation of the base
and downpipes		material and delamination of finis
External louvres	20 years	General integrity including agains
		corrosion, perforation and
		delamination of finish
Glazed roof	10 years	Structural integrity, transparency
		and water tightness
Dry wall/plasterboard and	Manufacturer's standard warranty	Manufacturer's standard
fibre cement linings	period	warranties apply
Resilient materials (including	Manufacturer's standard warranty	Manufacturer's standard
vinyl finishes other than	period	warranties apply
flooring)	-	
Non-fire rated doors and	5 years	Structural integrity
hardware	5	Otwart and list a smith
Fire rated doors, frames and	5 years	Structural integrity
hardware	2 1/22/22	Conorol integrity
Door seals	2 years	General integrity
Joinery and carpentry	2 years Manufacturor's standard warranty	Structural integrity
Custom wall systems,	Manufacturer's standard warranty	Structural integrity and colour fastness
cladding and panelling	period minimum 2 years Manufacturer's standard warranty	Manufacturer's standard
Floor and wall tiling including	period	
grouting and fixing materials	•	warranties apply
Timber flooring Aluminium window frames	2 years	Structural integrity
	10 years	General integrity including agains corrosion, perforation and
		delamination of finish




Item	Warranty Period	Scope of Warranty
Timber window frames	10 years	General integrity
Window glazing	10 years	Structural integrity and transparency
Curtain walls - including framing system, glazed and metal panels, louvers excluding seals and sealants forming	15 years	Structural and general integrity including against corrosion, perforation and delamination of finish.
the wall - seals and sealants	10 years	Structural integrity
Anti throw screens, sun screens and canopies	15 years	Structural and general integrity including against corrosion, perforation and delamination of finish
Carpet and vinyl flooring	7 years	Bonding, colour fastness, wear resistance
Civil works		
Paving, concrete and clay pavers	Manufacturer's standard warranty period	Manufacturer's standard warranties apply
External tiling to walkways including grouting and fixing materials	Manufacturer's standard warranty period	Manufacturer's standard warranties apply
Mechanical		
Mechanical ventilation plant and equipment	5 years	Against failure of non consumable elements
Air conditioning plant and equipment	5 years	Against failure of non consumable elements
Electrical		
Uninterrupted power supply including batteries	10 years subject to manufacturer's conditions	Manufacturer's standard warranties apply
Electrical equipment and	10 years subject to manufacturer's	Manufacturer's standard
fittings including light fittings Electrical and data cables	conditions 10 years subject to manufacturer's conditions	warranties apply Manufacturer's standard warranties apply
Hydraulic		
Sanitary fittings	5 years subject to manufacturer's conditions	Manufacturer's standard warranties apply
Tapware	5 years subject to manufacturer's conditions	Manufacturer's standard warranties apply
Hot water unit	5 years subject to manufacturer's conditions	Manufacturer's standard warranties apply
Fire protection		
Fire extinguishers	5 years	Against corrosion
Smoke and heat detectors	5 years subject to manufacturer's conditions	Manufacturer's standard warranties apply
Services and systems		
Building systems and services	Manufacturer's standard warranty period	Manufacturer's standard warranties apply
Fall arrest system	20 years	Against corrosion
Surface Finishes		
Interior paint finish	10 years	Adhesion, film integrity and colour retention
Exterior paint finishes including painting to structural steel and clear sealer/anti- graffiti coating	10 years	Adhesion, film integrity and coloui retention



Item Steel coatings other than paintwork including powder coating	Warranty Period 10 years subject to manufacturer's conditions	Scope of Warranty Manufacturer's standard warranties apply
Hot dip galvanising	20 years	Structural integrity





Schedule 1– Scope of Works, Drawings, Specifications and Pricing Schedule

A Scope of Work, Drawings and Specifications (refer to RFT)

- Attachment 1 Scope of Works
- Attachment 2 Program & Delivery Schedule / Stage Diagram
- Attachment 3 Specifications / Drawings
- Attachment 5 Subcontractor Management Pack
- Attachment 6 Geotechnical Factual Report
- Attachment 7 Hazardous Materials Register Report
- Attachment 8 not used
- Attachment 9 not used
- Attachment 10 DSS
- Attachment 12 Exhibit B TfNSW Works Brief
- Attachment 13 Exhibit E TfNSW Contract Specific Requirements
- Attachment 14 Not used
- Attachment 15 TfNSW Standard Requirements (Works Contracts)
- Attachment 16 TfNSW Standard Requirements (QMS)
- Attachment 17 TfNSW PMO Procurement Standard Requirement

B Pricing Schedule and Schedule of Rates (refer to RFT Pricing Schedule)

Pricing Schedule – Lump Sum

Item No.			Descriptions	Amount
5		3.1.22.2	East Entry	
	1204	3.1.22.2.1	Temporary hoarding screen at street level	45,360.00
4		3.3.3	Tanking & Waterproofing	
5		3.3.3.1	Lift Pit 1 (Platform 1)	
	2002	3.3.3.1.1	Tanking to lift pit base & walls with Voltex DS Sodium Bentonite blanket 4.8kg/m2 incl. HDPE liner protection - external	5,650.00
	2002	3.3.3.1.2	Extra Over to seal & terminate at ground anchors	433.00
	2002	3.3.3.1.3	Tanking to lift pit base & walls with paint on tanking - internal	908.00
5		3.3.3.2	Lift Pit 2 (Platform 2)	
	2002	3.3.3.2.1	Tanking to lift pit base & walls with Voltex DS Sodium Bentonite blanket 4.8kg/m2 incl. HDPE liner protection - external	3,420.00
	2002	3.3.3.2.2	Extra Over to seal & terminate at ground anchors	433.00
	2002	3.3.3.2.3	Tanking to lift pit base & walls with paint on tanking - internal	908.00
С		3.3.5.1.8	Others	
	2002	3.3.5.1.8.5	Supply and Install TGSI at Telopea Street	3,441.00
	2002	3.3.5.2.8.2	Supply and Install Bollards at Shirley Road	3,632.00
4		3.6.13	Scaffolding	



	Item No.		Descriptions	Amount
5		3.6.13.1	Lift 1- Railway Street	
	2401	3.6.13.1.1	Scaffolds to lift core - external	24,008.00
5		3.6.13.2	Lift 2- Platform 2/3	
	2401	3.6.13.2.1	Scaffolds to lift core & upper landing - external	25,605.00
4		3.8.2	Roofing & Metal Claddings	
5		3.8.2.1	Lift 1 (Platform 1)	
6		3.8.2.1.1	Lift shaft roof	
	4101	3.8.2.1.1.1	Colourbond Klip Lok metal roof to lift shaft roof including insulation on wire mesh	2,026.00
	4101	3.8.2.1.1.2	Colourbond roof capping	1,799.00
С		3.8.2.1.1.1	Rainwater Goods	
	4101	3.8.2.1.1.1.1	Stainless steel 316 half round eaves gutter	675.00
	4101	3.8.2.1.1.1.2	Gutter guard	382.00
	4101	3.8.2.1.1.1.3	Stainless steel 316 downpipe to new roof	1,857.00
С		3.8.2.1.1.2	Roof Access & Anchorage System	
	4101	3.8.2.1.1.2.1	Roof Access & Anchorage System	1,464.00
С		3.8.2.1.1.3	Temporary Roof Safety Barrier System	
	4101	3.8.2.1.1.3.1	Temporary roof safety barrier system	Included
5		3.8.2.2	Lift Canopy Awning Roof	
	4101	3.8.2.2.1	Colourbond Klip Lok metal roof to lift canopy awning including wire mesh	5,066.00
	4101	3.8.2.2.2	Colourbond roof capping	4,112.00
	4101	3.8.2.2.3	Colourbond flashing at lift shaft/roof	892.00
с		3.8.2.2.1	Rainwater Goods	
	4101	3.8.2.2.1.1	Stainless steel 316 box gutter	1,689.00
	4101	3.8.2.2.1.2	Gutter guard	956.00
	4101	3.8.2.2.1.3	Stainless steel 316 downpipe	2,533.00
С		3.8.2.2.2	Roof Access & Anchorage System	
	4101	3.8.2.2.2.1	Roof Access & Anchorage System	1,464.00
с		3.8.2.2.3	Soffit Lining	
	4101	3.8.2.2.3.1	Colourbond metal cladding to soffit	4,397.00
	4101	3.8.2.2.3.2	Colourbond edge trim	1,869.00
5		3.8.2.3	Lift 2 (Platform 2)	
6		3.8.2.3.1	Lift shaft roof	
	4101	3.8.2.3.1.1	Colourbond Klip Lok metal roof to lift shaft roof including insulation on wire mesh	2,026.00
	4101	3.8.2.3.1.2	Colourbond roof capping	1,799.00
C		3.8.2.3.1.1	Rainwater Goods	
	4101	3.8.2.3.1.1.1	Stainless steel 316 half round eaves gutter	675.00



ltem No.		em No.	Descriptions	Amount
	4101	3.8.2.3.1.1.2	Gutter guard	382.00
	4101	3.8.2.3.1.1.3	Stainless steel 316 downpipe to new roof	1,857.00
С		3.8.2.3.1.2	Roof Access & Anchorage System	
	4101	3.8.2.3.1.2.1	Roof Access & Anchorage System	1,464.00
С		3.8.2.3.1.3	Temporary Roof Safety Barrier System	
	4101	3.8.2.3.1.3.1	Temporary roof safety barrier system	Included
6		3.8.2.3.2	Lift Canopy Awning Roof	
	4101	3.8.2.3.2.1	Colourbond Klip Lok metal roof to lift canopy awning including wire mesh	5,066.00
	4101	3.8.2.3.2.2	Colourbond roof capping	4,112.00
	4101	3.8.2.3.2.3	Colourbond flashing at lift shaft/roof	892.00
С		3.8.2.3.2.1	Rainwater Goods	
	4101	3.8.2.3.2.1.1	Stainless steel 316 box gutter	4,301.00
	4101	3.8.2.3.2.1.2	Gutter guard	956.00
	4101	3.8.2.3.2.1.3	Stainless steel 316 downpipe	2,533.00
С		3.8.2.3.2.2	Roof Access & Anchorage System	
	4101	3.8.2.3.2.2.1	Roof Access & Anchorage System	1,464.00
С		3.8.2.3.2.3	Soffit Lining	
	4101	3.8.2.3.2.3.1	Colourbond metal cladding to soffit	4,397.00
	4101	3.8.2.3.2.3.2	Colourbond edge trim	1,869.00
5		3.8.2.4	BAZ Canopy - Platform 1 (1 No.)	
6		3.8.2.4.1	BAZ Canopy Roof	
	4101	3.8.2.4.1.1	Colourbond Klip Lok metal roof to canopy including wire mesh	4,728.00
	4101	3.8.2.4.1.2	Colourbond roof capping	2,827.00
с		3.8.2.4.1.1	Rainwater Goods	
	4101	3.8.2.4.1.1.2	Stainless steel 316 box gutter	2,581.00
	4101	3.8.2.4.1.1.3	Gutter guard	573.00
	4101	3.8.2.4.1.1.4	Stainless steel 316 downpipe	1,013.00
С		3.8.2.4.1.2	Roof Access & Anchorage System	
	4101	3.8.2.4.1.2.1	Roof Access & Anchorage System	1,767.00
C		3.8.2.4.1.3	Soffit Lining	
	4101	3.8.2.4.1.3.1	Colourbond metal cladding to canopy	4,104.00
	4101	3.8.2.4.1.3.2	Colourbond edge trim	2,082.00
5		3.8.2.5	BAZ Canopy - Platform 2 (1 No.)	
6		3.8.2.5.1	BAZ Canopy Roof incl. link to Lift 2	
	4101	3.8.2.5.1.1	Colourbond Klip Lok metal roof to canopy including wire mesh	7,430.00
	4101	3.8.2.5.1.2	Colourbond roof capping	5,140.00



item No.		Item No. Descriptions		Amount	
с	3.8.2.5.1.1 R		Rainwater Goods		
	4101	3.8.2.5.1.1.1	Stainless steel 316 half round eaves gutter	844.00	
	4101	3.8.2.5.1.1.2	Stainless steel 316 box gutter	3,441.00	
	4101	3.8.2.5.1.1.3	Gutter guard	1,243.00	
	4101	3.8.2.5.1.1.4	Stainless steel 316 downpipe	1,520.00	
С		3.8.2.5.1.2	Roof Access & Anchorage System		
	4101	3.8.2.5.1.2.1	Roof Access & Anchorage System	2,093.00	
С		3.8.2.5.1.3	Soffit Lining		
	4101	3.8.2.5.1.3.1	Colourbond metal cladding to canopy	6,448.00	
	4101	3.8.2.5.1.3.2	Colourbond edge trim	2,804.00	
6		3.9.2.1.7	Fencing		
	3456	3.9.2.1.7.1	Remove existing fencing for platform raising works	6,628.00	
	3456	3.9.2.1.7.2	Fencing to match existing loop type	46,215.00	
6		3.9.2.1.8	Coping Edge Paint		
	5028	3.9.2.1.8.1	Prepare surface, apply white paint to existing concrete coping	5,193.00	
	5028	3.9.2.1.8.2	Painted signage & car markings to coping	2,230.00	
	5028	3.9.2.1.8.3	Temporary yellow line - materials for tape	1,385.00	
6		3.9.2.1.9	BAZ canopy platform 1 - platform width to be extended by 1250mm		
	2002	3.9.2.1.9.2	Additional fence to suit width	4,894.00	
6		3.9.2.2.7	Fencing		
	3456	3.9.2.2.7.1	Remove existing fencing for platform raising works	7,131.00	
	3456	3.9.2.2.7.2	Fencing to match existing loop type	49,725.00	
6		3.9.2.2.8	Coping Edge Paint		
	5028	3.9.2.2.8.1	Prepare surface, apply white paint to existing concrete coping	5,193.00	
	5028	3.9.2.2.8.2	Painted signage & car markings to coping	2,230.00	
	5028	3.9.2.2.8.3	Temporary yellow line - materials for tape	1,385.00	
3		3.11	Building		
4		3.11.1	Masonry		
5		3.11.1.3	Platform 2 Brick Retaining Wall		
	9302	3.11.1.3.1	Brick low height retaining wall (say 230mm wide) build off the platform raising slab to prevent falling off small debris from battered slope	Included	
4		3.11.2	Glazing		
5		3.11.2.1	Lift 1 (Pacific Highway)		
с		3.11.2.1.1	Lift Shaft		
	9302	3.11.2.1.1.1	Glass cladding to lift shaft, Viridian Supergreen, or equal and approved, laminated safety glass, laminated with 1.5mm PVB interlayer, high security film to glass, HDG & painted steel angle support frame, stainless	64,606.00	



	lte	m No.	Descriptions	Amount
			steel fixings	
5		3.11.2.2	Lift 2 (Platform 1/2)	
C		3.11.2.2.1	Lift Shaft	
	9302	3.11.2.2.1.1	Glass cladding to lift shaft, Viridian Supergreen, or equal and approved, laminated safety glass, laminated with 1.5mm PVB interlayer, high security film to glass, HDG & painted steel angle support frame, stainless steel fixings	70,887.00
5		3.11.2.3	Platform Canopy Windbreaks	
4		3.11.3	Station Furniture	
5		3.11.3.1	Platform 1	
	9302	3.11.3.1.1	Bench seat incl. footings - allow to reuse existing seat fixture	9,462.00
	9302	3.11.3.1.2	Bench seat incl. footings - BAZ canopy	4,036.00
	9302	3.11.3.1.3	Double bin incl. slab base	11,470.00
	9302	3.11.3.1.4	Boarding Assistance Zone - allow to relocate boarding ramp with support frame, line markings on platform	850.00
5		3.11.3.2	Platform 2	
	9302	3.11.3.2.1	Bench seat incl. footings - allow to reuse existing seat fixture	6,308.00
	9302	3.11.3.2.2	Bench seat incl. footings - BAZ canopy	4,036.00
	9302	3.11.3.2.3	Double bin incl. slab base	11,470.00
	9302	3.11.3.2.4	Boarding Assistance Zone - allow to relocate boarding ramp with support frame, line markings on platform	850.00
4		3.11.4	Street Furniture incl. Bicycle Racks/Shelters	
5		3.11.4.1	Shirley Road (Platform 1)	
	9302	3.11.4.1.1	Relocate mail zone	7,392.00
	9302	3.11.4.1.2	Bike shelter	2,336.00
	9302	3.11.4.1.3	Relocate existing bike racks	1,274.00
	9302	3.11.4.1.4	Bollard	2,655.00
5		3.11.4.2	Telopea Street (Platform 2)	
	9302	3.11.4.2.2	Bench seat to kiss and ride	5,947.00
	9302	3.11.4.2.4	Bike racks	2,591.00
	9302	3.11.4.2.5	Bollard	2,655.00
4		3.11.5	Existing Platform Building Alterations, Additions & Refurbishment	
5		3.11.5.1	Platform Building Works	
6		3.11.5.1.1	Platform 1 - lower waiting room & new amenities	
C		3.11.5.1.1.1	Asbestos & Hazardous Material Removal	
	9302	3.11.5.1.1.1.1	Hazardous Materials Register dated 17/04/2019 notes that the platform 1 building contains asbestos ceilings & eaves, asbestos toilet cubicles - allow to remove where works are required	34,515.00



Item No.			Descriptions	Amount
С		3.11.5.1.1.2	Demolition	
	9302	3.11.5.1.1.2.1	Temporary propping of remaining external walls (where to be underpinned) & where external wall to be demolished, make good on completion	4,089.00
	9302	3.11.5.1.1.2.2	Strip out doors, walls, finishes, fixtures, etc., remove walls, form openings as required	38,044.00
	9302	3.11.5.1.1.2.3	Sawcut slab from inside face of external walls, remove slab, redundant in-ground services	Included
	9302	3.11.5.1.1.2.4	Hydraulic Services: cap off & temporary disconnect for demolition works	3,823.00
С		3.11.5.1.1.3	Excavation	
	9302	3.11.5.1.1.3.1	Excavate to new formation RL + perimeter beams for underpinning, likely rock	26,125.00
С		3.11.5.1.1.5	Concrete	
	9302	3.11.5.1.1.5.1	Underpinning of existing loadbearing edge beam - allow dowel 2 rows @ 150mm cts	37,860.00
	9302	3.11.5.1.1.5.2	Prepare subgrade, blinding, WPM	1,816.00
	9302	3.11.5.1.1.5.3	32MPa concrete in slab on ground with beams for underpinning to existing	21,920.00
	9302	3.11.5.1.1.5.4	Isolation joint	531.00
	9302	3.11.5.1.1.5.5	Surface finish	303.00
С		3.11.5.1.1.6	Formwork	
	9302	3.11.5.1.1.6.1	Formwork slab edge	4,843.00
С		3.11.5.1.1.7	Reinforcement	
	9302	3.11.5.1.1.7.1	Reinforcement to slab & beams	16,057.00
С		3.11.5.1.1.8	Existing Walls	
	9302	3.11.5.1.1.8.1	Make good existing external face of brickwork external walls where platform level is changed, to match existing walls above	4,894.00
	9302	3.11.5.1.1.8.2	Make good existing internal face of brick walls where FFL is lowered	6,975.00
	9302	3.11.5.1.1.8.3	Adjust threshold step to door at change in floor level	897.00
C		3.11.5.1.1.9	New External Wall	
	9302	3.11.5.1.1.9.1	Cavity brick external wall in face brickwork	30,836.00
C		3.11.5.1.1.10	Stud Frames	
	9302	3.11.5.1.1.10.1	Stud frame internal walls	6,117.00
C		3.11.5.1.1.11	Insulations	
	9302	3.11.5.1.1.11.1	Wall insulation	1,223.00
С		3.11.5.1.1.13	Walls	
	9302	3.11.5.1.1.13.1	Fibre cement wall linings to framed walls	11,470.00
	9302	3.11.5.1.1.13.2	Reline existing internal walls for new finish - allow fibre cement or cement render	11,215.00
С		3.11.5.1.1.14	Ceilings	



	lte	em No.	Descriptions	Amount
	9302	3.11.5.1.1.14.1	Suspended plasterboard ceiling with cornice/trims	13,859.00
	9302	3.11.5.1.1.14.2	Ceiling manhole (assume proprietary)	956.00
С		3.11.5.1.1.15	Eaves	
	9302	3.11.5.1.1.15.1	Fibre ecemt eaves to replace asbestos linings removed - to the extent of the waiting room & amenities works	3,441.00
С		3.11.5.1.1.16	Doors	
	9302	3.11.5.1.1.16.1	Single leaf external door with frame, door leaf, hardware	8,581.00
С		3.11.5.1.1.18	Waterproofing	
	9302	3.11.5.1.1.18.1	Waterproofing to wet area floors, upturn 1500mm above floor	7,901.00
С		3.11.5.1.1.19	Tiling	
-	9302	3.11.5.1.1.19.1	Wall tiling to wet areas with epoxy grout	34,409.00
	9302	3.11.5.1.1.19.2	Floor tiling to wet areas with epoxy grout	9,112.00
	9302	3.11.5.1.1.19.3	Coved skirting tiling to wet areas - Glennon Tiles to match floor tiles with epoxy grout	8,363.00
	9302	3.11.5.1.1.19.4	Floor tiling to waiting area with epoxy grout	9,112.00
	9302	3.11.5.1.1.19.5	Skirting tiling to waiting area with epoxy grout	1,593.00
	9302	3.11.5.1.1.19.6	Threshold tile	4,269.00
С		3.11.5.1.1.21	FAT	
	9302	3.11.5.1.1.21.1	Hand dryer - Dyson Airblades V Code AB12 white	1,699.00
	9302	3.11.5.1.1.21.2	Toilet Roll Holder - Bobrick B2890	319.00
	9302	3.11.5.1.1.21.3	SS grabrails to FAT WC	1,062.00
	9302	3.11.5.1.1.21.4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480	159.00
	9302	3.11.5.1.1.21.5	Baby Change Table - Metlam Foldable - Code ML8100H	1,646.00
	9302	3.11.5.1.1.21.6	Coat hook - SSS Metlam ML4159	80.00
	9302	3.11.5.1.1.21.7	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 600W	903.00
	9302	3.11.5.1.1.21.8	Sanitary bin - Canon Hygeine SS Modesty tray	637.00
	9302	3.11.5.1.1.21.9	Nappy disposal bin - Canon Hygeine nappy disposal bin	637.00
с		3.11.5.1.1.22	Ambulant WC - female	
	9302	3.11.5.1.1.22.1	Hand dryer - Dyson Airblades V Code AB12 white	1,699.00
	9302	3.11.5.1.1.22.2	Toilet Roll Holder - Bobrick B2890	319.00
	9302	3.11.5.1.1.22.3	SS grabrails to staff ambulant WC	1,062.00
	9302	3.11.5.1.1.22.4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480	159.00
	9302	3.11.5.1.1.22.5	Coat hook - SSS Metlam ML4159	80.00
	9302	3.11.5.1.1.22.6	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 600W	903.00



Item No.			Descriptions	Amount
с		3.11.5.1.1.23	Ambulant WC - male	
	9302	3.11.5.1.1.23.1	Hand dryer - Dyson Airblades V Code AB12 white	1,699.00
	9302	3.11.5.1.1.23.2	Toilet Roll Holder - Bobrick B2890	319.00
	9302	3.11.5.1.1.23.3	SS grabrails to staff ambulant WC	1,062.00
	9302	3.11.5.1.1.23.4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480	159.00
	9302	3.11.5.1.1.23.5	Coat hook - SSS Metlam ML4159	80.00
	9302	3.11.5.1.1.23.6	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 600W	903.00
С		3.11.5.1.1.24	Cleaners Room	
	9302	3.11.5.1.1.24.1	Cleaners storage closet - Bradley Australia 9983 SS surface mounted utility shelf	850.00
С		3.11.5.1.1.25	Waiting Room	
	9302	3.11.5.1.1.25.1	Bench seat	10,340.00
С		3.11.5.1.1.26	Painting	
С		3.11.5.1.1.28	Apply paint system to:-	
	9302	3.11.5.1.1.28.2	Internal ceiling linings	2,477.00
	9302	3.11.5.1.1.28.3	External eaves linings	841.00
	9302	3.11.5.1.1.28.4	Single leaf external grade doorset	1,189.00
C		3.11.5.1.1.29	Apply anti-graffiti coating equal to Sure Seal Graffiti Shield to (apply to internal public accessible room only):-	
	9302	3.11.5.1.1.29.1	Waiting room facebrick walls	3,360.00
	9302	3.11.5.1.1.29.2	Wall tiling to wet areas	8,641.00
	9302	3.11.5.1.1.29.3	Door leaf	1,020.00
с		3.11.5.1.1.30	Signage	
	9302	3.11.5.1.1.30.1	Door signage as required (per door)	935.00
6		3.11.5.1.2	Platform 1 - new MSB room	
	9302	3.11.5.1.2.1	Remove asphalt	1,540.00
	9302	3.11.5.1.2.2	Excavate for formation RL incl. ground beams	4,354.00
	9302	3.11.5.1.2.3	Slab with edge beams	16,567.00
	9302	3.11.5.1.2.4	External walls, 2hr FRL	25,522.00
	9302	3.11.5.1.2.5	Roof with frame, claddings, gutters & DP's	10,467.00
	9302	3.11.5.1.2.6	Single leaf fire door	4,093.00
	9302	3.11.5.1.2.7	Vinyl floor	2,379.00
	9302	3.11.5.1.2.8	Coved skirting	1,402.00
	9302	3.11.5.1.2.9	2 hr FRL ceiling	4,375.00
	9302	3.11.5.1.2.10	Paint	1,784.00
	9302	3.11.5.1.2.11	Door signage	234.00
6		3.11.5.1.3	Platform 2 - lower waiting room	



	lte	m No.	Descriptions	Amount
С		3.11.5.1.3.2	Demolition	
	9302	3.11.5.1.3.2.1	Temporary propping of remaining external walls (where to be underpinned) & where external wall to be demolished, make good on completion	3,027.00
	9302	3.11.5.1.3.2.2	Strip out finishes, fixtures, etc.	7,219.00
	9302	3.11.5.1.3.2.3	Sawcut slab from inside face of external walls, remove slab	Included
с		3.11.5.1.3.3	Excavation	
	9302	3.11.5.1.3.3.1	Excavate to new formation RL + perimeter beams for underpinning, likely rock	7,620.00
С		3.11.5.1.3.4	Concrete Slab incl. underpining of existing ground beams	
C		3.11.5.1.3.5	Concrete	
	9302	3.11.5.1.3.5.1	Underpinning of existing loadbearing edge beam - allow dowel 2 rows @ 150mm cts	13,434.00
	9302	3.11.5.1.3.5.2	Prepare subgrade, blinding, WPM	414.00
	9302	3.11.5.1.3.5.3	32MPa concrete in slab on ground with beams for underpinning to existing	6,393.00
	9302	3.11.5.1.3.5.4	Isolation joint	531.00
	9302	3.11.5.1.3.5.5	Surface finish	69.00
С		3.11.5.1.3.6	Formwork	
	9302	3.11.5.1.3.6.1	Formwork slab edge	1,274.00
С		3.11.5.1.3.7	Reinforcement	
	9302	3.11.5.1.3.7.1	Reinforcement to slab & beams	5,735.00
С		3.11.5.1.3.8	Existing Walls	
	9302	3.11.5.1.3.8.1	Make good existing external face of brickwork external walls where platform level is changed, to match existing walls above	918.00
	9302	3.11.5.1.3.8.2	Make good existing internal face of brick walls where FFL is lowered	1,635.00
	9302	3.11.5.1.3.8.3	Adjust threshold step to door at change in floor level	897.00
C		3.11.5.1.3.9	Tiling	
	9302	3.11.5.1.3.9.1	Floor tiling to waiting area with epoxy grout	4,625.00
	9302	3.11.5.1.3.9.2	Skirting tiling	1,168.00
	9302	3.11.5.1.3.9.3	Threshold tile	3,452.00
C		3.11.5.1.3.10	Fixtures & Fittings Waiting Room	
	9302	3.11.5.1.3.10.1	Bench seat	5,170.00
C		3.11.5.1.3.11	Painting	
	9302	3.11.5.1.3.11.1	Allow painting to new works only Apply paint system to:-	
	9302	3.11.5.1.3.11.3	Internal ceiling linings	607.00
	9302	3.11.5.1.3.11.7	Waiting room facebrick walls Subtotal	1,449.00
4		3.11.6	Hydraulic Services - Building Works	



Item No.			Descriptions	Amount
5		3.11.6.1	Lift 1 - Platform 1	
	9302	3.11.6.1.1	Strip drain to lift lobby/entry	5,629.00
	9302	3.11.6.1.2	Drainage & connect/discharge to stormwater	4,593.00
5		3.11.6.2	Lift 2 - Platform 2	
	9302	3.11.6.2.1	Strip drain to lift lobby/entry	5,629.00
	9302	3.11.6.2.2	Drainage & connect/discharge to stormwater	4,593.00
5		3.11.6.3	Platform Building Alterations	
6		3.11.6.3.1	Platform 1	
	9302	3.11.6.3.1.1	Sewer - allowance to modify existing in ground sewer to suit new layout	12,375.00
	9302	3.11.6.3.1.2	Water - disconnect existing damaged water service to the site, new mains connection at Shirley Street, incl. metering & RPZ, new 25mm service to platform 1 platform building, locate and connect to existing branch line at ULX for platform 2 water service allowance to modify existing water to suit new layout	38,187.00
	9302	3.11.6.3.1.3	Water - allowance to rough in water with in platform building to suit new layout	5,098.00
С		3.11.6.3.1.1	FAT	
	9302	3.11.6.3.1.1.1	Add hot water to FAT/ambulant WC - hydraulics (HWU, HW pipework & taps, tundish)	5,859.00
	9302	3.11.6.3.1.1.2	WC	6,797.00
	9302	3.11.6.3.1.1.3	Basin	5,204.00
	9302	3.11.6.3.1.1.4	Floor waste	531.00
	9302	3.11.6.3.1.1.5	Тар	797.00
С		3.11.6.3.1.2	AMB WC - female	
	9302	3.11.6.3.1.2.1	WC	6,797.00
	9302	3.11.6.3.1.2.2	Basin	5,204.00
	9302	3.11.6.3.1.2.3	Floor waste	531.00
	9302	3.11.6.3.1.2.4	Тар	797.00
С		3.11.6.3.1.3	AMB WC - male	
	9302	3.11.6.3.1.3.1	WC	6,797.00
	9302	3.11.6.3.1.3.2	Basin	5,204.00
	9302	3.11.6.3.1.3.3	Floor waste	531.00
	9302	3.11.6.3.1.3.4	Тар	797.00
С		3.11.6.3.1.4	Staff Room	
	9302	3.11.6.3.1.4.3	Boil water unit - assume n/a	1,784.00
С		3.11.6.3.1.5	Cleaners Room	
	9302	3.11.6.3.1.5.1	Cleaners sink	5,204.00
	9302	3.11.6.3.1.5.2	HWU	2,345.00
С		3.11.6.3.1.6	Air Conditioner Condensor Tundish	



	lte	m No.	Descriptions	Amount
	9302	3.11.6.3.1.6.1	Air Conditioner condensor tundish	2,953.00
С		3.11.6.3.1.7	Water Fountain	
	9302	3.11.6.3.1.7.1	Replace existing water fountain with DDA compliant	6,322.00
4		3.11.8	Mechanical Services - Building Works	
5		3.11.8.1	Lift 1 - Platform 1	
	9302	3.11.8.1.1	Mechanical air supply to lift shaft	9,323.00
5		3.11.8.2	Lift 2 - Platform 2	
	9302	3.11.8.2.1	Mechanical air supply to lift shaft	9,323.00
5		3.11.8.3	Platform Building Alterations	
	9302	3.11.8.3.1	Assume existing air-conditioning to platform building staff office to remain as is	
	9302	3.11.8.3.2	Mechanical exhaust to FAT	5,895.00
	9302	3.11.8.3.3	Mechanical exhaust to ambulant WC - female	5,895.00
	9302	3.11.8.3.4	Mechanical exhaust to ambulant WC - male	5,895.00
	9302	3.11.8.3.5	Mechanical exhaust to cleaner's room	5,895.00
	9302	3.11.8.3.6	Air conditioning to SSER	8,156.00
	9302	3.11.8.3.8	Outdoor air supply to SSER	5,895.00
4		3.11.9	Lifts BWIC (Lift Contractor engaged by the Principal)	
5		3.11.9.1	Lift 1 - Platform 1	
6		3.11.9.1.1	Liftronic Interface	
	9302	3.11.9.1.1.1	Cranage for delivery of Liftronic equipment - see Downer Preliminaries	4,995.00
	9302	3.11.9.1.1.2	Attendance at Sydney Trains inspection & obtain workcover certificates	Included
	9302	3.11.9.1.1.3	Attendance for delivery	Included
	9302	3.11.9.1.1.5	Temporary access to lift shaft	Included
	9302	3.11.9.1.1.6	Internal scaffold	6,435.00
	9302	3.11.9.1.1.7	Protection of lift shaft & temporary hoardings/gates	1,859.00
6		3.11.9.2.1	Liftronic Interface	
	9302	3.11.9.2.1.1	Cranage for delivery of Liftronic equipment - see Downer Preliminaries	4,995.00
	9302	3.11.9.2.1.2	Attendance at Sydney Trains inspection & obtain workcover certificates	Included
	9302	3.11.9.2.1.3	Attendance for delivery	Included
	9302	3.11.9.2.1.5	Temporary access to lift shaft	Included
	9302	3.11.9.2.1.6	Internal scaffold	6,435.00
	9302	3.11.9.2.1.7	Protection of lift shaft & temporary hoardings/gates	1,859.00
3		3.12	Finishes	
4		3.12.1	Painting (incl. anti-graffiti)	
5		3.12.1.1	Painting	



Item No.		m No.	Descriptions	Amount
С		3.12.1.1.1	Apply proprietary paint system to:	
	5028	3.12.1.1.1.1	HDG balustrade, 1100mm high	6,880.00
	5028	3.12.1.1.1.2	Lift shaft ceiling & plenums	1,963.00
5		3.12.1.2	Anti-Graffiti	
C		3.12.1.2.1	Apply anti-graffiti coating equal to Sure Seal Graffiti Shield to:-	
	5028	3.12.1.2.1.2	Concrete column/blade walls	960.00
	5028	3.12.1.2.1.3	Concrete sides of susp. walkways	1,040.00
	5028	3.12.1.2.1.5	Masonry walls	23,507.00
5		3.12.1.3	Nawkaw stain to concrete lift shaft	
	5028	3.12.1.3.1	Nawkaw stain to concrete lift shaft - lift 1	3,273.00
	5028	3.12.1.3.2	Nawkaw stain to concrete lift shaft - lift 2	2,345.00
4		3.12.2	Vermin/Bird Control	
	5028	3.12.2.1	Vermin/Bird Control - allowance	3,532.00
3		3.13	Fencing	
5		3.13.1	Eastern Entry	
	3456	3.13.1.1	Modify existing fence from Shirley Road to Platform 1 for new lift 1 & entry works, new MSB room	5,030.00
5		3.13.4	Platform 2	
С		3.13.4.1	Platform fencing to be replaced for platform raising - see PLATFORM RAISING trade	
	3456	3.13.4.1.1	Fence to front of west walkway trestle frames to prevent unauthorised access & claimbing of the structures	13,050.00
5		3.13.5	Lift 1 maintenance area	
	3456	3.13.5.1	Corridor fence	797.00
	3456	3.13.5.2	Extra Over for lockable gate	956.00
5		3.13.6	Lift 2 maintenance area	
	3456	3.13.6.1	Corridor fence	797.00
	3456	3.13.6.2	Extra Over for lockable gate	956.00
3		3.19	Landscaping	
4		3.19.1	East Entry	
	2035	3.19.1.1	Garden bed incl. excavate, cultivate subgrade, planter soils, mulch, plants	1,171.00
	2035	3.19.1.2	Relocate existing 6-8m high palm tree at east entry within existing paved 'observation deck' area incl. tree pit & 12 months maintenance	13,169.00
	2035	3.19.1.3	Replacement tree - allow 250 ltr with tree pit in garden bed, drainage, subsoil cultivation, soils, tree	2,570.00
4		3.19.2	West Entry	
	2035	3.19.2.1	Garden bed incl. excavate, cultivate subgrade, planter soils, mulch, plants	15,455.00
	2035	3.19.2.3	Replacement tree - allow 250 ltr with tree pit in garden	39,506.00



	ltem No.		Descriptions	Amount
			bed, drainage, subsoil cultivation, soils, tree	
	2035	3.19.2.5	Urban design precast concrete seat with timber slat top	11,565.00
4		3.19.3	Platform 1	
	2035	3.19.3.1	Protect & make good landscaping at north end of the platform during/after platform raising works	3,505.00
4		3.19.4	Platform 2	
	2035	3.19.4.1	Protect & make good landscaping at north end of the platform during/after platform raising works	3,080.00
	2035	3.19.4.2	Protect & make good landscaping at mid platform (adjacent station building) during/after platform raising works	1,274.00
	2035	3.19.4.3	Reinstate grassed area at south end of platform after construction works - new turf	9,787.00
3		Special	Handover documents as per checklist provided in Appendix 10	167,632.15
			TOTAL	\$ 1,676,399.15



Schedule of Rates

Item	SCHEDULE OF RATES (for works outside the Contract's	UNIT	UNIT RATE (\$)			
No.	scope)		Normal Time	Time and Half	Double Time	
	LABOUR					
1	General Labourer	Hr	\$55.00	\$83.00	\$110.00	
2	Skilled Labourer	Hr	\$62.00	\$93.00	\$124.00	
3	Concretor	Hr	\$100.00	\$130.00	\$160.00	
4	Carpenter	Hr	\$90.00	\$125.00	\$152.00	
5	Steel Fixer	Hr	\$100.00	\$130.00	\$160.00	
6	Formworker	Hr	\$100.00	\$130.00	\$160.00	
7	Glazier	Hr	\$95.00	\$125.00	\$150.00	
8	Machine Operators	Hr	N/A	N/A	N/A	
9	Leading Hand	Hr	\$75.00	\$110.00	\$140.00	
	Please insert, if required					
10	Plumber	Hr	\$100.00	\$130.00	\$160.00	
11	Mechanic	Hr	\$150.00	N/A	\$280.00	

<u>NOTES</u>

Monday to Friday: First 8 hours Normal Time, next 2 hours Time and Half Double Time thereafter

Saturday: First 2 hours Time and Half, Double Time thereafter

Sunday: Double Time.

Public Holiday: Double Time and Half

Night Shift: 18:00 to 06:00 (Time and Half)

All allowances including but not limited to travel, meal, first aid etc inclusive in the rates above

Hours should be nett off all meal times

Minimum hire period is 4 hours


The price above is subject to the following conditions

- The prices above are fixed for the term of this Agreement.
- All overhead costs, profit / margin and allowances are included in the prices and rates above.
- The prices above are exclusive of GST.



- The prices and rates above are inclusive of all costs, allowances, consumables, required testing, fully equipped vehicles and running cost of vehicles, and small tools required to complete the works.
- The quantities provided in above schedules are Indicative only.
- Travel time is included in the prices above (It is expected that locally available resources will be used),
- Workplace Health and Safety requirements including attendance at inductions, pre-start meetings, and toolbox talks are inclusive in above prices and rates.
- The rates / prices and time of above rates shall be in accordance with relevant EBA / award.
- The Subcontractor shall take signature from Downer's representative on timesheet on daily basis (after the work performed) and then submit this approved timesheets / dayworks with claim / invoices. Downer will pay the Subcontractor by applying the appropriate rates to the hours worked as per the approved timesheet authorised by Downer's representative.






Schedule 2 – Further Purposes or Requirements

See clause 5(i)(iv))

Not Applicable





Schedule 3 – Deed of Release (Clause 8.4)

То	Downer EDI Works Pty Ltd (ABN 66 008 709 608)
	Of Triniti Business Campus, 39 Delhi Road, North Ryde NSW 2113 (Downer)
Project	The construction of [insert description of the Subcontract Works] as further described in the Subcontract (the Work)
Subcontractor	[insert full name of Party] (ACN [insert] of [insert address of Party] (the Subcontractor)
Subcontract	Agreement made between Downer and the Subcontractor on(the Subcontract)

- 1 The Subcontractor agrees that, to the extent permitted by law, except for the amounts specified in clause 2 below, the total monies payable or that may in the future become payable under or in any way arising out of or connected with the Subcontract or the Work or any other work (**Other Work**) executed by the Subcontractor, its Secondary Subcontractors and/or suppliers on or about the Site of the Work is \$...... (including the retention amount) (the **Practical Completion Payment**).
- 2 The Practical Completion Payment does not include the amount for retention of \$ but in circumstances where Downer is entitled to terminate the Subcontract under clause 27.8 of the Subcontract the Subcontractor acknowledges and agrees that Downer is entitled to the proceeds of all then held retention and the Subcontractor has no entitlement to have that retention returned.
- **3** The Subcontractor acknowledges and agrees that to the extent permitted by law, payment by Downer to the Subcontractor of the Practical Completion Payment is acceptance by the Subcontractor of full and final payment to the Subcontractor of all amounts due and payable at Practical Completion of the whole of the Work and any Other Work, except for amounts described in clause 2 above (if any).
- 4 To the extent permitted by law, the Subcontractor waives, releases and forever discharges Downer from all or any liabilities, claims, actions, demands, suits, proceedings, damages, expenses, costs and the like (whether direct, indirect or consequential, past, present or future, certain or contingent, ascertained or not ascertained) howsoever arising under or in connection with the Subcontract or in any way connected with execution of the Work and any Other Work. The Subcontractor indemnifies and keeps indemnified Downer from all such liabilities, claims, entitlements, actions, demands, suits, proceedings, damages, expenses, costs and the like, which but for this provision, the Subcontractor may have had or may arise at any time.
- 5 Clause 4 does not apply in respect of the amounts described in clause 2 above (if any).
- 6 The Subcontractor certifies that at Practical Completion of the Work:
 - (a) all wages and allowances, including in respect of overtime and loadings, which become due and payable to all persons who have at any time been employed by the Subcontractor on the Work have been paid in full;
 - (b) all entitlements which have or should have accrued in respect of all persons who have at any time been employed by the Subcontractor on the Work, including in relation to annual leave, personal leave and RDOs, have been properly accounted for in accordance with any applicable legislation and legally binding agreement, award, workplace agreement or workplace policy;
 - (c) all Secondary Subcontractors engaged by the Subcontractor on the Work and all suppliers to the Subcontractor of plant, equipment and material for the Work have been paid in full; and
 - (d) all contributions and payments to any scheme for superannuation, long service leave, redundancy and severance pay or the like as required by legislation and any applicable and legally binding award or workplace agreement have been paid in full.



 Executed as a DEED on the
 day of
 20

 Executed by [insert Subcontractor] ACN [insert] in accordance with section 127 of the Corporations Act 2001:
 Image: Corporation of the Corporatic of the Corporatic of the Corporatic of the Corporation of the C



Schedule 3A – Deed of Final Release (Clause 8.5, 22.4)

- ToDowner EDI Works Pty Ltd (ABN 66 008 709 608)
Of Triniti Business Campus, 39 Delhi Road, North Ryde NSW 2113 (Downer)ProjectThe construction of [insert description of the Subcontract Works] as further described in the
Subcontract (the Work)Subcontractor[insert full name of Party]
(ACN [insert]
of [insert address of Party] (the Subcontractor)SubcontractAgreement made between Downer and the Subcontractor on
(the Subcontract)
- 2 The Subcontractor acknowledges and agrees that payment by Downer to the Subcontractor of the Final Payment is acceptance by the Subcontractor of full and final payment to the Subcontractor of all amounts due and payable now or in the future in connection with the Subcontract and the Work or any other work executed by the Subcontractor, its Secondary Subcontractors and/or suppliers on or about the site of the Work.
- 3 The Subcontractor waives, releases and forever discharges Downer from all or any liabilities, claims, actions, demands, suits, proceedings, damages, expenses, costs and the like (whether direct, indirect or consequential, past, present or future, certain or contingent, ascertained or not ascertained) howsoever arising under or in connection with the Subcontract or in any way connected with execution of the Work or work executed or materials supplied on or about the site of the Work. The Subcontractor indemnifies and keeps indemnified Downer from all such liabilities, claims, entitlements, actions, demands, suits, proceedings, damages, expenses, costs and the like, which but for this provision, the Subcontractor may have had or may arise at any time.
- 4 The Subcontractor certifies that:
 - (a) all wages and allowances which become due and payable to all persons who have at any time been employed by Subcontractor on the Work have been paid in full;
 - (b) all entitlements which have or should have accrued in respect of all persons who have at any time been employed by the Subcontractor on the Work, including in relation to annual leave, personal leave and RDOs, have been properly accounted for in accordance with any applicable legislation and legally binding agreement, award, workplace agreement or workplace policy;
 - (c) all Secondary Subcontractors engaged by the Subcontractor on the Work and suppliers to the Subcontractor of plant, equipment and material for the Work have been paid in full; and
 - (d) all contributions and payments to any scheme for superannuation, long service leave, redundancy and severance pay or the like as required by legislation and any award requirements have been paid in full.



Executed as a deed and delivered on the date shown on the first page.

Executed by [insert **Subcontractor**] ACN [insert] in accordance with section 127 of the *Corporations Act 2001:*

Director/Company Secretary

Director

Name of Director/ Company Secretary (BLOCK LETTERS)

Name of Director (BLOCK LETTERS)



Schedule 4– Moral Rights Consent

Deed poll dated

Made by	[insert full name of Author] of [insert address] (Author)
in favour of	Downer EDI Works Pty Ltd (ABN 66 008 709 608) of Triniti Business Campus, 39 Delhi Road, North Ryde NSW 2113 (Contractor)

Introduction

- A. Downer and [insert name and ACN of Subcontractor] entered into a building contract dated [insert date of building contract] (the **Agreement**) to perform or create certain building works (the **Work**).
- B. The Author has created or will create copyright material as described in this deed which may be used in connection with, or as part of, the Work.

The [Author] declares

1 Definitions

In this Deed:

- (a) **Authorised Persons** means Downer and any assignee or sub-licensee of Downer in relation to the Copyright Material or any subcontractor of Downer in relation to the Work; and
- (b) Copyright Material means:
 - (i) [describe the copyright works which the author has or will create as precisely as possible]; and
 - (ii) any other material in which copyright subsists for the purposes of the *Copyright* Act 1968 (Cth) (as amended) which the Author creates or has created for the purpose of the Agreement or the Work.

2 Consent

- 2.1 The Author consents to the Authorised Persons:
 - (a) not attributing to the Author authorship of the Copyright Material;
 - (b) falsely attributing authorship of the Copyright Material;
 - (c) modifying, varying or amending the Copyright Material;
 - (d) using the Copyright Material other than for the purpose for which it was intended when created; and
 - (e) changing, relocating, demolishing or destroying any three dimensional reproduction of the Copyright Material without prior notification to the Author.
- 2.2 The Author acknowledges that the consent given in this deed is genuinely given and is not provided under duress and is given in full knowledge that the Author is giving up rights granted under Part IX of the *Copyright Act 1968* (Cth)



3 Further actions

The Author agrees to do all things and execute all documents as Downer reasonably requests in order to give full effect to the consent provided in this deed.

4 Warranty

The Author warrants that the Author will not sue, enforce any claim, bring any action or exercise any remedy in respect of a breach of its moral rights in respect of the any Copyright Material by the Authorised Persons.

Executed as a deed poll and delivered on the date shown on the first page.

Signed, sealed and delivered by [insert name of author] in the presence of:

Signature of witness

Name of witness (BLOCK LETTERS)

Address of witness



Schedule 5 – New South Wales

1 OHS Rules (NSW)

- 1.1 The Subcontractor:
 - (a) shall comply with and ensure that its Secondary Subcontractors comply with the OHS Rules and shall do all things necessary and in a manner which ensures that Downer satisfies its obligations under the OHS Rules;
 - (b) acknowledges that Downer (or another party as advised by Downer) is engaged as the 'principal contractor' under the OHS Rules for the Site;
 - (c) shall comply with and ensure that its Secondary Subcontractors comply with any Direction of the principal contractor;
 - (d) shall, before commencing any Work, prepare and submit details of its work health, safety and rehabilitation management system and a Site specific safety plan incorporating safe work method statements; and
 - (e) shall, to the extent the Subcontractor designs any structure (or part of a structure) which is to be constructed, provide to Downer a written report that specifies the hazards relating to the design of that structure which, so far as the Subcontractor is reasonably aware, creates a risk to the health or safety of persons who are carrying out any construction work on the structure or part.
- 1.2 For the purpose of this clause:
 - (a) "OHS Rules" means:
 - (i) the WH&S Act and WH&S Regulation as updated from time to time; and
 - (ii) all relevant associated legislation, regulations, rules, Standards, Australian Standards, codes of practice and compliance guidelines applicable to the Work, workplace health and safety, environmental protection, dangerous goods and electrical safety together with any Directions on safety or notices issued by any relevant authority including, to the extent applicable to the Work the following:
 - (A) Dangerous Goods (Road and Rail Transport) Act 2008 (NSW);
 - (B) Explosives Act 2003 (NSW);
 - (C) Explosives Regulation 2013 (NSW);
 - (D) Work Health and Safety (Mines and Petroleum Sites) Act 2013 (NSW);
 - (E) Work Health and Safety (Mines and Petroleum Sites) Regulation 2014 (NSW);
 - (F) codes of practice relating to the NSW Work Health and Safety (Mines and Petroleum Sites) Regulation 2014 (NSW);
 - (G) Rail Safety National Law (NSW);
 - (H) Rail Safety (Adoption of National Law) Act 2012 (NSW);
 - (I) Rail Safety National Law National Regulations 2012 (NSW);
 - (J) Rural Workers Accommodation Act 1969 (NSW);
 - (K) Heavy Vehicle National Law (NSW);
 - (L) Heavy Vehicle (Adoption of National Law Regulations 2013 (NSW);
 - (M) all Heavy Vehicle Regulations;
 - (N) national compliance and enforcement policies;
 - (O) model codes of practice; and
 - (P) NSW codes of practice;
 - (b) "WH&S Act" means the Work Health and Safety Act 2011 (NSW); and
 - (c) "WH&S Regulation" means the Work Health and Safety Regulation 2017 (NSW).

2 Subcontractor's Statement

Each progress claim shall be accompanied by a duly signed written statement in a form approved by Downer and which complies with the Subcontractor's obligations under section 127 of the *Industrial Relations Act 1996* (NSW), Schedule 2 Part 5 of the *Payroll Tax Act 2007* (NSW) and section 175B of the *Workers Compensation Act 1987* (NSW) to provide a statement to the "principal contractor" as contemplated by those acts.

3 NSW Code of Practice for Construction Work

(a) In this clause:



- (i) "Construction Compliance Unit" means any unit established to monitor compliance with and receive reports of alleged breaches of the NSW Code; and
- (ii) "NSW Code" means the New South Wales Code of Practice for Procurement, as varied or replaced from time to time, and:
 - (A) prior to 1 July 2013, includes the Implementation Guidelines for the NSW Code of Practice and Code of Tendering
 - (B) from 1 July 2013, includes the Implementation Guidelines to the New South Wales Code of Practice for Procurement, as varied or replaced from time to time.

(The NSW Code is currently available at www.procurepoint.nsw.gov.au)

- (b) The Subcontractor must comply, and must ensure that its employees, agents, Secondary Subcontractors and Related Companies comply, with the NSW Code.
- (c) Compliance with the NSW Code does not relieve the Subcontractor from responsibility to perform the Subcontract, or from liability for any Defects arising from compliance with the NSW Code.
- (d) If the National Code applies, the National Code should be read conjointly with the NSW Code to the maximum extent lawfully possible.
- (e) The Subcontractor acknowledges and accepts that the NSW Government and Downer, and those authorised by the NSW Government or Downer, may:
 - (i) request full access to any Work to:
 - (A) inspect any work, material, machinery, appliance, article or facility;
 - (B) inspect and copy any record; and
 - (C) interview any person,

and on such request the Subcontractor must provide such access as is necessary to allow validation of compliance with the NSW Code by the Subcontractor and its employees, agents, Secondary Subcontractors and Related Companies;

- (ii) request specified documentation to be produced within a specified period, in person, by fax or by post and on such request the Subcontractor must provide such documentation; and
- (iii) publish or otherwise disclose information in relation to compliance with the NSW Code.
- (f) Where a change in the provision of the Work is proposed under the Subcontract and that change would affect compliance with the NSW Code, the Subcontractor must prepare a report to Downer, for provision to the NSW Government, specifying the extent to which compliance with the NSW Code by the Subcontractor or its employees, agents, Secondary Subcontractors or Related Companies will be affected (as applicable). Downer will, after consultation with the New South Wales Government and consideration of the legislation and relevant OHS Rules, direct the Subcontractor as to the course it must adopt once the report is received. The Subcontractor shall have no Claim in connection with any such Direction or compliance with any such Direction.
- (g) The Subcontractor must maintain, and must ensure that its Secondary Subcontractors and Related Companies maintain, adequate records of compliance with the NSW Code.
- (h) From 1 July 2013, the Subcontractor must notify Downer of any alleged breaches of the NSW Code (and voluntary remedial action proposed) within 24 hours of becoming aware, or when a competent contractor exercising good industry practice should have become aware, of the alleged breach.
- (i) If the Subcontractor, or any of its employees, agents, Secondary Subcontractors or any Related Company, does not comply with the requirements of the NSW Code, in the provision of the Work, such that a sanction is applied as a consequence, without prejudice to any rights that would otherwise accrue, the NSW Government will be entitled to record that non-compliance and take it into account in the evaluation of any future tenders that may be lodged by the Subcontractor, or any of its employees, agents, Secondary Subcontractors or Related Companies, in respect of work for any part of the State of New South Wales or its agencies.
- (j) The Subcontractor must:
 - (i) not engage any Secondary Subcontractor where the engagement would breach a sanction imposed by the Construction Compliance Unit;
 - (ii) ensure that each Secondary Subcontractor maintains and provides access for any person or entity authorised by the New South Wales Government to the same extent as required from the Subcontractor under this clause; and
 - (iii) ensure that all contracts with Secondary Subcontractors contain requirements equivalent to the requirements set out in this clause.



Schedule 13 - National Code

- 1 National Code of Practice for the Construction Industry (National Code)
- 1.1 In this Schedule 13:

ABCC means the body referred to in subsection 29(2) of the Act.

ABC Commissioner means the Australian Building and Construction Commissioner referred to in subsection 15(1) of the Act.

Act means the Building and Construction Industry (Improving Productivity) Act 2016.

Building Code means the *Code for the Tendering and Performance of Building Work 2016*, which is available at https://www.legislation.gov.au/Details/F2017C00668.

Building Contractor has the same meaning as in the Act.

Building Industry Participant has the same meaning as in the Act.

Building Work has the same meaning as in subsection 3(4) of the Building Code.

Commonwealth Funded Building Work means Building Work in items 1–8 of Schedule 1 of the Building Code.

Enterprise Agreement has the same meaning as in the Fair Work Act 2009 (Cth).

Exclusion Sanction has the same meaning as in subsection 3(3) of the Building Code.

Related Entity has the same meaning as in subsection 3(2) of the Building Code.

Sub-subcontractor means a Building Contractor or Building Industry Participant who the Subcontractor has entered, or proposes to enter, into a sub-subcontract with to undertake any of the Works.

Works means Commonwealth Funded Building Work that is the subject of this Subcontract.

- 1.2 The Subcontractor declares as at the date of commencement of this Subcontract in relation to the Works, that it:
 - (a) is not subject to an Exclusion Sanction;
 - (b) unless approved otherwise by the ABC Commissioner, is not excluded from performing Building Work funded by a state or territory government; and
 - (c) is not covered by, and does not have Related Entities covered by, an Enterprise Agreement that does not meet the requirements of section 11 of the Building Code.
- 1.3 The Subcontractor:
 - (a) declares as at the date of commencement of this Subcontract in relation to the Works; and
 - (b) must ensure that during the term of this Subcontract in relation to the Works,
 - that it and its Sub-subcontractors:
 - (c) comply with the Building Code;
 - (d) will only use products in relation to the Works that comply with the relevant Australian Standards published by, or on behalf of, Standards Australia;
 - (e) comply with the Workplace Relations Management Plan approved by the ABCC in accordance with Part 6 of the Building Code that applies to the Work.
- 1.4 Without limiting and notwithstanding the other provisions of this Schedule 14, the Subcontractor will ensure that remedial action is taken to rectify any behaviour on the part of it and its Sub-subcontractors that is non-compliant with the Building Code.
- 1.5 The Subcontractor must every six months during the term of this Subcontract advise Downer whether:
 - (a) it has in the preceding six months or since it last advised Downer, whichever is the earliest, had an adverse decision, direction or order of a court or tribunal made against it for a breach of a designated building law, work health and safety law or the Migration Act 1958 (Cth);
 - (b) it has in the preceding six months or since it last advised Downer, whichever is the earliest:
 - been required to pay any amount under an adjudication certificate (provided in accordance with a law relating to the security of payments that are due to persons in respect of building work) to a Building Contractor or Building Industry Participant; or
 - (ii) owed any unsatisfied judgement debts to a Building Contractor or Building Industry Participant.
- 1.6 Compliance with the Building Code does not relieve the Subcontractor from responsibility to perform this Subcontract, or from liability for any Defect in the Works arising from compliance with the Building Code.
- 1.7 The Subcontractor must notify the ABCC of any breach or suspected breach of the Building Code as soon as practicable but no later than two working days after becoming aware of the breach or suspected breach and of the steps proposed to be taken to rectify the breach.



- 1.8 The Subcontractor acknowledges the powers and functions of the ABC Commissioner and the ABCC under the Act and the Building Code and will ensure that it and its Sub-subcontractors comply with any requests made by the ABCC and the ABC Commissioner within those powers and functions, including but not limited to requests for entry under section 72 of the Act, requests to interview any person under section 74 of the Act, requests to produce records or documents under sections 74 and 77 of the Act and requests for information concerning matters relating to the Building Code under subsection 7(c) of the Building Code.
- 1.9 The Subcontractor must only enter into a sub-subcontract for any of the Work where:
 - (a) the Sub-subcontractor has submitted a declaration of compliance, including the further information outlined in Attachment A to the declaration of compliance, in substantively the same form as the model declaration of compliance applicable to contractors and subcontractors in relation to the Building Code (located in Part 4 in the document entitled Model Clauses Type B, available on the ABCC website (www.abcc.gove.au)); and
 - (b) the sub-subcontract with the Sub-subcontractor contains clauses in substantively the same form as the model contract clauses applicable to contractors and subcontractors in relation to the Building Code.
- 1.10 The Subcontractor must ensure that it and its Sub-subcontractors comply with clauses contained in the sub-subcontract referred to in this Schedule.



Schedule 14– Deed of Novation

THIS	DEED is made the	day of	20			
Parti	ies:					
1	[Relevant Downer Entity] (ACN)	of [insert address] (Downer)				
2	[Insert] (ACN) of [insert address]	(Subcontractor)				
3	[Insert] (ACN) of [insert address]	(Novatee)				
Bacl	Background					

A Downer has engaged the Subcontractor pursuant to the Subcontract.

B The parties have agreed to novate the Subcontract on the terms and conditions of this Deed.

1 Definitions and Interpretation

1.1 Definitions

In this Deed:

Deed means this document;

Effective Date means the date of this Deed; and

Subcontract means the contract between Downer and the Subcontractor dated [insert].

Interpretation

Unless expressed to the contrary, in this Deed:

- (a) headings are for convenience only and do not affect the interpretation of this Deed;
- (b) the singular includes the plural and vice versa;
- (c) words that are gender neutral or gender specific include each gender;
- (d) where a word or phrase is given a particular meaning, other parts of speech and grammatical forms of that word or phrase have corresponding meanings;
- (e) the words 'such as', 'including', 'particularly' and similar expressions are not used as nor are intended to be interpreted as words of limitation;
- (f) a reference to:
 - (i) a person includes a natural person, partnership, joint venture, government agency, association, corporation or other body corporate;
 - (ii) a thing (including a chose in action or other right) includes a part of that thing;
 - (iii) a party includes its successors and permitted assigns;
 - (iv) a contract includes all amendments or supplements to that contract;
 - (v) a clause, term, party, schedule or attachment is a reference to a clause or term of, or party, schedule or attachment to this Deed;



- a law includes a constitutional provision, treaty, decree, convention, statute, regulation, ordinance, by-law, judgment, rule of common law or equity or a rule of an applicable financial market and is a reference to that law as amended, consolidated or replaced;
- (vii) an agreement other than this Deed includes an undertaking, or legally enforceable arrangement or understanding whether or not in writing; and
- (viii) a monetary amount is in Australian dollars;
- (a) an agreement on the part of two or more persons binds them jointly and severally;
- (b) when the day on which something must be done is not a business day, that thing must be done on the following business day;
- (c) in determining the time of day where relevant to the Deed, the relevant time of day is:
 - (i) for the purposes of giving or receiving notices, the time of day where a party receiving a notice is located; or
 - (ii) for any other purpose under this Deed, the time of day in the place where the party required to perform an obligation is located; and
- (d) no rule of construction applies to the disadvantage of a party because that party was responsible for the preparation of this Deed or any part of it.

2 Novation

2.1 Novation

With effect on and from the Effective Date, the parties novate the Subcontract so that:

- (a) the Novatee replaces Downer under the Subcontract as if it were an original party to the Subcontract; and
- (b) all references in the Subcontract to Downer must be read as references to the Novatee.

2.2 Assumptions of rights and obligations

Subject to clause 3, on and from the Effective Date:

- (a) the Novatee:
 - (i) must comply with the Subcontract as if the Novatee had been originally named as a party to the Subcontract in place of Downer; and
 - (ii) obtains all rights and assumes all obligations of Downer under the Subcontract; and
- (b) the Subcontractor must comply with the Subcontract on the basis that the Novatee has replaced Downer under it in accordance with this Deed.

3 Release

3.1 Release by the Subcontractor and the Novatee

The Subcontractor and the Novatee release Downer from all obligations and liabilities of Downer arising out of or in connection with the Subcontract including:

- (a) any claims for payment made or to be made in relation to work or services provided or matters arising prior to the Effective Date; or
- (b) any claims made on any other basis whatsoever in relation to matters occurring prior to and after the Effective Date.



3.2 Warranty

The Subcontractor warrants to the Novatee that:

- (a) it has performed the Work under the Subcontract in accordance with the Subcontract;
- (b) it must perform the remaining Work under the Subcontract in accordance with the Subcontract; and
- (c) it is aware that the Novatee is relying on it to fulfil its obligations under the Subcontract.

4 Assignment

This Deed is personal between the parties and no party may assign any right under this Deed except with, and in strict compliance with any conditions of, the prior written consent of each of the other parties.

5 Governing law and jurisdiction

This Deed will be construed in accordance with the laws [insert relevant State or Territory] and the parties irrevocably submit to the jurisdiction of the Courts of that State.

6 Miscellaneous

6.1 Variation

No variation of this Deed is effective unless made in writing and signed by each party.

6.2 Waiver

- (a) No waiver of a right or remedy under this Deed is effective unless it is in writing and signed by the party granting it. It is only effective in the specific instance and for the specific purpose for which it is granted.
- (b) A single or partial exercise of a right or remedy under this Deed does not prevent a further exercise of that or of any other right or remedy.
- (c) Failure to exercise or delay in exercising a right or remedy under this Deed does not operate as a waiver or prevent further exercise of that or of any other right or remedy.

6.3 Further assurances

Each party agrees, at its own expense, on the request of any one of the other parties, to do everything reasonably necessary to cause this Deed and the transactions contemplated by it to be completed and become and remain effective.

6.4 Counterparts

This Deed may be executed in any number of counterparts, each of which, when executed, is an original. Those counterparts together make one instrument.

6.5 Cumulative rights

Except as expressly provided in this Deed, the rights of a party under this Deed are in addition to and do not exclude or limit any other rights or remedies provided by law.

6.6 Entire agreement

- (a) This Deed is the entire agreement between the parties about its subject matter and replaces all previous agreements, understandings, representations and warranties about that subject matter.
- (b) Each party represents and warrants that it has not relied on any representations or warranties about the subject matter of this Deed except as expressly provided in this Deed.



6.7 Relationship of the parties

Except as expressly provided in this Deed:

- (a) nothing in this Deed is intended to constitute a fiduciary relationship or an agency, partnership or trust; and
- (b) no party has authority to bind any other party.

6.8 Survival and merger

- (a) No term of this Deed merges on completion of any transaction contemplated by this Deed.
- (b) Clauses 1, 3, 5 and 6 survive termination or expiry of this Deed together with any other term which by its nature is intended to do so.

6.9 Capacity

Except as expressly provided in this Deed each person who executes this Deed does so solely in its own legal capacity and not as agent or trustee for or a partner of any other person.

Execution page

Vol 26.1

Executed as a deed

Signed and delivered by [Downer entity] in accordance with section 127 of the <i>Corporations Act 2001</i> (Cth) and by:				
Signature of director	Signature of director/secretary			
Name of director (print)	Name of director/secretary (print)			
Signed and delivered by [Subcontract] in accordance with section 127 of the <i>Corporations Act 2001</i> (Cth) and by:				
Signature of director	Signature of director/secretary			
Name of director (print)	Name of director/secretary (print)			
Signed and delivered by [Novatee] in accordance with section 127 of the <i>Corporations Act 2001</i> (Cth) and by:				
Signature of director	Signature of director/secretary			
Name of director (print)	Name of director/secretary (print)			
DG-LG-TP020	Page 121 of 123 Version: 1.3			
© Downer 2020. All Rights Reserved	Commercial in Confidence			



Schedule 15 – Subcontractor's Warranty

Form of Warranty

Subcontractor's Warranty – Refer to Appendix 3



Schedule 16 - Security of Payment

1 New South Wales

- 1.1 This clause applies to the extent that this Subcontract is for construction work carried out in New South Wales, or is for the supply of related goods and services for construction work carried out in New South Wales.
- 1.2 In this clause, 'construction work' and 'related goods and services' have the meaning given to those terms in the *Building and Construction Industry Security of Payment Act 1999* (NSW).
- 1.3 The Subcontractor shall:
 - (a) promptly give Downer a copy of any notice the Subcontractor:
 - (i) receives from a subcontractor under sections 15, 16 or 24 of the Security of Payment Act; or
 - has been required to supply to a subcontractor under section 15(1) of the Contractors Debts Act setting out Downer's name;
 - (b) ensure that each subcontractor promptly gives Downer a copy of any notice that the subcontractor receives from another person under sections 15, 16 or 24 of the Security of Payment Act; and
 - (c) promptly notify Downer if it becomes aware that a subcontractor intends to exercise a statutory lien, under section 11(3) of the Security of Payment Act, over unfixed plant and materials supplied by the subcontractor for use in carrying out the Work.
- 1.4 If Downer becomes aware that a subcontractor is entitled to suspend work under section 27 of the Security of Payment Act, Downer may pay the subcontractor such money that is, or may be, owing to the subcontractor for work forming part of the Work and Downer may recover any amount paid as a debt.
- 1.5 The Subcontractor shall indemnify Downer against any loss, expense or damage of any nature, including financial loss and legal costs on an indemnity basis, suffered or incurred by Downer arising out of or in connection with:
 - (a) a suspension by a subcontractor of work, which forms part of the Work, under section 27 of the Security of Payment Act;
 - (b) a notice of claim being served on Downer under Part 2 of the Contractors Debts Act;
 - (c) a subcontractor exercising a statutory lien, under section 11(3) of the Security of Payment Act, over unfixed plant or materials supplied by the subcontractor for use in carrying out work forming part of the Work; or
 - (d) a failure by the Subcontractor to comply with this clause.
- 1.6 If Downer is served with a payment withholding request under section 26A of the Security of Payment Act by a subcontractor or any other party in connection with any work carried out or material supplied by the Subcontractor to Downer forming part of the Work and Downer consequently retains money that is or becomes payable by Downer to the Subcontractor under this Subcontract:
 - (a) Downer is not in breach of its payment obligations under this Subcontract as a result only of the retention of such money in such circumstances; and
 - (b) the Subcontractor waives its rights and releases Downer from liability in respect of all losses or expenses of any nature suffered or incurred by the Subcontractor, and may not terminate, rescind or treat as repudiated the Subcontract arising out of or in connection with Downer retaining such money in such circumstances.
- 1.7 For the purposes of this clause:
 - (a) "Contractors Debts Act" means the Contractors Debts Act 1997 (NSW).
 - (b) "Security of Payment Act" means the Building and Construction Industry Security of Payment Act 1999 (NSW);
 - (c) "subcontractor" means any person engaged by the Subcontractor, its Secondary Subcontractors or any other person to do work, which forms part of the Work; and
 - (d) **"work**" refers to work which the Subcontractor is, or may be, required to do under this Subcontract and includes equipment, materials, plant, design and other services and temporary works.

Re: WLS Contract

From:	Andrew <gayedwork@gmail.com></gayedwork@gmail.com>
То:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
Date:	Tue, 27 Jul 2021 06:24:55 +1000
Attachments:	Unnamed Attachment (68 bytes); Unnamed Attachment (68 bytes); image001.png (18.04 kB); image002.png
	(11.12 kB); image001.png (18.04 kB)

Hi Mal

Just a couple of points:

SC46: Teambinder is the authorized document management system for the Project. The Subcontractor will be given user access (for a smsoall number of nominated personnel) to the Project on Downer Teambinder system for sending and receipt of contract correspondence and documentation. Notices, contract correspondence and documentation will not be acknowledged if sent via Microsoft Outlook or other electronic mail based system.

Have they been issuing you correspondence via teambinder?

Also, the most important point:

Schedule 1B - pricing schedule.

Specifically says above the table of rates : 'pricing schedule lump sum'.

It also says below the table of rates

'the quantities provided are indicative only'.

Tell Downer, you were provided the quantities but were told it was a lump sum contract and all the line items were required to be filled for claiming.

If they want to reduce 1 line item, they need to increase another because it's a lump sum contract.

Also note, section 14 of the Security of payment act states that after you submit your progress claim, Downer is to submit a payment schedule. That was the time to bring up any reduced payments.

Call me if you're free today.

Regards Andrew

On Mon, 26 Jul 2021, 1:33 pm Mal Helweh, <<u>mal@maizegroup.com.au</u>> wrote:

Regards,

Mal Helweh

Phone: (02) 9773 1027

Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

Notification of Invitation to Tender - Building Works - Hazelbrook

From: To:	Scott Harman <tap3@tbupload.com></tap3@tbupload.com>
Date:	Mal Helweh <mal@maizegroup.com.au> Mon, 11 Feb 2019 10:55:59 +1100</mal@maizegroup.com.au>
Attachments:	Unnamed Attachment (68 bytes)

Could not load the company logo.

INVITATION TO TENDER

Package **Building Works - Hazelbrook** Title: Project TAP 3 Title: Scheduled 05 February 2019 Tender Closina Date: Scheduled 05:00 PM +11:00 Tender Closina Time:

The following Tender Package has been released. A copy of the tender document(s) can be obtained from the TenderDocs website.

Click here to acknowledge the package

Notification	N-0004308
Number: Project	TAP3
Number: Package	BD1078.001
ID: Date Sent:	11 February 2019

Message:

Dear Tenderers,

Downer EDI wishes to invite you to tender for Building Works at Hazlebrook Station under the Transport Access Program (TAP 3).

We request that you sign and return the NDA as soon as practicable if you are interested in quoting for these works.

All returnable schedules are to be submitted through teambinder by 5th February 2019.

Please reach out to myself or Sina Bigdeli if you have any questions.

Many thanks,

Scott Harman

Hard copies of documents can be obtained from: Scott Harman, Downer IPD

Click here to launch the TenderDocs website

Login Details

User Id: MMAIZE

Company ID: MAIZEBUILD

Password: You can use your previous login details to access the Tender Packages.

The following document(s) were issued for Tender.

Item	Document No	Rev	Sts	Title
1	TAP3-DOWIPD-BD1078.001-	-	IFT	00 Request for Tender - Building Works - Hazelbrook

	PRP-CI-0001			E19-1595-AS-2-279-PR-0001
2	TAP3-DOWIPD-BD1078.001- QUO-CI-0001	A	IFT	Attachment 13 - Hazelbrook Building Works - Returnable Scedule (Price)
3	TAP3-DOWIPD-BD1078.001- SOW-CI-0001	-	IFT	Attachment 01 - Scope of Works - Hazelbrook - BD1078.001 - Building Works
4	TAP3-DOWIPD-BD1078.004- RPT-XX-0001	-	IFT	Attachment 17 - Hazardous Material Rpt- Hazelbrook
5	TAP3-DOWIPD-BD1078.004- RPT-XX-0002	-	IFT	Attachment 18 - Waste Clarification - Hazelbrook
6	TAP3-DOWIPD-LV1078.001- DRG-XX-0001	2	IFT	Attachment 05 - Hazelbrook Drawings and Specifications
7	TAP3-DOWIPD-LV1078.001- RPT-GE-0001	0	IFT	Attachment 10 - Geotechnical Factual Report - Hazelbrook
8	TAP3-DOWIPD-TD.000-AGR- XX-0001	1	IFT	Attachment 02 - Subcontract Agreement (Long Form)
9	TAP3-DOWIPD-TD.010-AGR- XX-0001	1	IFI	Attachment 14 - Confidentiality & Non-Disclosure Agreement
10	TAP3-DOWIPD-TD.010-PRP- XX-0002	1	IFI	Attachment 12 - Return Sch Non-Price
11	TAP3-DOWIPD-TD.010-REF- XX-0001	1	IFI	Attachment 07 - Possession dates
12	TAP3-DOWIPD-TD.010-REF- XX-0005	1	IFI	Attachment 08 - Exhibit E Contract Spec. Req - Hazelbrook
13	TAP3-DOWIPD-TD.010-REF- XX-0006	1	IFI	Attachment 09 - TfNSW Works Brief
14	TAP3-DOWIPD-TD.010-REF- XX-0007	0	IFI	Attachment 11 - Sustainability Guideline - TBA
15	TAP3-DOWIPD-TD.010-REF- XX-0011	1	IFI	Attachment 15 - Station Spec. Req 1078-HB
16	TAP3-DOWIPD-TD.010-REF- XX-0012	1	IFI	Attachment 16 - Teambinder User Guide
17	TAP3-DOWIPD-TD.010-STD- XX-0001	1	IFI	Attachment 03 - Subcontractor Management Pack
18	TAP3-DOWIPD-TD.010-STD- XX-0002	1	IFI	Attachment 06 - TfNSW Standard Requirements
19	TAP3-DOWIPD-TD23-PGM-CI- 0001	-	IFT	Attachment 04 - Program & Delivery Schedule HB.

Issued By: Scott Harman Downer IPD

This notification was generated by TeamBinder © 2001 - 2019 QA Software Pty Ltd

Attachments:




E19-1595-AS-2-279-PR-0001





11 Feb 2019 at 8:53 am



. 5G EB

11 Feb 2019 at 11:06 am

Hey bro, I got an email from Downer about Hazelbrook? When you get a chance to talk, call me and I'll discuss. Thanks

20 Feb 2019 at 12:35 pm

Hey bro, how's the court case going? Let me know when you have time to talk thanks

20 Feb 2019 at 3:04 pm

Hey Mal, sorry just got out. Call me when you're free

21 Feb 2019 at 10:23 am

Hang Up Message: 0815 reached your MessageBank on 21/02/2019 at 10:23 & did not leave a message.

Vol 26.1

21 Feb 2019 at 1:23 pm

192



21 Feb 2019 at 1:23 pm

Do I email the price or through the portal? I can't find how to submit through portal if that's how it's supposed to be done

Email to: Scott.harman@downergroup com And. <u>Sina.bigdeli@downergroup.com</u>

21 Feb 2019 at 2:59 pm

In a meeting, I'll call you back

Tender date now 4th March Iol

Lol clowns. No one responded


Should I still submit or wait until the 4th to see who else submitted? That way I can look at the addendum too

I'm still submitting.

0.

193

0



Hazelbrook

From:Mal Helweh <mal@maizegroup.com.au>To:Andrew Gayed <andrew@mansionbuilding.com.au>Date:Wed, 20 Feb 2019 16:31:36 +1100Attachments:Price Schedule.xlsx (41.95 kB)

Regards, Mal Helweh



Phone: (02) 9773 1027

Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

Cop	of	hice	+Schedule	
-----	----	------	-----------	--

Downer	
Domici	
Price Schedule - Building Works	
BD 1078.001	

To tenderers: Mease complete all sections of the below schedule

							Clarifications / not included
el tiem	Sil description	Unit B	Lovantity Rate			Downer	
ni bem 1581 2582	<u>Bil description</u> Preliminaries Mobilisation of plant,	13 13	<u>55000</u> 30000	1	55,000 30,000	Downer.	
3 5 8 3	equipment, labour and materials Waste disposal	5	13200	1	13,200		No skip bin and / or hi-rail
4 5.8.4	Construction plant and equipment	13	17000	,	17,000		oflowed for. Matte to use Downer upplied kilos No skip bin and (or N-call oflowed dic. Matte to use
	FAC7 Station Building 5020 Buildings - General						Downer uppfied skips
5 (1 4.19.1.3.)	Demolition Decommission, relocate, nemove, permonenthy or temporarily, and disposid al all existing fam and associated dutos and electricat boards etc., doarn, walt, finitias fix hares, apparatus etc., form openings as redundart by the works or innoder to		3651	1.00	3,631	5,107	
2 4.19.1.3.2	undertake the works Demolish and level the toilet floors and door	- 15	25530	1	25,530		
3 4.19.1.3.3	landing as specified Remove existing brick privacy screen at		14970	1	14.970	70350 Need to break dow n	Removal of footing
4 4.19.1.3.4	male tailet	5	1800	1.00	1,800	5,107	Removal of footing
iá 4.19.1.4.1	disconnect for demolition works Construct penetration for underground services entry point into fiemde toilet to connect to new CSR	15	4210		٥	4,350	not including freezing
4 11 4.19:1.7.1	Construction (as required) Prepare subgrade, blindings & WPM	m2	395	43	0 16,985	19,782 45m²	
2 4.19.1.7.2	32MPa concrete in stab on ground to interno rooms		1600	7.60	12,140	19,232 8m ⁴	
3 4.19.1.7.3 4 4.19.1.7.4	Isolationjoint Dow el joint	Item Item	500 RATE ONLY 500 RATE ONLY			1,332 840	
.5 4.19.1.7.5 .6 4.19.1.8.1	Surface finish Formw ork slab edge	m2 m	350 RATE ONLY 120 RATE ONLY			2,520	
.7 4.19.1.9.1 18 4.19.1.10.2	Reinforcement to slab, \$282 mesh Make good existing (assumed brickwork) external w als where platform level is	m2 m	45 150	43 49	2,795 7,350	3,938 45m² 9,100 52 LM	
9 4.19.1.10.3	changed, to match existing w alls above Make good existing internal w alls where ff	t m	249	48	11,952	13,440 48 LM	No new brick allow ed
10 4.19.1.10.4	is changed, to match existing walls above Adjust threshold step to door at change in	lard	1200	3	3,600	2.100 3 leafs	
11 4.18 1.11.1	floor level Close up existing window, leaving external		800	4.00	3,200	4,491 4 w indows	No stone or tile w ork allow ed for
	untouched, fire rate infit on the inside	-					No brickwork allow edifor. Also 60/60/60 fire rated firecheck allow edifor
12 4.19.1.12.1 13 4.19.1.12.2	face brick screen w all footh into existing masorry w all	m2 m			0	6,252 14m²	Not allow ed for as not noted on drawings provided Not allow ed for as not noted on drawings provided
14 4.19.1.13.1 15 4.19.1.13.2	Stud frame internal w alls Stud frame internal riser w alls	m2 m2			0		How many metrics?
16 4.19.1.13.3 17 4.19.1.14.1	Stud frame internal false w all Wall insulation	m2 m2	140 28	92 92	12,880 2,576	19,550 95m² 3,990 95m²	
18 4.19.1.14.2 19 4.19.1.16.1	Celling insulation - extent tbc fibre cement w all inings to framed w alls	m2 m2	28	78	2,184	3,276 78m²	How many matrix 9
20 4.19.1.16.2	Reline existing internal walls for new finish- allow fibre cement with botten frame or	m2	140	92	12,880	18,875 107m²	
21 4.19.1.16.3	cernent render Two hour fire rated wall to inside face of new Walting room: allow frame, shaft liner or functions.	m2	320	ы	20,480	27,300 45m²	
22 4.19.1.17.1	Two hour fire rated ceiling with corrice/trim	n m2	350	19	6,650	7,980 19m²	Allow ance for Y0mm standard corrice fire rated and trims
23 4.19.1.17.2	Suspended plasterboard ceiling with corrice/trims	m2	250	17	4,250	4,740 17m²	Allow ance for 90mm standard corrice and trims
9 4.19.1.18.1 5 4.19.1.18.2	Permonently close existing door Single leaf 2 hour HS, fire doorset complete	No. No.	250 2250	1	250 2,250	148 1 door 2,800 1 door	Allow ance to permanently close existing door by keeping original door
6 4.19.1.18.3	with hardw are Single leaf external grade doorset complete		1850 RATE ONLY				
7 412.1.18.4	with hardw are Extra Over door for translucent glazed pane		1175 RATE ONLY				How many R
8 4.19.1.18.5	in door - assume 450 x 600 mm high Remove door, low er door opening to suit	No.			0		
9 4.19.1.18.6	new FR, reinst all existing doorset complete with hardw ore Remove door, low er door opening to suit new FR, entarge opening to provide 850mm clear door leaf opening, new single leaf external grade doorset complete with	No.	4555	2.00	9,110	8,918 2 doors	Dow net to clarify as existing door will not w ark with new height as door opening will be Higher due to drop in
30 4.19.1.19.3	hardware Privacy film to existing windows	m2	250 RATE ONLY				Dow ner to clarify which doors to be installed. No allow nace for heritage or architectual doors
1 4.19.1.20.1	Waterproofing to wet area floors, upturn 1500mm above floor	m2	85	55	4,840	4,948 51m²	UPVCW at eproofing allow ed for. No angles or trims allow ed
2 4.19.1.21.1	Wall tiling to wet areas - Glernon Bes W310 300 x 100mm with epoxy grout	0 m2	350	71	24,850	24,111 49m²	
3 4.19.1.21.2	Roar tiling to wet areas - Glermon Tiles GN13140 600 x 300mm with epox y grout	m2	370	26	9,620	14,473 26m²	
H 4.19.1.21.3	Coved skirting tiling to wet areas - Glennon Bes to match floar tiles with epoxy grout	-	350	23	8,050	5,121 23 LM	
85 4.19.1.21.4	Roar tiling to waiting room - Glennon Tiles	m2	370 RATE ONLY				
6 4.19.1.21.5	GN13140.600 x 300mm with epoxy grout Skirting tiling to waiting room - Glernon Ties		350 RATE ONLY				How many metres?
37 4.19.1.21.6	to matchfloor tiles with epoxy grout Preshold tile	-	750	3	2,250	1,680 31M	How many metner# Glemnontile allow ed for. No stone
88 4.19.1.22.1	Roar preparation to existing floor for new viny I flooring		35	20	700	298 19m²	If there is floor prep, where is the viry! to be laid?
39 4.19.1.25.1	Hand dryer - Dyson Airblades V Code AB12 white				0	2,093 1 of	Provisional Item Cost. Item plus 15%
40 4.19.1.25.2 41 4.19.1.25.3	Toilet Roll Holder - 88A Group 82730 SS grabrails to staff ambulant W C	No. No.			0	333 1 of 910 1 of	Provisional Hern Cast. Hern plus 15% Provisional Hern Cast. Hern plus 15%
42 4.19.1.25.4	Soap Disperser - Kimberley Clark Aquarka Hand Cleanser Dispenser White/1 litre 69480	No.			0	145 1 of	Provisional Herr Cost. Herr plus 15%
43 4.19.1.25.5 44 4.19.1.25.6	Coat hook - \$\$\$Mettam ML4159 Aluminium framed \$\$minor, secured to concealed w all hanger with theft resistant	No. No.			0	85 1 of 1,050 1 of	Provisional Ham Cast, Hempliki 135 Provisional Ham Cast, Hempliki 135
	mounting equal to Babrick - 1000H x 350W						Provisional Herm Cast. Hermplus 15%
5 4.19.1.26.1	Hand dryer - Dyson Airbiades V Code AB12 white Todal Ball Moldar, IBIA Course 8770				0	2,093 1 of 333 1 of	Provisional Hern Cast. Hernplus 15% Provisional HernCast. Hernplus 15%
6 4.19.1.26.2 7 4.19.1.26.3 8 4.19.1.26.4	Tailet Roll Haider - RBA Group 82730 SS grabrails to FATW C Scop Dispenser - Kimberley Clark Aquarius	No. No.			0	333 1 of 1,120 1 of 145 1 of	Provisional Hern Cast. Hern plus 15% Provisional Hern Cast. Hern plus 15%
	Sodp Uniperser - Almoenery Clark Aquatia Hand Cleanser Dispenser White/1 litre 49480						Provisional Hern Cost. Hernplus 15%
9 4.19.1.26.5	Baby Change Table - Mettam Foldable - Cod ML9100EH	le No.			0	1,330 1 of	Provisional Herr Cost. Herr alus 195
0 4.19.1.26.6 i1 4.19.1.26.7	Aurrinium framed S3 mitror, secured to conceptied with the free secured to conceptied with hord resistant mounting equal to Babrick - 1000H x 600W	No. No.			0	85 1 of 1,050 1 of	Provisional Herri Loor, Herrigha 135 Provisional Herri Cost, Herrigha 135
0 4 19 1 26 8		No.			0	749 1 of	Provisional Hern Cast. Hernplus 15%
12 4.19.1.26.8 13 4.19.1.26.9	Sanitary bin-Canon Hygeine SS Modesty Iray Nappy disposal bin-Canon Hygeine nappy				0	749 1 of	Provisional Hern Cast. Hern plus 15%
3 4.19.1.26.9	disposal bin Sharas bin firstalled at existing toilets at	No.			0	/~/ 101	Provisional Hern Cost. Hern plus 15%
6 4.19.1.28.1	other stations - not scheduled - no allow ance) fire Extinguisher	No.			0	448 1 of	Provisional Herm Cost. Hermplus 15% Provisional Herm Cost. Hermplus 15%
7 4.19.1.30.1	Relocate existing access ramp cupboard		500	2	1,000	952 2 of	No allow ance to repair cupboard if pre-existing damage dane. Also new location to be confirmed by Dow ne
9 4.19.1.33.2	Internal walls linings Internal ceiling linings	m2 m2	44	110	4,840	4,038 103m² 1,714 36m²	This price is for painting as we have already allow ed for wall linings above. Allow ance for 1 primer, 21op coats This price is for painting as we have already allow ed for wall linings above. Allow ance for 1 primer, 21op coats
s0 4.19.1.33.3 s1 4.19.1.33.4	Single leaf external grade doorset Internal window s	No. m2	400	4	1,600	1,344 4 of 595 5m²	This price is for painting as we have already allowed for doors above. Allow ance for 1 primer, 21 op coats. Pain This price is for painting as we have already allowed for windows above. Allow ance for 1 primer, 21 op coats.
2 4.19.1.34.1	W all tiling to w et areas - Glennon Bes 1725 600 x 300mm with epoxy grout		60	71	4,260	3,478	Arti grafiti paint - 1 cost allow ed for
3 4.19.1.34.2 4 4.19.1.34.3	Internal painted w all Door leaf	m2 No.	60 RATE ONLY 250	r 3	750	998 3 of	Arti grafiti paint - 1 coat allow ed for Arti grafiti paint - 1 coat allow ed for
5 4.19.1.35.1 6 4.20.3.1.1	Door signage as required (per door) Sew er - allow ance to modify existing in	No. Item	357 23455	7 1.00	2,499 23,455	1,548 7 of 21,280	
7 4.20.3.1.2	ground sew or to suit new layout Water - allow ance to modify existing wate	er item	4850	1.00	4,850	5,600	No allow ance for sew er w arks outside the vicinity of the new toilets. Any w orks on platform to be done by a
8 4.20.3.1.1.1	to suit new layout WC	No.	7000	3.00	21,000	18,900	No allow ance for chasing and work outside vicinity of tailets
9 4.20.3.1.1.2	Basin Roarwaste	No. No.	5000 500	2.00 1.00	10,000 500	18,900 5,040	Only 1 noted on architectual drawings in FA1
70 4.20.3.1.1.3			1100	2	2,200	2,310	
9 4.20.3.1.1.3 71 4.20.3.1.1.4 83 4.23.2.1.2 94 4.23.2.1.3	Tap Mechanical exhaust to ambulant WC Mechanical exhaust to FAT ADJU STMENTS	No. Item Item	5800	1.00	5,800 5,800	6,300 6,300	

433,927 **428,764** 1.3 \$ 564,105.10 Paint as perspecs Paint as perspecs as perspecs

Re: Hazelbrook

From:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
То:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
Date:	Thu, 21 Feb 2019 09:32:25 +1100

Looks good, I'll show you what I'll send around midday.

Add these to your exclusions list:

Exclusions:

- 1. Hazardous material removal (asbestos, lead etc.)
- 2. Hi-rail plant
- 3. Craneage
- 4. Scaffolding
- 5. CC/BCA certification
- 6. Temporary works design/certification
- 7. Liaising with Sydney Trains/TfNSW
- Service searching/locating/NDD
 Service relocation (other than shown on drawings)
- 10. Survey
- 11. Heritage works 12. Out of hours work
- 13. GST
- 14. Site sheds/ablutions/laydown area15. Waste disposal/skip bins
- 16. Earthing/bonding
- 17. Welding 18. Delays/hold ups outside of Maize's control
- 19. Retention in contract

On Wed, Feb 20, 2019 at 4:31 PM Mal Helweh <<u>mal@maizegroup.com.au</u>> wrote:

Regards, Mal Helweh



Phone: (02) 9773 1027

Email: mal@maizegroup.com.au

Website: www.maizegroup.com.au

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at info@maizegroup.com.au or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

Hazelbrook Quote

From:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
То:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
Date:	Thu, 21 Feb 2019 13:28:28 +1100
Attachments:	Hazelbrook Building Tender - Downer1.docx (85.9 kB)

This is what I'm going to put through

Andrew Gayed Mansion Building Pty Ltd P: (02) 9606 6206 M: 0 815 E: a @mansionbuilding.com.au



QUOTATION

Downer Group

Tap 3 Project – Hazelbrook

Attention: Mr Scott Harman

Dear Sir,

We are pleased to submit our offer for Hazelbrook Station Building Upgrade works.

Our offer is **\$743,500 + GST**.

Inclusions:

ltem	Description
	Decommission, relocate, remove, permanently or temporarily, and disposal of all existing fans and associated dutcs and electrical boards etc., doors, walls, finishes, fixtures, apparatus etc., form openings as required/specified which are made
1	redundant by the works or in order to undertake the works
2	Demolish and level the toilet floors and door landing as specifed
3	Remove existing brick privacy screen at male toilet
4	Hydraulic Services : cap off & temporary disconnect for demolition works
5	Construct penetration for underground services entry point into Female toilet to connect to new CSR
6	Prepare subgrade, blindings & WPM
7	32MPa concrete in slab on ground to internal rooms
8	Isolation joint
9	Dowel joint





10	Surface finish
11	Formwork slab edge
12	Reinforcement to slab, SL82 mesh
13	Make good existing (assumed brickwork) external walls where platform level is changed, to match existing walls above
14	Make good existing internal walls where FFL is changed, to match existing walls above
15	Adjust threshold step to door at change in floor level
16	Close up existing window, leaving external untouched, fire rate infill on the inside
17	Face brick screen wall
18	Tooth into existing masonry wall
19	Stud frame internal walls
20	Stud frame internal riser walls
21	Stud frame internal false wall
22	Wall insulation
23	Ceiling insulation - extent tbc
24	Fibre cement wall linings to framed walls
25	Reline existing internal walls for new finish - allow fibre cement with batten frame or cement render
26	Two hour fire rated wall to inside face of new Waiting room : allow frame, shaft liner or Fyrcheck
27	Two hour fire rated ceiling with cornice/trims
28	Suspended plasterboard ceiling with cornice/trims
29	Permanently close existing door
30	Sinlge leaf 2 hour FRL fire doorset complete with hardware
31	Single leaf external grade doorset complete with hardware
32	Extra Over door for translucent glazed panel in door - assume 450 x 600 mm high
33	Remove door, lower door opening to suit new FFL, reinstall existing doorset complete with hardware





34	Remove door, lower door opening to suit new FFL, enlarge opening to provide 850mm clear door leaf opening, new single leaf external grade doorset complete with hardware
35	Privacy film to existing windows
36	Waterproofing to wet area floors, upturn 1500mm above floor
37	Wall tiling to wet areas - Glennon Tiles W310 300 x 100mm with epoxy grout
38	Floor tiling to wet areas - Glennon Tiles GN13140 600 x 300mm with epoxy grout
39	Coved skirting tiling to wet areas - Glennon Tiles to match floor tiles with epoxy grout
40	Floor tiling to waiting room - Glennon Tiles GN13140 600 x 300mm with epoxy grout
41	Skirting tiling to waiting room - Glennon Tiles to match floor tiles with epoxy grout
42	Threshold tile
43	Floor preparation to existing floor for new vinyl flooring
44	Relocate existing acccess ramp cupboard
45	Internal walls linings
46	Internal ceiling linings
47	Single leaf external grade doorset
48	Internal windows
49	Wall tiling to wet areas - Glennon Tiles F725 600 x 300mm with epoxy grout
50	Internal painted wall
51	Door leaf
52	Door signage as required (per door)
53	Sewer - allowance to modify existing in ground sewer to suit new layout
54	Water - allowance to modify existing water to suit new layout
55	WC
56	Basin
57	Floor waste
58	Тар
59	Mechanical exhaust to ambulant WC
60	Mechanical exhaust to FAT





61	SWMS/Management Systems
62	RIW inducted tradesmen
63	Project management
64	Fortnightly meeting attendance
65	All materials and labour to complete the above

Exclusions:

-	
1	Hand dryer - Dyson Airblades V Code AB12 white
2	Toilet Roll Holder - RBA Group B2730
3	SS grabrails to staff ambulant WC
4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480
5	Coat hook - SSS Metlam ML4159
6	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 350W
7	Hand dryer - Dyson Airblades V Code AB12 white
8	Toilet Roll Holder - RBA Group B2730
9	SS grabrails to FAT WC
10	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480
11	Baby Change Table - Metlam Foldable - Code ML9100EH
12	Coat hook - SSS Metlam ML4159
13	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 600W
14	Sanitary bin - Canon Hygeine SS Modesty tray
15	Nappy disposal bin - Canon Hygeine nappy disposal bin
16	Sharps bin (installed at existing toilets at other stations - not scheduled - no allowance)
17	Fire Extinguisher





18	Hi-Rail vehicles (including for material delivery)
19	Craneage
20	Certification services
21	Asbestos and lead paint removal (including hygienist reports)
22	Survey
23	Heritage works and/or reports
24	Waste disposal (to be taken to Downer designated location within 300m of work area)
25	Out of hours work (Standard work hours are 7am to 3pm Mon-Fri, 8am to 1pm Sat)
26	Retention and/or liquidated damages

Please feel free to call if you have any queries.

King Regards,

Andrew Gayed



RE: Hazelbrook Quote

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	Andrew Gayed <andrew@mansionbuilding.com.au></andrew@mansionbuilding.com.au>
Date:	Thu, 21 Feb 2019 13:56:20 +1100
Attachments:	TAP3-DOWIPD-BD1078.001-QUO-CI-0001.A.IFT.xlsx (41.23 kB); 524.pdf (105.93 kB)

This is what im sending:

"Hi Scott, Please find attached Price Schedule and Quote attached.

If the price is right, I can start sending off the other documents as per tender requirements" Good? Regards,

Mal Helweh



GROUP PTY LTD

Phone: (02) 9773 1027 Email: <u>mal@maizegroup.com.au</u> Website: <u>www.maizegroup.com.au</u>

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at info@maizegroup.com.au or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you. From: Andrew Gayed <andrew@mansionbuilding.com.au>
Sent: Thursday, 21 February 2019 1:28 PM
To: Mal Helweh <mal@maizegroup.com.au>
Subject: Hazelbrook Quote

This is what I'm going to put through

Andrew Gayed

Mansion Building Pty Ltd P: (6 6206 M: 0 815 E: a @mansionbuilding.com.au



Price Schedule - Building Works BD 1078.001

rel Bern 158.1	Bill description Preliminaries	<u>Unit</u> 15	<u>Bill quantity</u> <u>Rate</u> 97540	1	<u>Ameunt</u> 97,540
2 5.8.2	Preliminaries Mobilisation, demobilisation of plant, equipment, labour and materials	15	88000	1	97,540 88,000
5.8.3	Waste disposal	LS	26440	1	26,440
5.8.4	Construction plant and equipment	LS	36750	1	36,750
	PAC7 Station Building				0
5	5020 Buildings - General Demolition				0
.1 4.19.1.3.1	Decommission, relocate, removie, permanently or temporarily, and disposal of	LS	4251	1.00	4,251
	all existing fans and associated dutes and electrical boards etc., doors, walls, finishes,				
	fixtures, apparatus etc., form openings as required/specified which are made				
	redundant by the works or in order to undertake the works				
5.2 4.19.1.3.2	Demolish and level the toilet floors and door landing as specified		38530	1	38,530
5.3 4.19.1.3.3	Remove existing brick privacy screen at male toilet	LS	16970	1	16,970
5.4 4.19.1.3.4	Hydraulic Services : cap off & temporary disconnect for demolition works	LS	3200	1.00	3,200
5.6 4.19.1.4.1	Construct penetration for underground services entry point into Female tallet to	LS	4210	1.00	4,210
6	connect to new CSR Construction (as required)				0
5.1 4.19.1.7.1 5.2 4.19.1.7.2	Prepare subgrade, blindings & WPM 32MPa concrete in slab on ground to	m2 m3	405 1600	43 7.60	17,415 12,160
6.3 4.19.1.7.3	internal rooms Isolation joint	Item	500 RATE ONLY		
.4 4.19.1.7.4 .5 4.19.1.7.5	Doweljoint Surface finish	ltem m2	500 RATE ONLY 350 RATE ONLY		
.6 4.19.1.8.1 .7 4.19.1.9.1	Formwork slab edge Reinforcement to slab, SL82 mesh	m m2	120 RATE ONLY 65	43	2,795
.8 4.19.1.10.2	Make good existing (assumed brickwork) external walls where platform level is	m	150	49	7,350
5.9 4.19.1.10.3	changed, to match existing walls above Make good existing internal walls where FFL	m	249	48	11,952
19 4.19.1.10.3	is changed, to match existing walls above				
	Adjust threshold step to door at change in foor level	leaf	1200	3	3,600
11 4.19.1.11.1	Close up existing window, leaving external untouched, fire rate infill on the inside		900	4.00	3,600
12 4.19.1.12.1 13 4.19.1.12.2	Face brick screen wall Tooth into existing masonry wall	m2 m			0
14 4.19.1.13.1 15 4.19.1.13.2	Stud frame internal walls Stud frame internal riser walls	m2 m2			0
16 4.19.1.13.3 17 4.19.1.14.1	Stud frame internal false wall Wall insulation	m2 m2	160 30	92 92	14,720 2,760
17 4.19.1.14.1 18 4.19.1.14.2 19 4.19.1.16.1	Ceiling insulation - extent tbc	m2 m2 m2	30	92 78	2,760 2,340
19 4.19.1.16.1 20 4.19.1.16.2	Fibre cement wall linings to framed walls Reline existing internal walls for new finish -	m2 m2	155	92	0 14,260
	allow fibre cement with batten frame or cement render				
21 4.19.1.16.3	Two hour fire rated wall to inside face of new Walting room : allow frame, shaft liner or	m2	365	64	23,360
22 4.19.1.17.1	Pyrcheck Two hour fire rated ceiling with comice/trims		350	19	6,650
23 4.19.1.17.2	Suspended plasterboard celling with comice/trims	m2	250	17	4,250
24 4.19.1.18.1 25 4.19.1.18.2	Permanently close existing door Sinige leaf 2 hour FRL fire doorset complete	No. No.	250 2550	1	250 2,550
26 4.19.1.18.3	with hardware		1850 RATE ONLY	1.00	2,550
	Single leaf external grade doorset complete with hardware				
27 4.19.1.18.4	Extra Ov er door for translucent glazed panel in door - assume 450 x 600 mm high	No.	1175 RATE ONLY		
28 4.19.1.18.5	Remove door, lower door opening to suit new FFL, reinstall existing doorset complete	No.			0
29 4.19.1.18.6	with hardware Remove door, lower door opening to suit	No.	4555	2.00	9,110
	new FFL, enlarge opening to provide 850mm clear door leaf opening, new single leaf				
	external grade doorset complete with hardware				
30 4.19.1.19.3 31 4.19.1.20.1	Privacy film to existing windows	m2 m2	250 RATE ONLY 88	55	4.840
	Waterproofing to wet area floors, upturn 1500mm abov e floor				
32 4.19.1.21.1	Wall tiling to wet areas - Glennon Tiles W310 300 x 100mm with epoxy grout		350	71	24,850
33 4.19.1.21.2	Roar tiling to wet areas - Glennon Tiles GN13140 600 x 300mm with epoxy grout	m2	380	26	9,880
34 4.19.1.21.3	Covied skitting tilling to wet areas - Glennon Tiles to match floor tiles with epaxy grout	m	350	23	8,050
35 4.19.1.21.4	Roor tiling to waiting room - Glennon Tiles GN13140 600 x 300mm with epoxy grout	m2	380 RATE ONLY		
36 4.19.1.21.5		m	350 RATE ONLY		
37 4.19.1.21.6	Threshold file	m	750	3 20	2,250
38 4.19.1.22.1	Roar preparation to existing floor for new viny! flooring	m2	35	20	700
39 4.19.1.25.1	Hand dryer - Dyson Airblades V Code AB12 white				0
40 4.19.1.25.2 41 4.19.1.25.3	Tollet Roll Holder - RBA Group B2730 SS grabrails to staff ambulant WC	No. No.			0
42 4.19.1.25.4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 lifre 69480	No.			0
43 4.19.1.25.5 44 4.19.1.25.6	Coat hook - SSS Metlam ML4159 Aluminium framed SS mirror, secured to	No. No.			0
	concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 350W	-			·
45 4.19.1.26.1	Hand dryer - Dyson Airblades V Code AB12	No.			0
46 4.19.1.26.2	white Tollet Roll Holder - RBA Group B2730	No.			0
47 4.19.1.26.3 48 4.19.1.26.4	SS grabrails to FAT WC Soap Dispenser - Kimberley Clark Aquarius	No. No.			0
49 4.19.1.26.5	Hand Cleanser Dispenser White/1 litre 69480 Baby Change Table - Metiam Foldable -	No.			0
50 4.19.1.26.6	Code ML9100EH Coat hook - SSS Metlam ML4159	No.			0
51 4.19.1.26.7	Auminium framed SS mirror, secured to concealed wall hanger with theft resistant	No.			0
52 4.19.1.26.8	mounting equal to Bobrick - 1000H x 600W Sanitary bin - Canon Hygeine SS Modesty	No.			0
53 4.19.1.26.9	tray				
53 4.19.1.26.9	Nappy disposal bin - Canon Hygeine nappy disposal bin				
ae e.19.1.26.10	Sharps bin (installed at existing toilets at other stations - not scheduled - no	No.			0
56 4.19.1.28.1	allowance) Fire Extinguisher	No.			0
57 4.19.1.30.1 58 4.19.1.33.1	Relocate existing acccess ramp cupboard Internal walls linings		500 44	2 110	1,000
59 4.19.1.33.2 60 4.19.1.33.2	Internal ceiling linings	m2 No.	44 400	40	1,760
61 4.19.1.33.4	Single leaf external grade doorset Internal windows	m2	120	5	600
62 4.19.1.34.1	600 x 300mm with epoxy grout	m2	60	71	4,260
.63 4.19.1.34.2 .64 4.19.1.34.3	Internal painted wall Door leaf	m2 No.	60 RATE ONLY 250	3	750
65 4.19.1.35.1	Door signage as required (per door) Sewer - allowance to modify existing in	No. Item	357 23455	7	2,499 23,455
	ground sewer to suit new layout		5155	1.00	23,455
		item	5155	1.00	
.66 4.20.3.1.1	Water - allowance to modify existing water to suit new layout				
.67 4.20.3.1.2 .68 4.20.3.1.1.1 .69 4.20.3.1.1.2	Water - allowance to modify existing water to suit new layout WC Basin	No. No.	7000 5000	3.00 2.00	21,000 10,000
67 420.3.1.2 68 420.3.1.1.1 69 420.3.1.1.2 70 420.3.1.1.3 71 420.3.1.1.4	to sult new layout WC Basin Roor waste Tap	No. No. No.	5000 500 1100	2.00 1.00 2	10,000 500 2,200
	to suit new layout WC Basin Roor waste	No. No.	5000 500	2.00	10,000

No skip bin and / or hi-rail allowed for. Maize to use Downer supplied skips No skip bin and / or hi-rail allowed for. Maize to use Downer supplied skips

Clarifications

To tenderers: Please complete all sections of the below schedule

Removal of footing Not including freezing

No new brick allowed

No stone or file work allowed for No brickwork allowed for. Also 60/60/60 fire rated firecheck allowed for Not allowed for as not noted on drawings provided Not allowed for as not noted on drawings provided

Is it included in price line below?

Allowance for 90mm standard comice fire rated and trims Allowance for 90mm standard comice and trims

Allowance to permanently close existing door by keeping original door

UPVC Waterproofing allowed for. No angles or trims allowed

Glennon file allowed for. No stone If there is foor prep, where is the viny! to be laid ? Provisional Item Cost. Item plus 15% Provisional Item Cost. Item plus 15%

Anti graffiti paint - 1 coat allowed for Anti graffiti paint - 1 coat allowed for

Only 1 noted on architectual drawings in FAT

1. Hazardous material removal (asbestos, lead etc.) 2. Hi-rail plant 3. Graneage 4. Scaffolding

Exclusions:

No allowance for chasing and work outside vicinity of toilets

Allowance for exhaust fan only including labour. No metal ductwork allowed for Allowance for exhaust fan only including labour. No metal ductwork allowed for

Downer to clarify as existing door will not work with new heights as door opening will be higher due to drop in FFL

Provisional them Cast. Hem plus 18%. No adknowne to respect appboard if pe-easiting diamage done. Also new location to be confirmed by Downer. Alsowance for fait subcer mass that place is brapishing are have a elevaley adknowned for vali lineiga above. Allowance for 1 primer, 21 ap costs. Point as perspect that place is brapishing are have a elevaley adknowned for vali lineiga above. Allowance for 1 primer, 21 ap costs. Point as perspect that place is brapishing are have a elevaley adknowned two vali lineiga above. Allowance for 1 primer, 21 be costs. Point as perspect that place is brapishing are have a levaley adknowned two validations. Allowance to 1 primer, 21 be costs. Point as perspect his place is brapishing are levale ellevale adknowned was adknowned to 1 primer, 21 be costs. Point as perspect Are graditions 1... Card adknewned the validation adknown. Allowances to 1 primer, 21 be costs. Point as perspect

No allowance for sewer works outside the vicinity of the new toilets. Any works on platform to be done by others. No allowance to re-direct the fail if not matching to new location

when to clarify which doors to be installed. No allownace for heritage or architect

EMaize Group Pty Ltd

4/88 Violet St Revesby NSW 2212 Australia accounts@maizegroup.com.au www.maizegroup.com.au ABN: 11 169 460 379



Page 1 of 1

GROUP PTY LTD

Quote date: 21/02/2019

Quote

Bill to:	Expiry:
Downer	22/04/2019
Triniti Business Campus 39 Delhi Road	
North Ryde NSW 2113	

20

Australia

ITEM	DESCRIPTION		UNITS	UNIT PRICE (ex GST)	ΤΑΧ ΤΥΡΕ	AMOUNT (ex GST)
	As Per Pricing Schedule Attached	Qty	1	597,202.00	GST	597,202.00
					Total (ex GST): GST: TAL (inc GST):	\$597,202.00 \$59,720.20 \$656,922.20

Notes
Exclusions:
 Hazardous material removal (asbestos, lead etc.) Hi-rail plant Craneage Scaffolding CC/BCA certification Temporary works design/certification Temporary works design/certification Liaising with Sydney Trains/TfNSW Service searching/locating/NDD Service relocation (other than shown on drawings) Survey Heritage works Out of hours work
13. GST 14. Site sheds/ablutions/laydown area
15. Waste disposal/skip bins

- 16. Earthing/bonding
- 17. Welding
- 18. Delays/hold ups outside of Maize's control
- 19. Retention in contract
- 20. Addendum 1 Building Works (came out on last day, not enough time to price)

RE: Hazelbrook Station - Price Schedule & Quote

From:	Mal Helweh <mal@maizegroup.com.au></mal@maizegroup.com.au>
То:	Scott Harman <scott.harman@downergroup.com>, Sina Bigdeli <sina.bigdeli@downergroup.com></sina.bigdeli@downergroup.com></scott.harman@downergroup.com>
Date:	Fri, 22 Mar 2019 16:15:01 +1100
Attachments:	524a.pdf (106.47 kB); Price Schedule 2.xlsx (45.23 kB)

Hi Scott / Sina,

Please find Price Schedule and Quote attached. I have allowed for the Addendums.

You will notice I have allowed for the Mech Board and still the price is lower than before.

If the price is right, I can start sending off the other documents as per tender requirements.

If you have any questions please do not hesitate to contact me. Cheers

Regards,

Mal Helweh



Phone: (02) 9773 1027 Email: <u>mal@maizegroup.com.au</u> Website: <u>www.maizegroup.com.au</u>

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

From: Mal Helweh Sent: Thursday, 21 February 2019 4:19 PM To: 'Scott.harman@downergroup.com' <Scott.harman@downergroup.com>; 'sina.bigdeli@downergroup.com' <sina.bigdeli@downergroup.com> Subject: Hazelbrook Station - Price Schedule & Quote

Hi Scott / Sina,

Please find attached Price Schedule and Quote attached.

If the price is right, I can start sending off the other documents as per tender requirements.

If you have any questions please do not hesitate to contact me. Cheers

Regards,

Mal Helweh



Phone: (02) 9773 1027 Email: <u>mal@maizegroup.com.au</u> Website: <u>www.maizegroup.com.au</u>

This email is confidential and may also contain legally privileged information. If you are not the intended recipient, please contact the sender at <u>info@maizegroup.com.au</u> or call (02) 9773 1027 and do not use, disclose, copy, or distribute it to anyone. Confidentiality and legal privileges are not waived by reason of mistaken delivery to you.

EMaize Group Pty Ltd

4/88 Violet St Revesby NSW 2212 Australia accounts@maizegroup.com.au www.maizegroup.com.au ABN: 11 169 460 379



Page 1 of 1

Quote: 524a

GROUP PTY LTD

Quote date: 21/02/2019

Quote

Bill to:	Expiry:
Downer	22/04/2019
Triniti Business Campus 39 Delhi Road	
North Ryde NSW 2113	

70

Australia

ITEM	DESCRIPTION		UNITS	UNIT PRICE (ex GST)	ΤΑΧ ΤΥΡΕ	AMOUNT (ex GST)
	As Per Pricing Schedule Attached	Qty	1	589,602.00	GST	589,602.00
Sub-Total (ex GST): GST: TOTAL (inc GST):						

Notes

Exclusions:

- 1. Hazardous material removal (asbestos, lead etc.)
- 2. Hi-rail plant
- 3. Craneage
- 4. Scaffolding
- 5. CC/BCA certification
- 6. Temporary works design/certification
- 7. Liaising with Sydney Trains/TfNSW
- 8. Service searching/locating/NDD
- 9. Service relocation (other than shown on drawings)
- 10. Survey
- 11. Heritage works
- 12. Out of hours work
- 13. GST
- 14. Site sheds/ablutions/laydown area
- 15. Waste disposal/skip bins
- 16. Earthing/bonding
- 17. Welding
- 18. Delays/hold ups outside of Maize's control
- 19. Retention in contract

20. IMSB / All power and electrical except decommissioning / DB investigations / Only works that are stated on the Downer supplied schedule



To tenderers: Please complete all sections of the below schedule

Price Schedule - Building Works BD 1078.001

TOTAL: \$ 589,602.00

<u>ltem</u>	Bill description	<u>Unit</u>	<u>Bill</u> quantity		Rate		<u>Amount</u>	<u>Comments</u>
5.8.1	Preliminaries	LS	1	\$	93,550.00	\$	93,550.00	
5.8.2	Mobilisation, demobilisation of plant, equipment, labour and materials	LS	1	\$	84,000.00	\$	84,000.00	
5.8.3	Waste disposal	LS	1	\$	25,330.00	\$	25,330.00	No skip bin and / or hi- rail allowed for. Maize to use Downer supplied skips
5.8.4	Construction plant and equipment	LS	1	\$	32,650.00	\$	32,650.00	No skip bin and / or hi- rail allowed for. Maize to use Downer supplied skips
						\$	-	
	PAC7 Station Building					\$	-	
	5020 Buildings - General					\$	-	
	Demolition			-		\$	-	
4.19.1.3.1	Decommission, relocate, remove, permanently or temporarily, and disposal of all existing fans and associated dutcs and electrical boards etc., doors, walls, finishes, fixtures, apparatus etc., form openings as required/specified which are made redundant by the works or in order to undertake the works	LS	1	\$	4,251.00	\$	4,251.00	
4.19.1.3.2	Demolish and level the toilet floors and door landing as specifed	LS	1	\$	38,530.00	\$	38,530.00	
4.19.1.3.3	Remove existing brick privacy screen at male toilet	LS	1	\$	16,970.00	\$	16,970.00	Removal of footing
4.19.1.3.4	Hydraulic Services : cap off & temporary disconnect for demolition works	LS	1	\$	3,200.00	\$	3,200.00	Not including freezing
4.19.1.4.1	Construct penetration for underground services entry point into Female toilet to connect to new CSR	LS	1	\$	4,210.00	\$	4,210.00	
	Construction (as required)					\$	-	
4.19.1.7.1	Prepare subgrade, blindings & WPM	m2	43		405.00	\$	17,415.00	
4.19.1.7.2	32MPa concrete in slab on ground to internal rooms	m3	7.6	\$	1,600.00	\$	12,160.00	
4.19.1.7.3	Isolation joint	Item	RATE ONL	\$	500.00			
4.19.1.7.4	Dowel joint	Item	RATE ONL	\$	500.00			
4.19.1.7.5	Surface finish	m2	RATE ONL	· ·	350.00			
4.19.1.8.1	Formwork slab edge	m	RATE ONL	\$	120.00	<u> </u>		
4.19.1.9.1 4.19.1.10.2	Reinforcement to slab, SL82 mesh Make good existing (assumed brickwork) external walls where platform level is changed, to match existing walls above	m2 m	43		65.00 150.00	\$ \$	2,795.00 7,350.00	No new brick allowed
4.19.1.10.3	Make good existing internal walls where FFL is changed, to match existing walls above	m	48	\$	249.00	\$	11,952.00	
4.19.1.10.4	Adjust threshold step to door at change in floor level	leaf	3	\$	1,200.00	\$	3,600.00	No stone or tile work allowed for
4.19.1.11.1	Close up existing window, leaving external untouched, fire rate infill on the inside	No.	4	\$	900.00	\$	3,600.00	No brickwork allowed for. Also 60/60/60 fire rated firecheck allowed for
4.19.1.12.1	Face brick screen wall	m2				\$	-	Not allowed for as not noted on drawings provided
4.19.1.12.2	Tooth into existing masonry wall	m				\$	-	Not allowed for as not noted on drawings provided
4.19.1.13.1	Stud frame internal walls	m2				\$	-	

4.19.1.13.2	Stud from a internal vicer walls					Ś		
4.19.1.13.2	Stud frame internal riser walls Stud frame internal false wall	m2 m2	92	\$	160.00	ş Ş	- 14,720.00	
4.19.1.14.1	Wall insulation	m2	92	· ·	30.00	Ś	2,760.00	
4.19.1.14.2	Ceiling insulation - extent tbc	m2	78		30.00	\$	2,340.00	
4.19.1.16.1	Fibre cement wall linings to framed walls	m2				\$	-	Is it included in price
								line below?
4.19.1.16.2	Reline existing internal walls for new finish - allow fibre cement with batten frame or cement render	m2	92	\$	155.00	\$	14,260.00	
4.19.1.16.3	Two hour fire rated wall to inside face of new Waiting room : allow frame, shaft liner or Fyrcheck	m2	64	\$	365.00	\$	23,360.00	
4.19.1.17.1	Two hour fire rated ceiling with cornice/trims	m2	19	\$	350.00	\$	6,650.00	Allowance for 90mm standard cornice fire rated and trims
4.19.1.17.2	Suspended plasterboard ceiling with cornice/trims	m2	17	\$	250.00	\$	4,250.00	Allowance for 90mm standard cornice and trims
4.19.1.18.1	Permanently close existing door	No.	1	\$	250.00	\$	250.00	Allowance to permanently close existing door by keeping original dooi
4.19.1.18.2	Sinlge leaf 2 hour FRL fire doorset complete with hardware	No.	1	\$	2,550.00	\$	2,550.00	
4.19.1.18.3	Single leaf external grade doorset complete with hardware	No.	RATE ONL	\$	1,850.00			
4.19.1.18.4	Extra Over door for translucent glazed panel in door - assume 450 x 600 mm high	No.	RATE ONL	\$	1,175.00			
4.19.1.18.5	Remove door, lower door opening to suit new FFL, reinstall existing doorset complete with hardware	No.				\$	-	Downer to clarifiy as exisitng door will not work with new heights as door opening will be higher due to drop in FFI
4.19.1.18.6	Remove door, lower door opening to suit new FFL, enlarge opening to provide 850mm clear door leaf opening, new single leaf external grade doorset complete with hardware	No.	2	\$	4,555.00	\$	9,110.00	Downer to clarify which doors to be installed. No allownace for heritage or architectual doors
4.19.1.19.3	Privacy film to existing windows	m2	RATE ONL	\$	250.00			
4.19.1.20.1	Waterproofing to wet area floors, upturn 1500mm above floor	m2	55	\$	88.00	\$	4,840.00	UPVC Waterproofing allowed for. No angles or trims allowed
4.19.1.21.1	Wall tiling to wet areas - Glennon Tiles W310 300 x 100mm with epoxy grout	m2	71	\$	350.00	\$	24,850.00	
4.19.1.21.2	Floor tiling to wet areas - Glennon Tiles GN13140 600 x 300mm with epoxy grout	m2	26		380.00	\$	9,880.00	
4.19.1.21.3	Coved skirting tiling to wet areas - Glennon Tiles to match floor tiles with epoxy grout	m	23		350.00	\$	8,050.00	
4.19.1.21.4	Floor tiling to waiting room - Glennon Tiles GN13140 600 x 300mm with epoxy grout	m2	RATE ONL		380.00			
4.19.1.21.5	Skirting tiling to waiting room - Glennon Tiles to match floor tiles with epoxy grout	m	RATE ONL		350.00			
4.19.1.21.6	Threshold tile Floor preparation to existing floor for new vinyl	m m2	3	\$ \$	750.00	\$ \$	2,250.00	Glennon tile allowed for. No stone If there is floor prep,
4.19.1.22.1	flooring	mz	20	γ	35.00	Ş	700.00	where is the vinyl to be laid?
4.19.1.25.1	Hand dryer - Dyson Airblades V Code AB12 white	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.25.2	Toilet Roll Holder - RBA Group B2730 SS grabrails to staff ambulant WC	No.				\$ \$	-	Provisional Item Cost. Item plus 15% Provisional Item Cost.
		No.				-		Item plus 15%
4.19.1.25.4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.25.5	Coat hook - SSS Metlam ML4159	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.25.6	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 350W	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.1	Hand dryer - Dyson Airblades V Code AB12 white	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.2	Toilet Roll Holder - RBA Group B2730	No.				\$	-	Provisional Item Cost. Item plus 15%

				_				
4.19.1.26.3	SS grabrails to FAT WC	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.4	Soap Dispenser - Kimberley Clark Aquarius Hand Cleanser Dispenser White/1 litre 69480	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.5	Baby Change Table - Metlam Foldable - Code ML9100EH	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.6	Coat hook - SSS Metlam ML4159	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.7	Aluminium framed SS mirror, secured to concealed wall hanger with theft resistant mounting equal to Bobrick - 1000H x 600W	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.8	Sanitary bin - Canon Hygeine SS Modesty tray	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.9	Nappy disposal bin - Canon Hygeine nappy disposal bin	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.26.10	Sharps bin (installed at existing toilets at other stations - not scheduled - no allowance)	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.28.1	Fire Extinguisher	No.				\$	-	Provisional Item Cost. Item plus 15%
4.19.1.30.1	Relocate existing acccess ramp cupboard	No.	2	\$	500.00	\$	1,000.00	No allowance to repair cupboard if pre-existing damage done. Also new location to be confirmed by Downer. Allowance for flat surface masonry
4.19.1.33.1	Internal walls linings	m2	110	\$	44.00	\$	4,840.00	This price is for painting as we have already allowed for wall linings above. Allowance for 1 primer, 2 top coats. Paint as per specs
4.19.1.33.2	Internal ceiling linings	m2	40	\$	44.00	\$	1,760.00	This price is for painting as we have already allowed for wall linings above. Allowance for 1 primer, 2 top coats. Paint as per specs
4.19.1.33.3	Single leaf external grade doorset	No.	4	\$	400.00	\$	1,600.00	This price is for painting as we have already allowed for doors above Allowance for 1 primer, 2 top coats. Paint as per specs
4.19.1.33.4	Internal windows	m2	5	\$	120.00	\$	600.00	This price is for painting as we have already allowed for windows above. Allowance for 1 primer, 2 top coats. Paint as per specs
4.19.1.34.1	Wall tiling to wet areas - Glennon Tiles F725 600 x 300mm with epoxy grout	m2	71	\$	60.00	\$	4,260.00	Anti graffiti paint - 1 coat allowed for
4.19.1.34.2	Internal painted wall	m2	RATE ONL	\$	60.00			Anti graffiti paint - 1 coat allowed foi
4.19.1.34.3	Door leaf	No.	3	\$	250.00	\$	750.00	Anti graffiti paint - 1 coat allowed for
4.19.1.35.1	Door signage as required (per door)	No.	7		357.00	\$	2,499.00	
4.20.3.1.1	Sewer - allowance to modify existing in ground sewer to suit new layout	Item	1	\$	23,455.00	\$	23,455.00	No allowance for sewer works outside the vicinity of the new toilets. Any works on platform to be done by others. No allowance to re-direct the fall if not matching to new location
4.20.3.1.2	Water - allowance to modify existing water to suit new layout	Item	1	\$	5,155.00	\$	5,155.00	No allowance for chasing and work outside vicinity of toilets
4.20.3.1.1.1	WC	No.	3	\$	7,000.00	\$	21 000 00	i
4.20.3.1.1.1	WC	140.	5	Ş	7,000.00	>	21,000.00	

4.20.3.1.1.3	Floor waste	No.	:	1\$	500.00	\$ 500.00	Only 1 noted on architectual drawings in FAT
4.20.3.1.1.4	Тар	No.		2\$	· · · · · · ·	2,200.00	
4.23.2.1.2	Mechanical exhaust to ambulant WC	Item		1\$	6,000.00	\$ 6,000.00	As per Addendum 1
4.23.2.1.3	Mechanical exhaust to FAT	Item		1\$	6,000.00	\$ 6,000.00	As per Addendum 1
5.1.2.1	Supply and install a mechanical board	Item		1\$	5,600.00	\$ 5,600.00	Only supply of board and connection to the exhaust from the MSSB once installed by Downer electrician
ADJUSTMENT							
	st any items that are not included in above>					\$ -	
	st any items that are not included in above>					\$ -	
	<list above="" any="" are="" in="" included="" items="" not="" that=""></list>					\$ -	
SCHEDULE O	FRATES						
				_			Exclusions:
							 Hazardous material removal (asbestos, lead etc.) Hi-rail plant Craneage Scaffolding CC/BCA certification Temporary works design/certification Liaising with Sydney Trains/TfNSW Service searching/locating/N DD
							 9. Service relocation (other than shown on drawings) 10. Survey 11. Heritage works 12. Out of hours work
							13. GST
							14. Site

sheds/ablutions/layd own area 15. Waste disposal/skip bins 16. Earthing/bonding

17. Welding 18. Delays/hold ups outside of Maize's control 19. Retention in contract 20. IMSB / All power and electrical except decommissioning / DB investigations / Only works that are stated on the Downer supplied schedule